Career Building

Dundalk Community College

Gaudreau, Inc. — **Architects · Planners · Engineers**

Faisant Associates, Inc. — Structural Engineers

Burdette, Koehler, Murphy & Associates, Inc. — Mechanical/Electrical Engineers

9-27-82

MATERIALS & SYMBOLS

- BRICK
- CMU
- CONCRETE
- EARTH
- GRAVEL
- INSULATION, BATT
- INSULATION, RIGID
- METAL
- PLYWOOD
- SAND/MORTAR
- WOOD, FINISH
- WOOD, CONTINUOUS
- WOOD, INTERRUPTED

- A / 1 — COLUMN LINE
- D1 — DOOR SYMBOL
- 5 — WINDOW TYPE
- C — LOUVER TYPE
- 3 / A8 — SECTION (on Plan)
- 3 / A6 — DETAIL (on Plan)
- 2 / A2 — ELEVATION (on Plan)
- 3 / A1 — DETAIL, SECTION or ELEVATION (Drawn)
- 2 — WALL CONSTRUCTION
- OFFICE 108 — ROOM IDENTIFICATION
- PROPERTY LINE
- 78 — CONTOUR, NEW
- 78 — CONTOUR EXISTING

ABBREVIATIONS

&	AND
∠	ANGLE
@	AT
℄	CENTERLINE
⊏	CHANNEL
Φ	DIAMETER OR ROUND
⊥	PERPENDICULAR
#	POUND OR NUMBER
(e)	EXISTING
□	SQUARE
⌑	SQUARE FEET
ACOUST.	ACOUSTICAL
AC. T.	ACOUSTICAL TILE
A.D.	AREA DRAIN
ADJ.	ADJUSTABLE
AGG.	AGGREGATE
ALT.	ALTERNATE
ALUM.	ALUMINUM
APPROX.	APPROXIMATELY
ARCH.	ARCHITECTURAL
BD.	BOARD
BIT.	BITUMINOUS
BLDG.	BUILDING
BLK.	BLOCK
BLKG.	BLOCKING
B.M.	BENCHMARK
BM.	BEAM
BOT.	BOTTOM
BRK.	BRICK
CAB.	CABINET
C.B.	CATCH BASIN
CBD.	CHALKBOARD
CEM.	CEMENT
CEM. PL.	CEMENT PLASTER
C.T.	CERAMIC TILE
CER.	CERAMIC
C&G	CURB & GUTTER
C.I.	CAST IRON
C.J.	CONTROL JOINT
CLG.	CEILING
CLO.	CLOSET
CLR.	CLEAR
CMU.	CONCRETE MASONRY UNIT
C.O.	CLEAN OUT
COL.	COLUMN
COMB.	COMBINATION
CONC.	CONCRETE
CONF.	CONFERENCE
CONN.	CONNECTION
CONST.	CONSTRUCTION
CONST. JT.	CONSTRUCTION JOINT
CONT.	CONTINUOUS
CONTR.	CONTRACTOR
CORR.	CORRIDOR
CTR.	CENTER
CTSK.	COUNTERSUNK
DBL.	DOUBLE
DEPT.	DEPARTMENT
DET.	DETAIL
D.F.	DRINKING FOUNTAIN
DIA.	DIAMETER
DIM.	DIMENSION
DISP.	DISPENSER
DN.	DOWN
D.P.	DAMPROOFING
DR.	DRAIN
D.T.	DRAIN TILE
DSP.	DRY STANDPIPE
DWG.	DRAWING
E.	EAST
EA.	EACH
E.J.	EXPANSION JOINT
EL.	ELEVATION
ELEC.	ELECTRICAL
ELEV.	ELEVATOR
EMER.	EMERGENCY
ENCL.	ENCLOSURE
E.P.	ELECTRICAL PANEL
EQ.	EQUAL
EQUIP.	EQUIPMENT
EX.	EXISTING
EXP.	EXPOSED
EXT.	EXTERIOR
F.W.	FACE OF WALL
F.A.	FIRE ALARM
F.B.	FLAT BAR
F.D.	FLOOR DRAIN
F.E.	FIRE EXTINGUISHER
F.E.C.	FIRE EXTINGUISHER CABINET
F.H.C.	FIRE HOSE CABINET
F.H.	FIRE HYDRANT
FIN.	FINISH
FL.	FLOOR
F.F.	FINISH FLOOR
FLASH.	FLASHING
F.P.	FIREPROOFING
F.S.	FINISH SLAB
FT.	FEET OR FOOT
FTG.	FOOTING
FOUND.	FOUNDATION
FURR.	FURRING
FUT.	FUTURE
GA.	GAUGE
GALV.	GALVANIZED
G.B.	GRAB BAR
GL.	GLASS
GEN.	GENERAL
GR.	GRADE
G.B.	GYPSUM BOARD
GYP.	GYPSUM
H.B.	HOSE BIBB
H.C.	HOLLOW CORE
HCPD.	HANDICAPPED
HDWD.	HARDWOOD
HDWE.	HARDWARE
HT.	HEIGHT
H.M.	HOLLOW METAL
HOR.	HORIZONTAL
H.P	HIGH POINT
I.D.	INSIDE DIAMETER
INSUL.	INSULATION
INT.	INTERIOR
INV.	INVERT
JAN.	JANITOR
JT.	JOINT
KIT.	KITCHEN
K.O.	KNOCK OUT
LAB.	LABORATORY
LAM.	LAMINATE
LAV.	LAVATORY
L.H.	LEFT HAND
L.P.	LOW POINT
LT.	LIGHT
LVR.	LOUVER
M.	MEN
MACH.	MACHINE
MAG.	MAGNETIC
MAR. T.	MARBLE THRESHOLD
MAS.	MASONRY
MAX.	MAXIMUM
M.C.	MEDICINE CABINET
MECH.	MECHANICAL
MEMB.	MEMBRANE
MET.	METAL
MET. T.	METAL THRESHOLD
MEZZ.	MEZZANINE
MFR.	MANUFACTURER
MH.	MANHOLE
MIN.	MINIMUM
MIR.	MIRROR
MISC.	MISCELLANEOUS
M.O.	MASONRY OPENING
M.P.	METAL PARTITION
M.S	METAL STUD
MTD.	MOUNTED
MUL.	MULLION
N.	NORTH
N.I.C.	NOT IN CONTRACT
NO.	NUMBER
NOM.	NOMINAL
N.T.S.	NOT TO SCALE
O.A.	OVERALL
O.C.	ON CENTER
O.D.	OUTSIDE DIAMETER
OFF.	OFFICE
O.H.	OVERHEAD
OPG.	OPENING
OPP.	OPPOSITE
PL.	PLASTER
℄	PLATE, PROPERTY LINE
P. LAM.	PLASITC LAMINATE
PLWD.	PLYWOOD
PNL.	PANEL
PR.	PAIR
PT.	PAINT, POINT
PTD.	PAINTED
P.T.D.	PAPER TOWEL DISPENSER
PTN.	PARTITION
P.T.R.	PAPER TOWEL RECEPTACLE
Q.T.	Quarry Tile
R.	RISER, RADIUS
R.D.	ROOF DRAIN
REF.	REFERENCE
REFR.	REFRIGERATOR
REINF.	REINFORCED
REQ'D	REQUIRED
REV. C&G	CURB & GUTTER W/ REVERSED SLOPE
RESIL.	RESILIENT
R.H.	RIGHT HAND
RM.	ROOM
R.L.	RAIN LEADER
R.O.	ROUGH OPENING
RDWD.	REDWOOD
R.T.	RESILIENT TILE
S.	SOUTH
S.C.	SOLID CORE
S.D.	STORM DRAIN, SOAP DISPENSER
SCHED.	SCHEDULE
SECT.	SECTION
SHT.	SHEET
SIM.	SIMILAR
S.N.D.	SANITARY NAPKIN DISPENSER
S.N.R.	SANITARY NAPKIN RECEPTACLE
SPEC.	SPECIFICATION
SQ.	SQUARE
SS.	STAINLESS STEEL, SERVICE SINK
STA.	STATION
STD.	STANDARD
STL.	STEEL
STOR.	STORAGE
STRUC.	STRUCTURAL
SUSP.	SUSPENDED
SYM.	SYMMETRICAL
T.	TOILET
T.B.	TOWEL BAR
TBD.	TACKBOARD
T.C.	TOP OF CURB
TEL.	TELEPHONE
TEMP.	TEMPORARY
TER.	TERRAZZO
T&G	TONGUE & GROOVE
THK.	THICK
T.P.	TOP OF PAVEMENT
T.P.D.	TOILET PAPER DISPENSER
T.W.	TOP OF WALL
T.S.	TOP OF STEEL
TYP.	TYPICAL
UNF.	UNFINISHED
U.C.	UNDERCUT
U.O.N.	UNLESS OTHERWISE NOTED
V.	VINYL
V.T.	VINYL TILE
V.A.T.	VINYL ASBESTOS TILE
V.B.	VINYL BASE
V.C.	VINYL COVERED
VERT.	VERTICAL
VEST.	VESTIBULE
V.W.C.	VINYL WALL COVERING
W.	WOMEN, WEST
W/	WITH
W.C.	WATER CLOSET
WD.	WOOD
W/O	WITHOUT
WP.	WATERPROOF
WDW.	WINDOW
WK. PT.	WORKING POINT
WT.	WEIGHT

INDEX OF DRAWINGS

SITE

C-1 GRADING PLAN
C-2 LAYOUT & UTILITY PLAN
C-3 SEDIMENT & EROSION CONTROL PLAN

ARCHITECTURAL

A-1 GROUND LEVEL PLAN
A-2 SECOND LEVEL PLAN
A-3 ROOF PLAN & DETAILS
A-4 BUILDING ELEVATIONS & DETAILS
A-5 BUILDING SECTIONS
A-6 WALL SECTIONS
A-7 WALL SECTIONS/DETAILS
A-8 STAIRS
A-9 PARTIAL PLANS/DETAILS
A-10 WINDOW & DOOR SCHEDULES
A-11 PARTITIONS/DETAILS
A-109R REVISIONS TO THE GROUND FLOOR PLAN
A-110R REVISIONS TO THE SECOND FLOOR PLAN

STRUCTURAL

S-1 FOUNDATION PLAN
S-2 SECOND FLOOR & LOW ROOF FRAMING PLAN
S-3 HIGH ROOF FRAMING PLAN
S-4 DETAILS
S-5 DETAILS & SCHEDULE

MECHANICAL/ELECTRICAL

M-1 GROUND LEVEL PLAN H.V.A.C.
M-2 SECOND LEVEL PLAN H.V.A.C.
M-3 GROUND LEVEL PLAN PLUMBING
M-4 SECOND LEVEL PLAN PLUMBING
M-5 SECTIONS & SANITARY RISER DIAGRAM
M-6 SCHEDULES & A.T.C. DIAGRAMS
M-7 DETAILS
M-8 DUCT SECTIONS
E-1 SITE PLAN & DETAILS
E-2 GROUND LEVEL PLAN LIGHT & POWER
E-3 SECOND LEVEL PLAN LIGHT & POWER
E-4 DETAILS & RISER DIAGRAMS
E-5 LEGENDS, SCHEDULES & ABBREVIATIONS
ME-105 REVISIONS TO THE GROUND FLOOR PLAN [AHU + DUCTS]
ME-106 " " " SECOND " " [DUCTS]
ME-107 " " " GROUND " " [LIGHTING]
ME-108 " " " SECOND " " [LIGHTING]

D-012000 G-8217