

Estimate of the cost of the Eastern Shore Rail Road, 118 miles 377 yards long, from a point in the Wilmington and Susquehanna Rail Road, near Elkton, to Tangier Sound, and of a line of steam boats thence; 85 miles to Portsmouth, in Virginia.

FOR THE ROAD.

1st Division 19 miles 1474 yards.

97,238 cubic yds. of excavation,	\$10,716 80	
Clearing and grubbing,	2,815 00	
Bridges and culverts,	14,292 00	
Superstructure of road,	76,798 65	
	<hr/>	104,622 45

2d Division, 9 miles 1230 yards.

103,387 cubic yds. of excavation and embankment,	19,474 00	
Grubbing and clearing,	2,154 00	
Bridges and culverts,	16,096 00	
Superstructure of road,	37,636 59	
	<hr/>	75,360 59

3d Division, 14 miles 330 yards.

79,374 cubic yards excavation and embankment,	13,520 52	
Clearing and grubbing,	2,030 00	
Bridges and culverts,	11,054 00	
Superstructure,	55,047 50	
	<hr/>	81,652 02

4th Division, 13 miles 1220 yards.

86,074 cubic yards excavation and embankment,	10,604 55	
Clearing and grubbing,	1,130 00	
Bridges and culverts,	300 00	
Superstructure,	52,729 24	
	<hr/>	64,763 79