CE 272-07 Carpenters Point Wastewater Consistency Report System

51839-6523

St toloils

Martin O'Malley
Governor

Anthony G. Brown Lt. Governor



Margaret G. McHale Chair

Ren Serey
Executive Director

STATE OF MARYLAND CRITICAL AREA COMMISSION CHESAPEAKE AND ATLANTIC COASTAL BAYS

1804 West Street, Suite 100, Annapolis, Maryland 21401 (410) 260-3460 Fax: (410) 974-5338 www.dnr.state.md.us/criticalarea/

July 14, 2009

Mr. Anthony DiGiacomo, AICP Cecil County Government Office of Planning and Zoning County Administration Building 200 Chesapeake Boulevard, Suite 2300 Elkton, MD 21921

Re: Carpenter's Point Wastewater Collection

Dear Mr. DiGiacomo:

We are in receipt of proposed plans and the planting plan for Phase III of the Carpenter's Point Wastewater Collection System. The project is located within a Limited Development Area (LDA) and is 4.4 acres in size.

Based on our review of the project, we have determined that the project may be found generally consistent with the Cecil County Critical Area Program for the reasons outlined below:

- 1. Total existing lot coverage is 0.05 acres (1.1%); upon completion of this project, total lot coverage will be 0.12 acres (2.7%).
- 2. There is no disturbance to the 110-foot or expanded Buffer.
- 3. No tidal or non-tidal wetland impacts will occur.
- 4. There are no impacts to Habitat Protection Areas.

Please submit a signed and completed consistency report sheet to this office as required by COMAR 27.02.02 - State and Local Agency Actions Resulting in Development of Local Significance on Private Lands or Lands Owned by Local Jurisdictions. To make a final consistency determination, please address the following comment:

• Since 41,894 square feet (21.8%) of clearing is proposed on the site, mitigation at a 1.5:1 ratio is required (62,841 square feet). Currently, only 1:1 mitigation is proposed. Mitigation in the form of tree plantings would be acceptable and should consist of a mix of native trees and shrubs Furthermore, a site plan showing the location and species of mitigation is required along with the submitted planting plan.

Finally, prior to the start of construction, please submit copies of the sediment and erosion control permit, as well as the stormwater management permit, for this project. It is our understanding that a stormwater management waiver has been received for the project.

Thank you again for your cooperation and assistance with reviewing this project. If you have any questions, please call me at (410) 260-3483.

Sincerely,

Mick Hells Nick Kelly

Natural Resource Planner

cc: Roger Greve, GMB

CE 272-07



STATE OF MARYLAND CRITICAL AREA COMMISSION CHESAPEAKE AND ATLANTIC COASTAL BAYS

1804 West Street, Suite 100, Annapolis, Maryland 21401 (410) 260-3460 Fax: (410) 974-5338 www.dnr.state.md.us/criticalarea/

May 21, 2007

Mr. W. Scott Flanigan, Director Cecil County Department of Public Works 129 E. Main Street Elkton, Maryland 21921

Re: Carpenters Point Wastewater Collection System, Phase 2
Chesapeake Bay Critical Area Consistency Report

Dear Mr. Flanigan:

This office has received the Consistency Report Form for the above-referenced project to this office per the requirements of COMAR 27.02.02 - State and Local Agency Actions Resulting in Development of Local Significance on Private Lands or Lands Owned by Local Jurisdictions. After reviewing the Consistency Determination Form reviewed and signed by the Planning and Zoning Office, and the accompanying site plan, this office agrees that the project is consistent with the Cecil County Critical Area Program. Although approximately 900 feet of the project is located within the 110-foot Buffer, these impacts are permitted for utilities in Limited Development Areas.

In addition, the project will result in the following:

- The installation of the sewer lines will be temporary and construction should be completed within one working day.
- Any requested staging areas will not be located within the 110-foot Buffer and will not necessitate the need for clearing of natural vegetation or trees.
- No additional impervious surfaces will be created.
- No trees or natural vegetation will be removed for construction.
- No other Habitat Protection Areas will be impacted by the construction activities.
- The County will provide mitigation of native Buffer plantings for the 900 square feet of impact to the 110-foot Buffer at a 3:1 ratio resulting in a total of 2,700 square feet.

Mr. Flanigan May 21, 2007 Page Two

Since the project is consistent with the local program, it will not require formal approval by the Chesapeake Bay Critical Area Commission, notwithstanding any other required resource agency approvals. Please forward the mitigation location and plantings plan within 60 days.

Thank you again for your cooperation and assistance with reviewing this project. If you have any questions, please telephone me at (410) 260-3478.

Sincerely,

Lisa A. Hoerger, Chief

Project Evaluation Division

cc: Mr. Eric Sennstrom, Planning & Zoning

Lun a.7 Course

Mr. Stephen Udzinski, Public Works

Ms. Kate Schmidt, Critical Area Commission

CE 272-07



STATE OF MARYLAND CRITICAL AREA COMMISSION CHESAPEAKE AND ATLANTIC COASTAL BAYS

1804 West Street, Suite 100, Annapolis, Maryland 21401 (410) 260-3460 Fax: (410) 974-5338 www.dnr.state.md.us/criticalarea/

May 10, 2007

Mr. W. Scott Flanigan, Director Cecil County Department of Public Works 129 E. Main Street Elkton, MD 21921

Re: Carpenter's Point Wastewater Collection System Phase II

Dear Mr. Flanigan:

The above referenced project has been forwarded to our office per the requirements of COMAR 27.02.02 - State and Local Agency Actions Resulting in Development of Local Significance on Private Lands or Lands Owned by Local Jurisdictions. It appears Cecil County is proposing to extend sewer lines to several new areas along Carpenters Point. Based on the information provided, we have determined that the project may be found generally consistent with the Cecil County Critical Area Program for the reasons outlined below.

- 1. The areas of work within the Critical Area will occur only with the Limited Development Area (LDA).
- 2. Approximately 75-feet of line, located on Sheet C-3 between manholes 603-2 and 603-3 is within the 110-foot Buffer. However, COMAR 27.01.02.04.B allows for roads, bridges, and utilities that must cross a Habitat Protection Area provided they are located to minimize negative impacts and provide maximum erosion protection.

Given the items outlined above, this office believes you may submit the included Consistency Report Form for Local Government Projects in conjunction with the necessary mitigation for the proposed work within the 110-foot Buffer. Given the area of disturbance is approximately 900 square feet, mitigation of 3:1, or 2,700 square feet, would be required. The Consistency Report Form includes space to describe how the mitigation is to be achieved. Mitigation in the form of tree plantings would be acceptable and should consist of a mix of native trees and shrubs. Typically, at least 900 square feet of the mitigation would be provided within the 110-foot Buffer.

Mr. W. Scott Flanigan May 10, 2007 Page 2 of 2

If you have any questions or would like further assistance please feel free to contact me at (410) 260-3475.

Sincerely,

Kate Schmidt

Natural Resources Planner

CE 272-07

Cc: Mr. Eric Sennstrom, Planning & Zoning

Mr. Brice Foxwell, GMB


Consistency Report for Local Government Projects


Project Name: Carpenters Point	Jurisdiction: Cecil County					
Project Description: Carpenters Point Phase 2 - Inst	all new wastewater collection system					
Local Agency proposing project: Cecil Cour	nty Department of Public Works					
Contact Name and Phone Number: Steph						
Project Location (include street address, tax	map and parcel number):					
Carpenters Point - Area highlighted	on attacked tax map					
Critical Area acreage and designation: LDA						
Project	et Data					
Existing forest/woodland/trees:0	% of site:					


Pro	oject Data
Existing forest/woodland/trees:0	% of site:
Proposed clearing: 0	% of existing forest:
Mitigation to be provided: Ø 2,700 SF	
Planting location & species (also show on The mitigation will be tree planting	n site plan): Site to be determined by July is with a mix of native trees and shrubs
Existing impervious surface:	% of site:
Proposed new impervious:0	
Total impervious surface:	% of site:
If the % of impervious cover exceeds the perr need a Conditional Approval from the Critical Commission planner for assistance.	mitted amount in the LDA or RCA, the project may Area Commission. Please contact your
Total Area Disturbed: 89,000 SF	
Stormwater Management: (If site is in the	e IDA, the 10% worksheets must be attached.
Otherwise, local stormwater requirement This project is granted a Variance because it is a linear utility p	s must be addressed.) Stormwater management regulation reject with no added impervious area
Yes	WM and sediment and erosion control plans?
Buffer impacts? 900 SF	Is project water dependent? No
a Conditional Approval from the Critical Area planner for assistance.	project is not water dependent, the project may need Commission. Please contact your Commission
Other Habitat Protection Areas:	
Colonial Nesting Waterbird site? Yes ☐ No X	Waterfowl Staging Area? Yes ☐ No X
Endangered / threatened species? Yes □ No X	Forest Interior Dwelling Bird Habitat? Yes ☐ No X
Anadromous Fish Propagation Waters? Yes □	No X
Non-tidal Wetland Impacts? Yes ☐ No	X If yes, MDE permit #:
Tidal Wetland Impacts? Yes □ No X	If yes, MDE permit #:
In accordance with COMAR 27.02.02,	we hereby certify that this local agency


project is consistent with the requirements of the local Critical Area Program.


Please sign above, attach the site plan to this report and submit to the Critical Area Commission at 1804 West St., Suite 100, Annapolis, MD 21401











UTILITY NOTES

- A) CONTRACTOR SHOULD OPEN ONLY THAT SECTION OF TRENCH THAT CAN BE BACKFILLED AND STABILIZED EACH DAY. IF TRENCH MUST REMAIN OPEN LONGER THAN ONE DAY, SILT FENCE SHALL BE PLACED BELOW (DOWNSLOPE) THE TRENCH.
- B) PLACE ALL EXCAVATED MATERIAL ON UPHILL SIDE OF TRENCH.
- C) ANY SEDIMENT CONTROLS DISTURBED BY UTILITY CONSTRUCTION ARE TO BE REPAIRED IMMEDIATELY.
- D) CONTRACTOR TO PROVIDE ALL TEMPORARY MEASURES NECESSARY FOR ACCESS TO ALL PRIVATE LOTS THROUGHOUT CONSTRUCTION.

DRAWING NOTES

1. CONTRACTOR SHALL EXERCISE EXTREME CAUTION WHEN WORKING IN THE VICINITY OF EXISTING PRIVATE STRUCTURES AND/OR FEATURES LOCATED EITHER WITHIN OR OUTSIDE OF THE EASEMENT. CONTRACTOR WILL BE RESPONSIBLE FOR COMPLETE RESTORATION OF ALL DAMAGED PRIVATE STRUCTURES AND/OR FEATURES AT NO ADDITIONAL COST TO THE OWNER.

COLLECTION SYSTEM PLAN NO. 4 SCALE: 1" = 40'

OILS

KeB2 KEYPORT LOAM, 2 TO 5 PERCENT SLOPES, MODERATELY ERODED

KpC2 KEYPORT LOAM, 5 TO 10 PERCENT SLOPES, MODERATELY ERODED

SaB2 SASSAFRAS SANDY LOAM, 2 TO 5 PERCENT SLOPES, MODERATELY ERODED

NO.	DATE	REVISIONS	
-			

CARPENTERS POINT WASTEWATER COLLECTION SYSTEM PHASE III

CECIL COUNTY, MARYLAND
BID NO. 10-30-55002

GEORGE, MILES & BUHR, LLC

ARCHITECTS & ENGINEERS

SALISBURY · BALTIMORE · LEWES · SEAFORD · YORK


www.gmbnet.com

COLLECTION SYSTEM EROSION AND SEDIMENT CONTROL PLAN NO. 4

DESIGN	WBF	SHEET NO.
DRAWN	BNA	
CHECKED	RAG/WBF	ES-7
JOB	080231	

DRAWING 7 OF 11


DATE JULY, 2009 DRAWING
© COPYRIGHT 2009 GEORGE. MILES & BUHR, LLC





G:\I3II9\SURVEY\RPLATS\I3II9_Keysheet.pro


SHEET I OF 2


SCALE: 1" = 2000"














6:\I3II9\SURVEY\RPLATS\I3II9 Keusheet 2.oro



6:\I3II9\SURVEY\RPLATS\I3II9 plat2.pro





FOREST PROTECTION PROCEDURES AND SEQUENCE

- CLEARING AND GRUBBING OF FOREST AREAS SHOWN ON THIS PLAN WILL BE COMPLETED AS PART OF A PHASED MASS GRADING PLAN. THERE WILL BE NO CLEARING IN FOREST PROTECTION AREAS SHOWN ON THIS PLAN. FOREST TO REMAIN SHALL HAVE BLAZE ORANGE MESH TREE PROTECTION FENCE (DETAIL #5 THIS SHEET) INSTALLED TO THE EDGE OF THE CRITICAL ROOT ZONE (CRZ). ADJUSTMENTS TO THIS FENCE WILL BE PERMITTED ONLY FOR FINAL PLACEMENT OF LIGHT WEIGHT SOIL MIX OR ROOT PRUNING (DETAIL #3 THIS SHEET) IMMEDIATELY PRIOR TO DOING THE WORK. PRIOR TO INSTALLATION OF PERIMETER SEDIMENT CONTROL MEASURES, THE LIMIT OF CLEARING AS SHOWN ON THE F.C.P. SHALL BE FLAGGED AND FOREST RETENTION SIGNS (DETAIL #1 THIS SHEET) POSTED EVERY 50 FEET. SEDIMENT CONTROL DEVICES SHALL REMAIN OUTSIDE OF PROTECTED FOREST AREAS.
- STOCKPILE AREAS, EMPLOYEE PARKING AND EQUIPMENT STAGING AREAS SHALL BE CONTAINED WITHIN THE LIMIT OF CLEARING AS SHOWN ON THE F.C.P. OR SEDIMENT & EROSION CONTROL
- 4. FILTER CLOTH ON WIRE MESH (DETAIL #6 THIS SHEET) SHALL BE INSTALLED IN LIEU OF STANDARD SILT FENCE OR HIGH VISIBILITY FLAGGING SHALL BE PLACED ON SUPER SILT FENCE WHERE APPLICABLE ON THE SEDIMENT & EROSION CONTROL PLAN. EARTH DIKES AND SWALES SHALL BE INSTALLED OUTSIDE OF THE FOREST AREAS PROTECTED BY BLAZE ORANGE FENCE.
- TREES OVER 18" DBH REQUIRING EXCAVATION WITHIN THE CRITICAL ROOT ZONE SHALL HAVE ROOTS PRUNED (DETAIL #3 THIS SHEET) AND CROWN REDUCED (DETAIL #2 THIS SHEET) PROPORTIONAL TO THE PERCENTAGE OF ROOT SYSTEM REMOVED TO MAXIMUM OF 20%. A 2" PROTECTIVE MULCH LAYER SHALL BE SPREAD 5 FOOT BEYOND THE ROOT PRUNING LINE, IMMEDIATELY FOLLOWING REMOVAL OF PROTECTIVE FENCING AT THE END OF FINAL GRADING AND STABILIZATION. SPRING AND FALL LOW NITROGEN FERTILIZERS (10-25-15) SHALL BE APPLIED BY MEANS OF
- LIQUID PRESSURE INJECTIONS (DETAIL #4 THIS SHEET) TO THE ROOT ZONE OF TREES OVER 18" DBH THAT WERE AFFECTED BY CONSTRUCTION WITHIN THE CRZ. EACH GROUP OF TREES MUST ALSO BE MONITORED FOR DISEASE AND INSECT PROBLEMS DURING
- EXOTIC TREE AND SHRUB SPECIES SHALL BE ERADICATED BY CUTTING AND/OR SPRAYING WITH AN APPROVED HERBICIDE [I.E. GLYPHOSATE, (ROUNDUP , RODEO)] BY A STATE CERTIFIED PESTICIDE APPLICATOR, 2 APPLICATIONS/YEAR FOR 2 YEARS MAY BE NECESSARY.

FOREST RETENTION PROTECTION PROCEDURES

AND AFTER CONSTRUCTION, FOR A PERIOD OF TWO YEARS.

- PROTECTION DEVICES A. ALL RETENTION AREAS AND ISOLATED SPECIMEN TREES SHALL BE PROTECTED BY HIGHLY VISIBLE, WELL ANCHORED TEMPORARY PROTECTION DEVICES.
- B. ALL PROTECTION DEVICES SHALL BE IN PLACE PRIOR TO ANY GRADING OR LAND CLEARING.
 THE COUNTY PLANNING OFFICE MUST BE CONTACTED FOR INSPECTION AND APPROVAL OF THE
 INITIAL CLEARING. C. ALL PROTECTION DEVICES SHALL REMAIN IN PLACE UNTIL ALL CONSTRUCTION IS COMPLETED IN THE IMMEDIATE VICINTIY.
- D. ALL PROTECTION DEVICES SHALL BE MAINTAINED THROUGHOUT CONSTRUCTION. E. ATTACHMENT OF SIGNS, OR ANY OTHER OBJECTS TO TREES IS PROHIBITED. F. NO EQUIPMENT, MACHINERY, VEHICLES, MATERIALS, OR EXCESSIVE PEDESTRIAN TRAFFIC SHALL BE ALLONED WITHIN PROTECTED AREAS.
- PRE-CONSTRUCTION MEETING
 AFTER THE BOUNDARIES OF THE FOREST RETENTION AREA HAVE BEEN STAKED AND FLAGGED
 AND BEFORE ANY DISTURBANCE HAS TAKEN PLACE ON SITE, A PRE-CONSTRUCTION MEETING AT
 THE CONSTRUCTION SITE SHALL TAKE PLACE. THE DEVELOPER, CONTRACTOR OR PROJECT MANAGER,
 AND APPROPRIATE LOCAL INSPECTORS SHALL ATTEND.
- ON-SITE DECISIONS
 ANY CHANGES MADE TO THE FOREST CONSERVATION PLAN DUE TO ON-SITE CONDITIONS SHALL BE MADE
 IN CONSULTATION WITH A QUALIFIED INDIVIDUAL AND APPROVED BY CECIL COUNTY PLANNING DEPARTMENT
 AND SHALL REQUIRE UPDATING OF THE F.C.P.
- POST-CONSTRUCTION PHASE THE FOLLOWING MEASURES SHALL BE TAKEN WHEN APPROPRIATE: A. CORRECTIVE MEASURES IF DAMAGES WERE INCURRED.


 * REMOVAL OF DEAD OR DYING TREES: THIS MAY BE DONE ONLY IF TREES POSE AN IMMEDIATE SAFETY HAZARD. B. REMOVAL OF TEMPORARY STRUCTURES: THE FOLLOWING MINIMUM STANDARDS SHALL BE OBSERVED DURING THE REMOVAL OF TEMPORARY STRUCTURES:

 * NO BURIAL OF DISCARDED MATERIALS WILL OCCUR ON-SITE WITHIN THE CONSERVATION AREA.

 * NO OPEN BURNING WITHIN 100 FEET OF A WOODED AREA.


 * ALL TEMPORARY FOREST PROTECTION STRUCTURES WILL BE REMOVED AFTER CONSTRUCTION.

 * THE "FOREST RETENTION AREA" SIGNAGE IS TO REMAIN AFTER CONSTRUCTION IS COMPLETED.




1. Bottom of signs to be higher than top of tree protection fence.
 2. Signs to be placed approximately 50' feet apart. Conditions on site affecting visibility may warrant placing signs closer or farther apart.
 3. Attachment of signs to trees is prohibited.

Source: Adapted from Forest Conservation Manual, 1991




Remove branch weight by undercutting at A and remove timb by cutting through at B. Remove stub at CD (line between branch bark ridge and outer edge of branch collar). If D is difficult to find on hardwoods, drop vertical from C (line CX). Angle XCY=XCD.

Crown Reduction





1. Only prune at specified times 2. No more than 30% of crown to be removed at one time.





1. Retention Areas to be established as part of the forest conservation plan review process.
2. Boundaries of Retention Areas to be staked, flagged and/or fenced prior to trenching.
3. Exact location of trench should be identified.
4. Trench should be immediately backfilled with soil removed or organic soil.
5. Roots should be cleanly cut using vibratory knife or other acceptable equipment.

Source: Adapted from Steve Clark & Associates/ACRT, Inc. and Forest Conservation Manual, 1991









2 'SORANGE STREAMERS

6' STEEL "T-BAR" STAKE AT ROOT ZONE OF TREES DRIVEN INTO GROUND OR YELLOW PINE POST IN



REFORESTATION SUMMARY


SUMMARY FOREST RETENTION AREA IN AREA DESIGNATION ACRES 49.33 AC. TOTAL 49.33 AC.

FOREST RETENTION

REFORESTATION AREA IN AREA DESIGNATION ACRES 0.07 AC. 0.08 AC. R-3 0.08 AC. 0.56 AC. 0.08 AC. 1.74 AC. 4.08 AC. 0.53 AC. R-9 O.II AC.

O.II AC.

7.44 AC.



NOT TO SCALE

							1" CA	ALIPER	R STO	CK RE	FORE	STATIC	DN				
		REFORESTATION AREA															
		R-I	R-2	R-3	R-4	R-5	R-6	R-7	R-8	R-9	R-10	TOTAL	BOTANICAL NAME	COMMON NAME	SIZE	SERIALSTAGE	SPACING
ACRES		0.07	0.08	0.08	0.56	0.08	1,74	4.08	0.53	0.11	0.11	7.44					
	AR	3	2	2	20	2	58	136	17	4	4	248	ACER RUBRUM	RED MAPLE	4 GAL. CONT. (66"-72")	PIONEER/SUBCLIMAX	16'± O.C.
	QA	3	2	2	20	2	58	136	17	4	4	248	QUERCUS ALBA	WHITE OAK	4 GAL. CONT. (66"-72")	SUBCLIMAX	16'± O.C.
	10	2	3	3	19	3	58	136	18	3	4	249	ILEX OPACA	AMERICAN HOLLY	4 GAL. CONT. (66"-72")	CLIMAX	16'± O.C.
QUANTITY	FG	2	3	3	19	3	58	136	18	3	4	249	FAGUS GRANDIFOLIA	AMERICAN BEECH	4 GAL. CONT. (66"-72")	CLIMAX	16'± O.C.
(200/AC)	QR	2	3	3	19	3	58	136	18	4	3	249	QUERCUS RUBRA	RED OAK	4 GAL. CONT. (66"-72")	SUBCLIMAX/CLIMAX	16'± O.C.
	LS	2	3	3	19	3	58	136	18	4	3	249	LIQUIDAMBAR STYRACIFLUA	SWEETGUM	4 GAL. CONT. (66"-72")	PIONEER/SUBCLIMAX	16'± O.C.
SUE	STOTAL	14	16	16	II2	16	348	816	106	22	22	1488					

FOREST CLEARING

SUMMARY

ACRES

0.31 AC.

0.34 AC.

0.03 AC.

0.12 AC.

0.05 AC.

0.01 AC.

1.46 AC.

FOREST CLEARING AREA DESIGNATION

CL-2


CL-3

CL-4

CL-5

CL-6

TOTAL



1. Blaze orange or blue plastic mesh fence for forest protection device, only. . Boundaries of Retention Area will be established as part of the forest conservation plan review process.

3. Boundaries of Retention Area should be staked and flagged prior to installing device.

4. Avoid damage to critical root zone. Do not damage or sever large roots when installing posts.
5. Protection signs are required.
6. Device should be maintained throughout construction.

Source: Adapted from Prince George's County, Maryland: Woodland Conservation Manual and Forest Conservation Manual, 1991

2. Wire, snow fence, etc. for tree protection only.

3. Boundaries of Retention Area will be established as part of the forest conservation plan review

process.

4. Boundaries of Retention Area should be staked and flagged prior to installing device.

5. Avoid root damage when placing anchor posts.

6. Device should be properly maintained throughout construction.


7. Protection signs are also required.

8. Locate fence outside the Critical Root Zone.

1. Silt fence to be heeled into the soll.

Source: Adapted from Steve Clark & Associates/ACRT, Inc.


3445-A BOX HILL CORPORATE CENTER DRIVE ABINGDON, MARYLAND 21009 (410) 515-9000 FAX (410) 515-9002




FINAL ENVIRONMENTAL ASSESSMENT/ HABITAT PROTECTION PLAN/ **BUFFER MANAGEMENT PLAN**

DATE | REVISIONS JOB NO: 13119 SCALE: | 1" = 100 DATE: 08/8/08 DRAWN BY: KCP DESIGN BY: KCP

REVIEW BY: JMK SHEET: 2 OF 2





REVIEW BY: JMK SHEET: 1 OF 1