

**MARYLAND HISTORICAL TRUST
DETERMINATION OF ELIGIBILITY FORM**

NR Eligible: yes
no

Property Name: Wilson Farmhouse Inventory Number: AA-913

Address: 862 Galesville Road City: Galesville Zip Code: 20765

County: Anne Arundel USGS Topographic Map: Deale

Owner: Estate of Mary Wilson Is the property being evaluated a district? yes

Tax Parcel Number: 572 Tax Map Number: 69 Tax Account ID Number: 09244000

Project: Moreland Property (910-002-030B) Agency: FCC

Site visit by MHT Staff: no yes Name: _____ Date: _____

Is the property located within a historic district? yes no

If the property is within a district

District Inventory Number: _____

NR-listed district yes Eligible district yes District Name: _____

Preparer's Recommendation: Contributing resource yes no Non-contributing but eligible in another context

If the property is not within a district (or the property is a district)

Preparer's Recommendation: Eligible yes no

Criteria: A B C D Considerations: A B C D E F G None

Documentation on the property/district is presented in:

Description of Property and Eligibility Determination: *(Use continuation sheet if necessary and attach map and photo)*

This two-and-a-half-story, three-bay wood-framed structure is set back approximately 150 feet from Galesville Road. It is located almost one-third of a mile southeast of the intersection of Muddy Creek Road and Galesville Road. The house is clad with asbestos siding, and the cross-gabled roof is sheathed with asphalt shingles. The foundation was snow-covered, and thus not visible. The most prominent feature of the symmetrical southwest façade is the central front-wall gable pierced by a diamond-shaped window. There are, additionally, two interior brick chimneys symmetrically flanking the center gable. There is a gable-roofed addition on the north end of the rear elevation. The site is overgrown, and the house is in a much-deteriorated condition. All of the windows and doors are missing, as are some roof shingles. Clearly visible through the windows is the decaying interior. Floors, ceilings, and walls have each collapsed in places, and plaster litters the remaining floor. Almost 300 feet to the north of the house is what appears to be a ball-field. There is a wooden grandstand at the corner of the square area, and two concrete-block dugouts. There is an additional wooden building to the east of the grandstand. All of these structures are in varying states of disrepair.

Either Henry Wilson or his son Richard built the farmhouse some time in the last quarter of the nineteenth century.¹ Henry Wilson was the first, and largest, African-American property owner in the Galesville region. He bought two acres of land in 1865, and supplemented that with an adjacent twenty-five-and-a-half acres in 1871. This is the land upon which the farmhouse was built. Henry Wilson had died by 1878, when a map identified his widow, Kitty, as the property owner. The 1900 Census identifies Richard Wilson as the head-of-household. Upon Richard Wilson's death, the property passed to his

MARYLAND HISTORICAL TRUST REVIEW

Eligibility recommended Eligibility not recommended

Criteria: A B C D Considerations: A B C D E F G None

Comments: _____

[Signature] ✓
Reviewer, Office of Preservation Services

4/10/03

Date

[Signature]
Reviewer, NR Program

4/9/03

Date

MARYLAND HISTORICAL TRUST
NR-ELIBILITY REVIEW FORM

Continuation Sheet No. 1

AA-913


wife Mary, whose estate still owns the property. Richard and Mary Wilson's daughter Mary Louise Crowner occupied the house until 1970. She was the last person to live there.

The Wilson Farmhouse, located at 862 Galesville Road, does not meet National Register Criteria A, B, or C. The dwelling does have an historical association with Henry Wilson, a prominent local African-American landowner. However, due to its deteriorated condition, the integrity of the historic materials and workmanship have been severely compromised. Criterion D, information potential, was not evaluated for this study.

Prepared by: Laura H. Hughes, Andrea F. Schoenfeld, and Gerald M. Maready, Jr., Date Prepared: February 25, 2003
Architectural Historians

¹ The historical information used for this Determination of Eligibility is taken from a Maryland Historical Trust (MHT) State Historic Sites Inventory Form for this property. Susan R. Wetherill, a volunteer, completed the inventory form in 1985 on behalf of MHT.

Resource Sketch Map




I.D. # AA913

Name

Wilson Farmhouse
862 Galesville Rd.

Galesville
Anne Arundel County

AA-913
Wilson Farmhouse
Galesville
Anne Arundel County
Deale, MD USGS Map



P. 52

P 572

521

GALESVILLE

P. 354

P 527

468

530

531

P. 532

P. 350

420

P. 519

P. 351


P. 426

P. 376

2 3

1

AA-913
Wilson Farmhouse
Galesville
Anne Arundel County
Deale, MD USGS Map





AA-913

Wilson Farm

812 Gallopville Road

Anne Arundel County, Maryland

ERT TRACES

2/2003

MD SHPO

cutting east towards house from tower site

1 of 4





AA-913

Wilson Farmhouse

662 Gatesville Road

Anne Arundel County, Maryland

Exit 100

100

SHPO

Northwest corner

100



AA-913

Wilson Farmhouse

862 Galesville road

Fine Annsel County Maryland

ETH Trace 105

of 2003

MD SHTPO

Home southwest of point

2 of 4

Maryland Historical Trust State Historic Sites Inventory Form

Magi No.

DOE yes no

1. Name (indicate preferred name)

historic THE WILSON FARMHOUSE

and/or common

2. Location

street & number 862 Galesville Road not for publicationcity, town Galesville vicinity of congressional district

state Maryland county Anne Arundel

3. Classification

Category	Ownership	Status	Present Use	
<input type="checkbox"/> district	<input type="checkbox"/> public	<input type="checkbox"/> occupied	<input type="checkbox"/> agriculture	<input type="checkbox"/> museum
<input type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input checked="" type="checkbox"/> unoccupied	<input type="checkbox"/> commercial	<input type="checkbox"/> park
<input checked="" type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> work in progress	<input type="checkbox"/> educational	<input type="checkbox"/> private residence
<input type="checkbox"/> site	Public Acquisition	Accessible	<input type="checkbox"/> entertainment	<input type="checkbox"/> religious
<input type="checkbox"/> object	<input type="checkbox"/> in process	<input checked="" type="checkbox"/> yes: restricted	<input type="checkbox"/> government	<input type="checkbox"/> scientific
	<input type="checkbox"/> being considered	<input type="checkbox"/> yes: unrestricted	<input type="checkbox"/> industrial	<input type="checkbox"/> transportation
	<input checked="" type="checkbox"/> not applicable	<input type="checkbox"/> no	<input type="checkbox"/> military	<input type="checkbox"/> other:

4. Owner of Property (give names and mailing addresses of all owners)

name Estate of Mary Wilson

street & number c/o Calvin Snowden, 1330 Kennedy St., N.W., telephone no.:

city, town Washington state and zip code D.C. 20011

5. Location of Legal Description

courthouse, registry of deeds, etc. Anne Arundel County Registry of Deeds liber NHG 13

street & number folio 390; also:

city, town Annapolis, Maryland 41401 liber SH 6

state folio 154

6. Representation in Existing Historical Surveys

title Maryland Historic Sites Inventory

date federal state county local

depository for survey records Maryland Historical Trust

city, town Annapolis state MD

7. Description

Survey No. AA-913

Condition		Check one	Check one	
<input type="checkbox"/> excellent	<input checked="" type="checkbox"/> deteriorated	<input type="checkbox"/> unaltered	<input checked="" type="checkbox"/> original site	
<input type="checkbox"/> good	<input type="checkbox"/> ruins	<input checked="" type="checkbox"/> altered	<input type="checkbox"/> moved	date of move _____
<input type="checkbox"/> fair	<input type="checkbox"/> unexposed			

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

The Wilson Farmhouse, built between 1871 and 1900, is an example of a house style found everywhere in Maryland beginning in the 1880's and especially common after 1900. It is a 2-story frame house with 3-bay facade, cross gable over the center bay, a central stairhall separating two rooms on each floor, and a wing protruding from the rear which forms the letter "L". The appearance of this house style toward the end of the 19th century coincided with the transition from open fireplace to wood stove. Thus, one often sees in this type of house mantles without fireplaces: the mantle is retained only as a decorative element, while a wood or kerosene stove placed in front of it provides heat for cooking and comfort.

The Wilson Farmhouse is wood frame, transitional construction (part post-and-beam and part balloon), set on brick piers. The original block contains two rooms on each floor with a central hallway running from front to back of the house. There is an exterior door at each end of the hall. The original exterior wall-covering was weatherboard, now covered by asbestos shingles. The gable roof is covered with two layers of asphalt shingles over top of the original wood shingles. Oral informants tell of a front porch, gone now. A small 1½-story kitchen wing was added to the rear (NE side) of the house, its gable roof set crosswise to the ridge line of the main block. Access to the wing at the second floor level is through the original window opening in the northernmost bay of the NE wall of the main block. Windows are 6/6 double hung sash, except for one single 6/sash set diagonally within the front cross gable, at the attic level. There are three narrow brick chimneys, one centered on either side of the central hall, and one inside the NE wall of the kitchen.

The interior walls are plaster over machine-cut lathes. There are four mantles with stove flues, one in each of the rooms on the first two floors of the main block. A turned newell post at the foot of the stairway anchors a bannister which curves continuously upward through 2½ stories.

Narrow beaded tongue-and-groove boards, commercially available around the turn of the century, and used here on the underside of the eaves, suggest a construction date closer to 1900 than 1871.

Conversely, "modern" machine cut nails found in the structural framing members of the house suggest a construction date prior to 1880 after which time wire nails were commonly available.

Dimensions: see attached floor plan.

8. Significance

Survey No. AA-913

Period	Areas of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input type="checkbox"/> community planning	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> education	<input type="checkbox"/> military	<input type="checkbox"/> social/ humanitarian
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	<input type="checkbox"/> theater
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> commerce	<input type="checkbox"/> exploration/settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> transportation
<input type="checkbox"/> 1900-	<input type="checkbox"/> communications	<input type="checkbox"/> industry	<input type="checkbox"/> politics/government	<input checked="" type="checkbox"/> other (specify) Black History
		<input type="checkbox"/> invention		

Specific dates	Builder/Architect
check: Applicable Criteria: <input type="checkbox"/> A <input type="checkbox"/> B <input type="checkbox"/> C <input type="checkbox"/> D and/or Applicable Exception: <input type="checkbox"/> A <input type="checkbox"/> B <input type="checkbox"/> C <input type="checkbox"/> D <input type="checkbox"/> E <input type="checkbox"/> F <input type="checkbox"/> G Level of Significance: <input type="checkbox"/> national <input type="checkbox"/> state <input checked="" type="checkbox"/> local	

Prepare both a summary paragraph of significance and a general statement of history and support.

Henry Wilson was the first black property owner in Galesville. The Wilson Farmhouse, built either by Henry between 1871-78, or by his son Richard after 1878, is believed to be the oldest house in Galesville.

It was the first of four similar, rather elaborate houses to be built by blacks in Galesville (Wilson; Crowner; Booze; and Hicks). All four were 2½-story frame houses with cross gables at the roofline and kitchen wings at the rear. It is the only one of the four still standing.

In 1865 Henry Wilson bought two acres of land (NHG 13/390) from the owners of Tulip Hill. In 1871 he bought an additional adjacent 25½ acres, including an existing house which carried a life tenancy for its occupant "Old Mrs. Weedon" (SH6/154). (Ann E. Weedon, 75, is listed in the 1870 Census of Galesville. She does not appear in the 1880 Census. It is not known where her house stood.)

Henry Wilson was dead by the time of the 1878 Hopkins Map. His widow, "Kitty" or "Kate", was identified on the Map as the owner of two houses located on her 27½ acres. One was situated on the original two-acre (1865) parcel. (Today that site is occupied by a c.1978 house belonging to Henry's great great grandson Tom Perry.) The other appeared to be on the 25½-acre (1871) portion and would have been either Mrs. Weedon's house or the "new" Wilson Farmhouse.

In the 1880 Census, Kitty was listed as "Head" of her household which included son Richard, his wife Mary and four children, ^{Kitty's} son James, and three other boarders. In the 1900 census, Richard was the "Head" of household including wife Mary, thirteen children, and Kitty ^{his} mother.

Kitty Wilson died in 1901. Her only surviving child Richard inherited her real estate. Later, when Richard's widow Mary died, the property was never partitioned among her heirs. One daughter, Mary Louise Crowner, was the last occupant of the Farmhouse, in 1970. The real estate is still undivided today and owned in common by Mary Wilson's many descendents. Some of them have hopes of restoring the Farmhouse. However, concensus among so many owners is difficult to achieve, and the house continues to deteriorate while they discuss its future.

9. Major Bibliographical References

Survey No. AA-#913

1. Interview, Tom Perry, great great grandson of Henry Wilson, 4/16/85.
2. Federal Censuses: 1860, 1870, 1880, 1900.
3. A.A. County Board of Health (Deaths) 1899-1904 (MdHR 20,182-1), p.97 Kitty Wilson, 1901.
4. Black Historical Resources, Geo. W. McDaniel, Sugarloaf Regional Trails, 1979, p.26
5. Galesville, Md.-Its History & Its People, Dorothy L. Dunham, The Paper Mill, Severna Pk., Md., 1980, p.2

10. Geographical Data

Acreage of nominated property 26.50 acresQuadrangle name DealeQuadrangle scale 1:24,000

UTM References do NOT complete UTM references

A	<input type="text"/>	<input type="text"/>	<input type="text"/>	B	<input type="text"/>	<input type="text"/>	<input type="text"/>
	Zone	Easting	Northing		Zone	Easting	Northing
C	<input type="text"/>	<input type="text"/>	<input type="text"/>	D	<input type="text"/>	<input type="text"/>	<input type="text"/>
E	<input type="text"/>	<input type="text"/>	<input type="text"/>	F	<input type="text"/>	<input type="text"/>	<input type="text"/>
G	<input type="text"/>	<input type="text"/>	<input type="text"/>	H	<input type="text"/>	<input type="text"/>	<input type="text"/>

Verbal boundary description and justification

List all states and counties for properties overlapping state or county boundaries

state	code	county	code
-------	------	--------	------

state	code	county	code
-------	------	--------	------

11. Form Prepared By

name/title Susan R. Wetherill, Volunteerorganization AA/MHTdate November 1985street & number P.O. Box 1573

telephone

city or town Annapolis,state MD 21404

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust
Shaw House
21 State Circle
Annapolis, Maryland 21401
(301) 269-2438

Maryland Anne Arundel County to wit
 I William P Green, Clerk of Anne Arundel
 County Court, do hereby Certify, that it
 hath been proved to my satisfaction, that the
 bearer hereof named Rebecca Johnson aged
 about twenty two years about five feet eight
 and an half inches high, black complexion has
 a scar on the left arm near her elbow, and that
 she was named in the County aforesaid.

Given the 12th day of June 1828

Maryland Anne Arundel County to wit
 I William P Green Clerk of Anne Arundel
 County Court, do hereby Certify that it hath been
 proved to my satisfaction that the bearer hereof
 named Therry Wilson aged about twenty three
 years about five feet eight and an half
 inches high dark complexion has a scar on the
 right cheek is the same person mentioned
 by Thomas Wilson Esq and dated the tenth
 day of July in the year of our Lord one
 thousand eight hundred and twenty eight
 and that he was named in the County aforesaid

Given the 10th day of July 1828

Maryland, Anne Arundel County to wit
 I William P Green, Clerk of Anne Arundel County
 Court, do hereby Certify, that it hath been proved to my
 satisfaction, that the bearer hereof, named Minty Powell aged
 about forty years, about five feet one inch high, light
 complexion, has a scar on the right hand is the identical
 person manumitted by Thomas Poice Esq and dated the
 fifteenth day of July in the year of our Lord one thousand
 eight hundred and twenty three and that she was named
 in the County aforesaid.

Given the 15th day of July 1828.

Name in Full: **Richard Burdges**

Town or P. O.: **Harwood** a. a. co. Month: **11** Day: **2** Y. M. D.: **75** Native of: **U. S.** Occupation: **Farmer**

Died at: **Harwood** On: **11-2-75** Age: **75**

Male Married Widower Divorced 5 Husband of **unknown**

Female Colored Single Widower No. of children living: **0** Wife of **unknown**

Father's Name: **unknown** Mother's Name: **unknown**

Cause of Death: Primary **Mitral Regurgitation** How long sick: **8 months** Reported by: **Dr Murray Chester**

Death: Immediate **Syncope** Accident, Suicide, Homicide: **Harwood, Md** Address: **Harwood, Md**

Name in Full: **Kitty Wilson**

Town or P. O.: **Galesville** a. a. co. Month: **11** Day: **29** Y. M. D.: **82** Native of: **U. S.** Occupation: **Housewife**

Died at: **Galesville** On: **11-29-82** Age: **1**

Male Married Widower Divorced 1 Husband of **Henry Wilson**

Female Colored Single Widower No. of children living: **0** Wife of **Henry Wilson**

Father's Name: **Neale** Mother's Name: **unknown**

Cause of Death: Primary **Heart failure** How long sick: **3 days** Reported by: **S. G. W. Latimer**

Death: Immediate **Asphyxia** Accident, Suicide, Homicide: **West River, Md** Address: **West River, Md**

Name in Full: **Elsie Swann**

Town or P. O.: **Friendship** a. a. co. Month: **11** Day: **4** Y. M. D.: **1.12** Native of: **Md** Occupation: **—**

Died at: **Friendship** On: **11-4-1.12** Age: **—**

Male Married Widower Divorced Husband of **Mellie Hutchins**

Female Colored Single Widower No. of children living: **0** Wife of **Mellie Hutchins**

Father's Name: **Joseph Swann** Mother's Name: **—**

Cause of Death: Primary **Enteric Colitis** How long sick: **12 days** Reported by: **Dr A. H. Perrie**

Death: Immediate **Asphyxia** Accident, Suicide, Homicide: **McFendree, Md** Address: **McFendree, Md**

Name in Full: **John Somerville**

Town or P. O.: **Level Station** a. a. co. Month: **Decem** Day: **8** Y. M. D.: **55** Native of: **Md** Occupation: **Laborer**

Died at: **Level Station** On: **Decem 8 55** Age: **55**

Male Married Widower Divorced 5 Husband of **Jadonia Johnson**

Female Colored Single Widower No. of children living: **0** Wife of **Jadonia Johnson**

Father's Name: **Somerville** Mother's Name: **unknown**

Cause of Death: Primary **Cr. Indigestion hepatic** How long sick: **18 months** Reported by: **Dr Jno. M. Hoag**

Death: Immediate **Uremia, Toxemia** Accident, Suicide, Homicide: **Magoff P.O., Md** Address: **Magoff P.O., Md**

Name in Full: **Bessie Sophia Diggs**

Town or P. O.: **Crownville** a. a. co. Month: **11** Day: **17** Y. M. D.: **3.8.7** Native of: **Md** Occupation: **—**

Died at: **Crownville** On: **11-17-3.8.7** Age: **3.8.7**

Male Married Widower Divorced Husband of **Lola Diggs**

Female Colored Single Widower No. of children living: **0** Wife of **Lola Diggs**

Father's Name: **James Branford** Mother's Name: **Lola Diggs**

Cause of Death: Primary **Scrophula** How long sick: **—** Reported by: **Dr J. W. Dubois**

Death: Immediate **Septicemia** Accident, Suicide, Homicide: **Gambrells, Md** Address: **Gambrells, Md**

Name in Full: **Mary Groshey**

Town or P. O.: **Waterbury** a. a. co. Month: **11** Day: **22** Y. M. D.: **49** Native of: **—** Occupation: **—**

Died at: **Waterbury** On: **11-22-49** Age: **49**

Male Married Widower Divorced Husband of **James Groshey**

Female Colored Single Widower No. of children living: **0** Wife of **James Groshey**

Father's Name: **Mathews** Mother's Name: **Mary Mathews**

Cause of Death: Primary **Peritonitis** How long sick: **4 days** Reported by: **S. H. B. Gantt**

Death: Immediate **Peritonitis** Accident, Suicide, Homicide: **Mullinville, Md** Address: **Mullinville, Md**

Name in Full: **Mrs. A. Brown**

Town or P. O.: **2nd Dist.** a. a. co. Month: **Dec** Day: **21** Y. M. D.: **- 6 -** Native of: **Md** Occupation: **—**

Died at: **2nd Dist.** On: **Dec 21 - 6 -** Age: **61**

Male Married Widower Divorced 61 Husband of **—**

Female Colored Single Widower No. of children living: **0** Wife of **—**


Father's Name: **—** Mother's Name: **—**

Cause of Death: Primary **Althous pneumonia** How long sick: **—** Reported by: **Dr Jno Ridout**


Death: Immediate **Althous pneumonia** Accident, Suicide, Homicide: **—** Address: **—**

HENRY WILSON FAMILY TREE

AA-913



Prepared 6/86 by S. Wetherill




SCALE $\frac{1}{8}$ " = 1'0"

DALE DOWLING

THE WILSON FARMHOUSE
GALESVILLE, MARYLAND

JUNE 19, 1986

2ND FLOOR



STAIRS TO 3RD FLOOR
NOT TO SCALE




SCALE $1/8'' = 1'0''$

DALE DOWLING

THE WILSON FARMHOUSE
GALESVILLE, MARYLAND

JUNE 19, 1986

AA-913



Deale, Md.
 USGS 7.5 minute Series
 Scale 1:24,000
 1957; photorevised 1970

AA-913
 Wilson Farmhouse.
 862 Galesville Rd.
 Galesville.



AA-913

Wilson Farmhouse

A.A. Co., Md.

S. Wehrull 2/85

~~Roll # 6~~

~~FRAME 20~~

facade, SW elev.



AA-913

Wilson Farmhouse

A. A. Co., Md.

S. Wetherill 2/85

~~Roll # 6~~

~~FRAME 17~~

East corner



AA-913

Wilson Farmhouse

A.A.Co., Md

S. Wetherill 2/85

~~Roll #6~~

~~FRAME 18~~

South corner



THE WILSON HOUSE, GALESVILLE, MD.

NOV. 1984

AA-913

A.A. Co, md.

S. Weirill ~~2~~

west corner



AA. 913

Wilson Farmhouse

A.A. Co., Md.

S. Wetherell 1985

Interior

1st floor Stairhall

(Banister-rail Curves

Continuously up to 3rd floor.)



WILSON HOUSE, GALESVILLE, MD. 2/85

AA-913

J. Weatherill

A.A. County

~~Plot # 6~~

~~FRAME 25~~

North Corner



AA. 913

West corner, ceiling
NW room - 2nd floor



AA-913

East corner, 2nd floor



AA-913

~~NW gable end~~ window in
cross-gable of attic

— SW facade —

Top of stair banister
at right.



AA-913



Cross-gable window in
attic stairhall

SW facade



AA-913





AA-913





AA-913


SE gable end window
attic level





AA-913

boxed cornice, NW gable end





AA-913


NW gable end window,
attic level



AA-913

2nd floor NW room, West corner





AA-913

IMAGING BY
Kodak
MAY 18 11



AA-913





AA-913

2nd Floor hall

Center-bay window, SW
facade



AA. 913



East corner, 2nd floor



AA-913





AA-913





AA-913





AA-913

boxed cornice
SE gable end





AA-913





AA-913

Newell post, 1st floor hall



AA. 913



2nd floor Stair hall

Center bay window, NE
elevation

looking at roof and chimney
of 1-story rear el.