

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

(Type all entries complete applicable sections)

STATE:	Maryland
COUNTY:	Baltimore
FOR NPS USE ONLY	
ENTRY DATE:	

1. NAME

COMMON:
Ballestone Mansion

AND/OR HISTORIC:
Cedar Point Mansion

2. LOCATION

STREET AND NUMBER:
Rocky Point Park, Back River Neck Road

CITY OR TOWN:
Essex

CONGRESSIONAL DISTRICT:
Second

STATE: Maryland CODE: 24 COUNTY: Baltimore CODE: 005

3. CLASSIFICATION

CATEGORY (Check One)	OWNERSHIP	STATUS	ACCESSIBLE TO THE PUBLIC
<input type="checkbox"/> District <input type="checkbox"/> Site <input type="checkbox"/> Object <input checked="" type="checkbox"/> Building <input type="checkbox"/> Structure <input type="checkbox"/> Both	<input checked="" type="checkbox"/> Public <input type="checkbox"/> Private <input type="checkbox"/> Both Public Acquisition: <input type="checkbox"/> In Process <input type="checkbox"/> Being Considered	<input type="checkbox"/> Occupied <input checked="" type="checkbox"/> Unoccupied <input type="checkbox"/> Preservation work in progress	Yes: <input type="checkbox"/> Restricted <input type="checkbox"/> Unrestricted <input checked="" type="checkbox"/> No

PRESENT USE (Check One or More as Appropriate)

<input type="checkbox"/> Agricultural	<input type="checkbox"/> Government	<input type="checkbox"/> Park	<input type="checkbox"/> Transportation	<input type="checkbox"/> Comments
<input type="checkbox"/> Commercial	<input type="checkbox"/> Industrial	<input type="checkbox"/> Private Residence	<input checked="" type="checkbox"/> Other (Specify)	
<input type="checkbox"/> Educational	<input type="checkbox"/> Military	<input type="checkbox"/> Religious	vacant, soon to be restored	
<input type="checkbox"/> Entertainment	<input type="checkbox"/> Museum	<input type="checkbox"/> Scientific		

4. OWNER OF PROPERTY

OWNER'S NAME:
Baltimore County Department of Recreation and Parks

STREET AND NUMBER:
301 Washington Avenue

CITY OR TOWN:
Towson

STATE: Maryland CODE: 24

5. LOCATION OF LEGAL DESCRIPTION

COURTHOUSE, REGISTRY OF DEEDS, ETC.:
Baltimore County Courthouse

STREET AND NUMBER:
200 Washington Avenue

CITY OR TOWN:
Towson

STATE: Maryland CODE: 24

6. REPRESENTATION IN EXISTING SURVEYS

TITLE OF SURVEY:
Landmark List, Baltimore County

DATE OF SURVEY:
 Federal State County Local

DEPOSITORY FOR SURVEY RECORDS:
Heritage Society of Essex and Middle River, Inc.

STREET AND NUMBER:
113 Riverside Road

CITY OR TOWN:
Essex

STATE: Maryland CODE: 24

SEE INSTRUCTIONS

FOR NPS USE ONLY
ENTRY NUMBER
DATE

7. DESCRIPTION

CONDITION	(Check One)				
	<input type="checkbox"/> Excellent	<input type="checkbox"/> Good	<input type="checkbox"/> Fair	<input checked="" type="checkbox"/> Deteriorated	<input type="checkbox"/> Ruins
	(Check One)			(Check One)	
	<input checked="" type="checkbox"/> Altered	<input type="checkbox"/> Unaltered		<input type="checkbox"/> Moved	<input checked="" type="checkbox"/> Original Site

DESCRIBE THE PRESENT AND ORIGINAL (if known) PHYSICAL APPEARANCE

The Ballestone Mansion is located on Cedar Point between Back River and Middle River in Essex, Baltimore County, Maryland, and is presently part of the Rocky Point Park, owned by Baltimore County. The house was originally built in the late 1700's or early 1800's and has been enlarged twice. The original house measured 20.2 feet by 17.5 feet, approximately 350 square feet. The major addition was 20.6 feet by 24.6 feet, adding 506 square feet on one floor. A second story was later added to this addition, bringing the total floor area to 1362 square feet (see sketches).

The old part of the existing house, built c. 1800, is brick: Flemish bond brickwork on the roadside (northwest), Common bond brickwork on the Middle River side (southeast) and ends (i.e. header course every sixth course). The bricks were generally soft burned, with a few glazed headers on gable end wall. A carry-over from the eighteenth century, the pitch of the roof is above 45° to the horizontal. There is a corbelled brick cornice in the rear (southeast facade) under the roof. Before being raised for the two-story porch, the front cornice was similar to that in the rear. The cornice is wood with ogee cove molding, sawtooth dentils, square volutes, The main block of the house had three bays on the front and rear. End walls are blank except for a small attic light. The window frames are narrow (2 1/2 inches) with half-round face. The second floor bedroom door dates from the late eighteenth century (c. 1780) and has flush raised panels; other doors appear to date from 1820 or later. Typical of Maryland houses of this period are the wide random-width floor boards in the attic (probably tulip poplar) and narrower random-width floor boards on the first and second floors. Pine trim is also a characteristic feature. The original attic rafters were lapped at the ridge and pinned together. The original collars tied the rafters together with a dovetail joint. The attic was never plastered. The stairway is the type used in the eighteenth and early nineteenth centuries.

It appears that the Miller family added the second story to the addition c. 1870-80. The brickwork is all common bond. The front pitch of the 1800-20 portion had the rafters changed to carry the flatter roof over the porch. Prior to the addition of the second story wing and porch, the original rafters had the same pitch as the rear roof and were pegged at the ridge. The full-length, two-story porch, second floor of this addition, three dormers and Victorian trim around the

SEE INSTRUCTIONS

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

(Continuation Sheet) #1

STATE	Maryland	
COUNTY	Baltimore	
FOR NPS USE ONLY		
ENTRY NUMBER		DATE

(Number all entries)

Ballestone Mansion

7. DESCRIPTION, continued

new porch cornice were a later part of the 1870-80 addition. The fireplace mantel dates sometime after 1850. A chimney, painted red and located over the attic window at the end of the later wing, balances the chimney of the 1800-20 part. A central main entrance, leading into the 1800 section stairhall, widened the original door. The original flat-jack arch was removed and the space covered by the wall framing member of the second floor porch, c. 1870-80. Evidence of cutting and patching in brickwork for second floor porch rafters can be seen. The brick porch wall was whitewashed and later painted gray.

A concrete block shed has been added, within the last fifty years. Also, the rear wall of the later addition was rebuilt in a nonconforming design and will have to be restored as to brick type and coursing and window openings.

The sash windows on the front (northwest) elevation measure 5 feet 6 inches by 3 feet with 6 over 6 panes. The front entrance door, in the third bay from the left (facing house) consists of a masonry opening of 5 feet four inches. The frame includes a full width transom light and two panels, each with side light and two raised panels below. The lintels are brick flat-jack arches and the sills brick row-lock.

The basic first floor plan of this house consists of a center hall and stair, with a large parlor to the left and two rooms to the right, probably dining and sitting rooms (in the later addition), or possibly the kitchen. Upstairs there is one bedroom to the left and two interconnected rooms on the right.

A graveyard is located nearby, across the road. The graveyard has one Stansbury gravestone. Others, including that of Thomas Stansbury, were removed, subsequently recovered are presently guarded by the local historical society. They will eventually be replaced.

6. SIGNIFICANCE

PERIOD (Check One or More as Appropriate)

- Pre-Columbian: 16th Century 18th Century 20th Century
 15th Century 17th Century 19th Century

SPECIFIC DATE(S) (If Applicable and Known) 1800, 1870-1880's

AREAS OF SIGNIFICANCE (Check One or More as Appropriate)

- | | | | |
|--|--------------------------------------|---|---|
| <input type="checkbox"/> Aboriginal | <input type="checkbox"/> Education | <input type="checkbox"/> Political | <input type="checkbox"/> Urban Planning |
| <input type="checkbox"/> Prehistoric | <input type="checkbox"/> Engineering | <input type="checkbox"/> Religion/Phi- | <input checked="" type="checkbox"/> Other (Specify) |
| <input type="checkbox"/> Historic | <input type="checkbox"/> Industry | lasophy | local _____ |
| <input checked="" type="checkbox"/> Agriculture | <input type="checkbox"/> Invention | <input type="checkbox"/> Science | history _____ |
| <input checked="" type="checkbox"/> Architecture | <input type="checkbox"/> Landscape | <input type="checkbox"/> Sculpture | _____ |
| <input type="checkbox"/> Art | Architecture | <input type="checkbox"/> Social/Human- | _____ |
| <input type="checkbox"/> Commerce | <input type="checkbox"/> Literature | itarian | _____ |
| <input type="checkbox"/> Communications | <input type="checkbox"/> Military | <input type="checkbox"/> Theater | _____ |
| <input type="checkbox"/> Conservation | <input type="checkbox"/> Music | <input type="checkbox"/> Transportation | _____ |

STATEMENT OF SIGNIFICANCE

Back River Neck in Baltimore County, situated between Back River to the south and Middle River to the north, was once a rural district populated mainly by farmers. Today, just across Back River from the Baltimore Beltway, it is becoming an increasingly suburban area. As the only extant farmer's house in this area, Ballestone Mansion is the sole visible reminder of its past way of life.

In about 1800 when the first part of the house was built, possibly by Joseph Ward Stansbury or his son Ephraim Stansbury, 95 percent of the families in the United States lived on farms or in small country towns.¹ Ballestone probably began its existence as the home of one such American farming family. When the property was to be sold at auction in 1817 in the settlement of Joseph Ward Stansbury's estate, it was described as follows in a newspaper advertisement:

...[a] Farm called BALISTON, containing about 100 acres of land, distant about 13 miles from the city in Back River Neck-the improvements are, a two story dwelling in good order, with barns, stabling and other suitable buildings...²

The property was sold for \$17.06 per acre to Willim Cook, stepfather of Ephraim Stansbury's two children, William and Mary Ann. It remained in the Stansbury family until 1852 when Richardson Collins, son of Mary Ann (Stansbury) Collins, submitted it for auction.

According to Russel B. Nye in his Cultural Life of the New Nation, the farmer in the early nineteenth century "made his living by hard, backbreaking labor that involved his entire family...His farm was supposed to provide for practically all his needs, with a surplus for sale or export, and it usually did."³

¹Russel Blaine Nye, The Cultural Life of the New Nation, 1776-1830, The New American Nation Series, Harper Torchbooks (New York: Harper & Row, Publishers, 1960), p. 128.

²Newspaper clipping from the American, April-May 1817. Chancery Paper 4782, Baltimore County. Hall of Records, Annapolis, Maryland.

³Nye, p. 129.

SEE INSTRUCTIONS

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

(Continuation Sheet) #2

BA-262

STATE	
Maryland	
COUNTY	
Baltimore	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

(Number all entries)

Ballestone Mansion

8. SIGNIFICANCE, continued

Ballestone's proximity to Baltimore gave its owners an added advantage in marketing their crops. It was a large city which, according to Henry Adams, has the "diversity of interests and local markets"⁴ which made it possible for farmers and planters to realize a profit from their labor.

Ballestone was purchased in 1855 by Edward Miller, whose heirs owned it until 1969. In about 1870 the Millers enlarged the farmhouse by adding a one and one half story wing to one end. It was apparently some time during the 1870's or 1880's that this addition was made into a full two stories and the cornice, dormers, and two-story porch were added. These alterations made the house much more imposing. Today Ballestone is the only house in Back River Neck in restorable condition. It is still in a fairly rural setting, being surrounded by a golf course. Owned by the Baltimore County Department of Recreation and Parks, it will be restored by the Essex-Middle River Bicentennial Committee for use by the community as a part of Rocky Point Park.

11. FORM PREPARED BY, continued

Peter C. Powell, AIA
Mark Beck Associates, Inc.
762 Fairmount Avenue
Towson, Maryland 21204

Pamela James, Research Assistant
Maryland Historical Trust
2525 Riva Road
Annapolis, Maryland 21401

⁴Henry Adams, The United States in 1800, Cornell Paperbacks, (Ithaca, New York: Cornell University Press, 1955 (orig. 1889), p. 23.

9. MAJOR BIBLIOGRAPHICAL REFERENCES

Chancery Records (Baltimore County). Hall of Records,
 Annapolis, Maryland.
 Land Records, Baltimore County. Hall of Records.
 Probate Records, Baltimore County. Hall of Records.

10. GEOGRAPHICAL DATA

LATITUDE AND LONGITUDE COORDINATES DEFINING A RECTANGLE LOCATING THE PROPERTY			O R	LATITUDE AND LONGITUDE COORDINATES DEFINING THE CENTER POINT OF A PROPERTY OF LESS THAN TEN ACRES		
CORNER	LATITUDE	LONGITUDE		LATITUDE	LONGITUDE	
	Degrees Minutes Seconds	Degrees Minutes Seconds		Degrees Minutes Seconds	Degrees Minutes Seconds	
NW	° ' "	° ' "		° ' "	° ' "	
NE	° ' "	° ' "		° ' "	° ' "	
SE	° ' "	° ' "		° ' "	° ' "	
SW	° ' "	° ' "		° ' "	° ' "	

APPROXIMATE ACREAGE OF NOMINATED PROPERTY: 5 acres

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE:	CODE	COUNTY	CODE

11. FORM PREPARED BY

NAME AND TITLE: Edward Seidel, Chariman (See continuation sheet No. 2)

ORGANIZATION: Baltimore County Bicentennial Committee through DATE: August 1974

STREET AND NUMBER: 211 Courtland Street

CITY OR TOWN: Towson STATE: Maryland CODE: 24

the Essex Bicentennial

12. STATE LIAISON OFFICER CERTIFICATION NATIONAL REGISTER VERIFICATION

<p>As the designated State Liaison Officer for the National Historic Preservation Act of 1966 (Public Law 89-665). I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the National Park Service. The recommended level of significance of this nomination is:</p> <p>National <input type="checkbox"/> State <input type="checkbox"/> Local <input type="checkbox"/></p> <p>Name <u>Orlando Ridout IV</u></p> <p>Title <u>State Historic Preservation Officer</u></p> <p>Date _____</p>	<p>I hereby certify that this property is included in the National Register.</p> <p>_____ <i>Director, Office of Archeology and Historic Preservation</i></p> <p>Date _____</p> <p>ATTEST:</p> <p>_____ <i>Keeper of The National Register</i></p> <p>Date _____</p>
--	--

SEE INSTRUCTIONS


BIBLIOGRAPHY
BALLESTONE MANSION AND ESTATE
ESSEX, BALTIMORE COUNTY, MARYLAND

- 1659 Cecilius Calvert granted William Ball 420 acres which he called "BALLESTONE." William Ball's son Joseph was the father of Mary Ball, who was George Washington's mother. This was confirmed by William Marye of Bradshaw, Md., who is descended from William Ball through his daughter Hannah.
- 1671 June 10 - William Ball - Resurvey of Ballestone (Hall of Records - Annapolis- Liber 16 - Fol 268-269-270 - Patents) This Deed of Resurvey refers to the original Deed of Grant.
- 1678 Indenture - William Ball to Major Thomas Long. John Long inherited Ballestone from his grandfather, Thomas Long.
- 1733 John Long conveyed to Joseph Ward "and by him devised to Mary Stansbury, mother of Joseph Ward Stansbury." (Mary Stansbury was the daughter of Joseph Ward). *no-granddaughter*
- 1766/1769 Dates on tombstones of Jane and Thomas Stansbury - located on grounds.
- 1776 Dixon Stansbury obtained a warrant on 30 acres of ground bordering on Ballestone and called it "Ballestone Support."
- Joseph Ward's heir was Ephraim Stansbury, whose heirs were *no, Ephraim dead, other heirs*
- 1819 William Stansbury and his sister, Mary Ann Stansbury. William's heir was his sister, Mary Ann, and her heir was her son, Richardson Collins.
- 1819 February 13 - Nicholas Brewer Deed to William Stansbury and Mary Ann Stansbury (Hall of Records - Annapolis - Liber 149 - Fol. 679 - 680 - copy attached). Refers to Land Record in Liber TS (or IS) No. 8 folio - 378 &c - partial copy attached.
- 1819-1839 Sometime within these 20 years, Andrew Leakin and, subsequently, his son Shepard C. Leakin (Mayor of Baltimore City) obtained Ballestone. *no!*
- 1840 Shepard C. Leakin lost this property at public auction - purchasers were Robert Purvience, Jr. and John S. Gittings.
- 1844 June 11 - James B. Price Admor of A. T. Leakin deed vs. Shepard C. Leakin (Chancery Records TK 34 - Folio 542). This is one of the Title References in *←* the Deed of 1855.
- 1852 November 24 - John Taylor Trustee and others Deed to Robert Purvience, Jr. and others - Towson Courthouse - Book #3 Folios 428 - 9 - 30 - 1 - copy attached. Refers to Indenture in Liber W. G. No.149 Folio 678 &c - copy attached.

- 1852 December 20 - Sydenham R. Clarke and his wife Deed to Robert Purvience, Jr. Towson Courthouse - Book #4 - Folios 207 - 8 - 9 - copy attached. Refers to Indenture in Liber HMF No. 3 - copy attached.
- 1855 Edward Miller obtained the property from Messrs. Purvience and Gittings - up to this point, the property had retained the name "Ballestone" or "Balston."
- 1855 February 5 - Robert Purvience, Jr. and John S. Gittings and his wife - Deed to Edward Miller (Towson Courthouse - Book 10 Folios 484 - 5 - 6 - copy attached. Title reference in deed: Chancery Record of Baltimore County Court T. K. No. $\frac{31}{150}$
- T. K. $\frac{34}{542}$
- 1969 May - Baltimore County Department of Recreation and Parks purchased the property from the heirs of Edward Miller.

BA-262

North West



24.6'

1870

1800

17.55'

SHED TO BE REMOVED

7.35'

20.6'


26.2'

46.8'

South East

SCALE 1" = 6.0'

GROUND FLOOR PLAN BALLESTONE MANSION



Ballestone Mansion Phase I

L. C. 170
L. C. 190

BR-262



Ballestone Mansion Phase 2

BR-262



Ballestone Mansion Phase 3

1870-80

BA-262



BALLESTONE

BA-262




THE CEDAR POINT MANSION

"BALLESTONE"

QWENSNER

BA 262

Looking back at Ballestone



Ballestone Mansion, saved from decay by a community effort and reopened a decade ago, is nearly 200 years old and is now owned by Baltimore County. SATURDAY SUN PHOTOS/BARBARA HADDOCK

Mansion at Rocky Point opens its doors to visitors on Sundays

By Steve Purchase

volunteers from the Essex-Middle River

e
s and
n Miller,
ork
s at

orful
eing.
.m.

n

The


Theatre,
a.

ons
usic
ut
3125.

Ish

Jester
The

BA-262
w
st
st



BA-262




1850 SURVEY MAP OF BALTIMORE COUNTY

195

BA-262

NAME



12th DISTRICT.

Hotel.

SCHMIDT'S PAVILION,
North Point Road 5 Miles from the City,
binding on Bear Creek, with Fishing
Shore and Pleasure Grounds. Fish,
Crabs and all other luxuries served in
Season in the best Style and at the
Shortest Notice. A liberal patronage
solicited. Jno Schmidt, Proprietor.

Manufacturer.

ALFRED ROSS,
[Formerly A. & D. Ross.]
Manufacturer of Crochet Needles, Button
Hooks, Nail Punches, Cotton Hooks,
Currier's Blades and Sickle Chisels, Ore-
ster Knives, &c. All Orders sent by Mail
will be Promptly Attended to
White House, Chases Station F. O. P. W. and
B. R. R., Baltimore Co. Md.

Plasterer.

WM. H. RUSSELL,
Gardener and Plasterer,
Chases Station.

Teacher.

C. T. SHAFFER,
Chases Station.


EAST PART OF

TWELFTH DISTRICT.

Scale 2 Inches = to a Mile.


1877 Geological Survey

Entered in mailing pocket of maps in the year 1877 by G.M.H.




Middle River Quadrangle
 U.S.G.S. 7.5 minute map
 scale 1:24000
 1969

BA-262



Sparrows Point Quadrangle
 U.S.G.S. 7.5 minute map
 scale 1:24000
 1969

Hart Cove



BA-262

U.S.G.S. 7.5 minute map
MIDDLE RIVER QUADRANGLE
scale: 1:24000
1969

C H E S A P E A K

4348
4347
4346000m
39° 1
4345
4344
5100
FEET
4343
4342

HOLLY 25 NECK

Breezy Point Beach Wells Pt

DIFFENDAL ROAD 19

NECK

EVERGREEN LANE RD

WILDWOOD BEACH

BARRISON 5

ROAD

ROCKY POINT

CEGAR

Porters Park

BALLESTONE MANSION

HAWK

BACK

RIVER

HAWK COVE

Claybank Pt

Cedar Pt

Drum Pt

Hart I

Cuckold Pt

Swan Point

Ramona Beach

WILSONS FARM RD

MILLERS NECK

Marsh

Black

BM 21

BM 4

Light

BM 9 X

BM 28

Rocky Pt

Tidal Flat

ROAD

ROAD

BROOKS CREEK

Balston Point

Island View Beach

Tidal Flat

Essex SkyPark

Open Park

BM 21



NO TRESPASSING
PROPERTY OF THE STATE OF OHIO
DEPT. OF REVENUE & TAXATION

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES

PROPERTY PHOTOGRAPH FORM

(Type all entries - attach to or enclose with photograph)

STATE	
COUNTY	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

SEE INSTRUCTIONS

1. NAME			
COMMON: Ballestone Mansion			
AND/OR HISTORIC: Cedar Point Mansion			
2. LOCATION			
STREET AND NUMBER:			
Rocky Point Park, Back River Neck Road			
CITY OR TOWN:			
Essex			
STATE:	CODE	COUNTY:	CODE
Maryland		Baltimore County	
3. PHOTO REFERENCE			
PHOTO CREDIT: Robert Dugent			
DATE OF PHOTO: July 17, 1974			
NEGATIVE FILED AT: Robert Dugent			
442 Margaret Avenue Essex			
4. IDENTIFICATION			
DESCRIBE VIEW, DIRECTION, ETC.			
Looking due West showing East facade.			



UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES
PROPERTY PHOTOGRAPH FORM

(Type all entries - attach to or enclose with photograph)

STATE	
COUNTY	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

SEE INSTRUCTIONS

1. NAME

COMMON: Ballestone Mansion

AND/OR HISTORIC: Cedar Point Mansion

2. LOCATION

STREET AND NUMBER:

Rocky Point Park, Back River Neck Road

CITY OR TOWN:

Essex

STATE:

Maryland

CODE

COUNTY:

Baltimore County

CODE

3. PHOTO REFERENCE

PHOTO CREDIT: Robert Dugent

DATE OF PHOTO: July 17, 1974

NEGATIVE FILED AT: Robert Dugent

442 Margaret Avenue Essex

4. IDENTIFICATION

DESCRIBE VIEW, DIRECTION, ETC.

Looking due North showing South facade and surrounding grounds.

Looking from graveyard.



BA-262

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES


PROPERTY PHOTOGRAPH FORM

(Type all entries - attach to or enclose with photograph)

STATE	
COUNTY	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

SEE INSTRUCTIONS

1. NAME			
COMMON: Ballestone Mansion			
AND/OR HISTORIC: Cedar Point Mansion			
2. LOCATION			
STREET AND NUMBER:			
Rocky Point Park, Back River Neck Road			
CITY OR TOWN:			
Essex			
STATE:	CODE	COUNTY:	CODE
Maryland		Baltimore County	
3. PHOTO REFERENCE			
PHOTO CREDIT: Robert Dugent			
DATE OF PHOTO: July 17, 1974			
NEGATIVE FILED AT: Robert Dugent			
442 Margaret Avenue Essex			
4. IDENTIFICATION			
DESCRIBE VIEW, DIRECTION, ETC.			
Looking due East showing West facade.			



BA-262

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES
PROPERTY PHOTOGRAPH FORM

(Type all entries - attach to or enclose with photograph)

STATE	
COUNTY	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

SEE INSTRUCTIONS

1. NAME			
COMMON: Ballestone Mansion			
AND/OR HISTORIC: Cedar Point Mansion			
2. LOCATION			
STREET AND NUMBER:			
Rocky Point Park, Back River Neck Road			
CITY OR TOWN:			
Essex			
STATE:	CODE	COUNTY:	CODE
Maryland		Baltimore County	
3. PHOTO REFERENCE			
PHOTO CREDIT: Robert Dugent			
DATE OF PHOTO: July 17, 1974			
NEGATIVE FILED AT: Robert Dugent			
442 Margaret Avenue Essex			
4. IDENTIFICATION			
DESCRIBE VIEW, DIRECTION, ETC.			
Looking Southeast showing West facade			



BA-262

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES
PROPERTY PHOTOGRAPH FORM

(Type all entries - attach to or enclose with photograph)

STATE	
COUNTY	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

SEE INSTRUCTIONS

1. NAME			
COMMON: Ballestone Mansion			
AND/OR HISTORIC: Cedar Point Mansion			
2. LOCATION			
STREET AND NUMBER:			
Rocky Point Park, Back River Neck Road			
CITY OR TOWN:			
Essex			
STATE:	CODE	COUNTY:	CODE
Maryland		Baltimore County	
3. PHOTO REFERENCE			
PHOTO CREDIT: Robert Dugent			
DATE OF PHOTO: July 17, 1974			
NEGATIVE FILED AT: Robert Dugent			
442 Margaret Avenue Essex			
4. IDENTIFICATION			
DESCRIBE VIEW, DIRECTION, ETC.			
Interior showing original mantel.			



BA-262

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES
PROPERTY PHOTOGRAPH FORM

(Type all entries - attach to or enclose with photograph)

STATE	
COUNTY	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

SEE INSTRUCTIONS

1. NAME			
COMMON: Ballestone Mansion			
AND/OR HISTORIC: Cedar Point Mansion			
2. LOCATION			
STREET AND NUMBER:			
Rocky Point Park, Back River Neck Road			
CITY OR TOWN:			
Essex			
STATE:	CODE	COUNTY:	CODE
Maryland		Baltimore County	
3. PHOTO REFERENCE			
PHOTO CREDIT: Robert Dugent			
DATE OF PHOTO: July 17, 1974			
NEGATIVE FILED AT: Robert Dugent			
442 Margaret Avenue Essex			
4. IDENTIFICATION			
DESCRIBE VIEW, DIRECTION, ETC.			
Interior showing added brick work in attic for addition and raised roof			

HERE
LIES THE
BODY OF JANE
STUBBY WHO
DEPARTED THIS
LIFE OCTOBER 7 1766
AGED 77 YEARS

BA-262

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES

PROPERTY PHOTOGRAPH FORM

(Type all entries - attach to or enclose with photograph)

STATE	
COUNTY	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

SEE INSTRUCTIONS

1. NAME			
COMMON: Ballestone Mansion			
AND/OR HISTORIC: Cedar Point Mansion			
2. LOCATION			
STREET AND NUMBER:			
Rocky Point Park, Back River Neck Road			
CITY OR TOWN:			
Essex			
STATE:	CODE	COUNTY:	CODE
Maryland		Baltimore County	
3. PHOTO REFERENCE			
PHOTO CREDIT: Robert Dugent			
DATE OF PHOTO: July 17, 1974			
NEGATIVE FILED AT: Robert Dugent			
412 Margaret Avenue, Essex.			
4. IDENTIFICATION			
DESCRIBE VIEW, DIRECTION, ETC.			
Tombstone of Jane Stansbury; one of seven tombstones to be restored.			



BA-262