

CAPSULE SUMMARY
BA-1096
343 Hillen Road
East Towson, Baltimore County
Circa 1900
Private

The dwelling at 343 Hillen Road was constructed circa 1900 in the East Towson neighborhood of Baltimore County. The history of East Towson dates from the purchase of one-and-a-quarter acres of land by Daniel Harris in September 1853. This is believed to be the first documented African-American landholding in Towson, and is among the oldest such ethnic enclave in Baltimore County. Further, manumitted slaves and/or descendants of former slaves, many of who were owned by Charles Ridgely, populated the neighborhood. Hampered by the low economic status of the residents, development in the 19th century was slow, increasing after the turn of the 20th century. The setting of the property, building styles, and construction materials were guided by the limited economic status of the residents and their desire to establish a neighborhood of their own without the assistance of white architects, builders, and craftsmen. By 1927, the community was ninety-five percent improved with single-family dwellings, social buildings, a school, and religious structures.

Fronting south, this two-story house is sited on a level grassy lot surrounded by mature trees with a gravel driveway, and a power plant to the rear. This vernacular wood frame dwelling is two bays wide with off center fenestration covered with a one-story shed roof porch across the façade. The porch is supported with square posts and square-edged balusters. The façade is lighted with three windows 1/1 double-hung vinyl sash windows with square aluminum surrounds, and the side passage door is single-leaf 6-light 2-panel. The building is re-clad with vinyl siding and is capped with a side gable roof with overhanging eaves. The roof features a square-edged boxed wood cornice and is sheathed with asphalt shingles. Numerous one and two-story additions are seen on the side and rear elevations.

Maryland Historical Trust

Maryland Inventory of Historic Properties Form

Inventory No. BA-1096

1. Name of Property (indicate preferred name)

historic 343 Hillen Road

other

2. Location

street and number 343 Hillen Road not for publication

city, town Baltimore vicinity

county Baltimore County

3. Owner of Property (give names and mailing addresses of all owners)

name Amy E. Davis

street and number 343 Hillen Road telephone Not available

city, town Baltimore state MD zip code 21286-5424

4. Location of Legal Description

courthouse, registry of deeds, etc. Baltimore County Courthouse tax map and parcel: 70/891

city, town Towson liber 10483 folio 206

5. Primary Location of Additional Data

- Contributing Resource in National Register District
- Contributing Resource in Local Historic District
- Determined Eligible for the National Register/Maryland Register
- Determined Ineligible for the National Register/Maryland Register
- Recorded by HABS/HAER
- Historic Structure Report or Research Report
- Other

6. Classification

Category	Ownership	Current Function	Resource Count	
			Contributing	Noncontributing
<input type="checkbox"/> district	<input type="checkbox"/> public	<input type="checkbox"/> agriculture		
<input checked="" type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> commerce/trade	1	
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> defense		
<input type="checkbox"/> site		<input checked="" type="checkbox"/> domestic		
<input type="checkbox"/> object		<input type="checkbox"/> education		
		<input type="checkbox"/> funerary	1	0
		<input type="checkbox"/> government		
		<input type="checkbox"/> health care		
		<input type="checkbox"/> industry		
		<input type="checkbox"/> landscape		
		<input type="checkbox"/> recreation/culture		
		<input type="checkbox"/> religion		
		<input type="checkbox"/> social		
		<input type="checkbox"/> transportation		
		<input type="checkbox"/> work in progress		
		<input type="checkbox"/> unknown		
		<input type="checkbox"/> vacant/not in use		
		<input type="checkbox"/> other:		
			Number of Contributing Resources previously listed in the Inventory 1	

7. Description

Inventory No. BA-1096

Condition

<input type="checkbox"/> excellent	<input type="checkbox"/> deteriorated
<input type="checkbox"/> good	<input type="checkbox"/> ruins
<input checked="" type="checkbox"/> fair	<input type="checkbox"/> altered

Prepare both a one paragraph summary and a comprehensive description of the resource and its various elements as it exists today.

EXTERIOR

Fronting south, this two-story house is sited on a level grassy lot surrounded by mature trees with a gravel driveway, and a power plant to the rear. This wood-frame vinyl-clad dwelling is two stories in height and two bays wide with off-center fenestration. It rests on a solid foundation and is capped with a side-gable roof clad with asphalt shingles. The roof features overhanging eaves and a boxed cornice. A two-story shed-roof addition was constructed on the rear elevation. A second addition was constructed on the east elevation of the rear section. A third addition, one-story high was built on the rear elevation. There is no basement to this dwelling, and the attic was not accessible. No secondary resources are associated with this property.

The first story of the façade features an off-center entry flanked by one 1/1 vinyl-sash window. The entrance contains a single-leaf 6-light/2-panel wood door. The second story holds two 1/1 vinyl-sash windows. Each of the openings have square-edged aluminum surrounds. Across the façade covering the first story is a shed-roof porch supported with square wood posts and square-cut balusters. The first story of the side addition has a single 1/1 vinyl-sash window flanking a single-leaf entry. The entrance contains a 4-panel wood door. The second story of the side addition holds two 1/1 vinyl-sash windows.

The east elevation of the main section has one 1/1 vinyl-sash window centrally located in the first and second stories. The first story of the side shed addition has a 1-light fixed wood window and a two pairs of 6-light sliding wood windows. The one-story rear addition has one single-leaf entry covered by a jalousie aluminum storm door and a flush wood door.

The three shed-roof additions are visible on the rear elevation. The second story of the first rear addition exhibits one 2/2 (horizontal lights) wood-sash window, and one 1/1 vinyl-sash window. Two 1/1 vinyl sash windows are visible on the second story of the north elevation of the side addition. The north elevation of the one-story addition features a center single-leaf entry flanked by 2-light fixed wood windows. The entry contains a 6-light/2-panel wood door. This one-story addition is clad with pressed vertical-board siding.

One 1/1 vinyl-sash window are centrally located on the first and second story of the west elevation of the main block. The first story of the rear addition on the west elevation has three 1/1 vinyl-sash windows. Two 1/1 vinyl-sash windows are on the second story of the rear addition.

INTERIOR

The original section of the dwelling features a two room plan with a straight-flight stair. The two rooms on the first floor are situated north and south, and the two rooms on the second floor are situated east and west. With the multiple additions, the first floor has nine separate rooms and the second story contains seven rooms. Entrance into the house is into the living room. This room features painted original lath and plaster walls and replacement vinyl tiles covering the wood floors. The original five inch flush wood baseboard is square-edged with a shoe molding. The window and door wood casings are square-edged. The window casings are four inches wide and the door casings are five and one-half inches wide. Two open doorways on the north wall lead either to the stair or to the dining room. The doorway to the stairs has an applied lintel with a cyma reversa molding. The exterior door features a replacement brass knob.

The straight-flight stair is wood and has square-cut balusters. A thin plywood door leads to a bathroom underneath the stair. The dining room features painted original lath and plaster walls and a replacement drywall ceiling. The wood floor is covered with carpet. Around the perimeter of the room is an original three-inch wood baseboard. The window and door casings are one inch wide. The applied crown molding has a cyma reversa molding.

Maryland Inventory of
Historic Properties Form

Name 343 Hillen Road

Continuation Sheet

Number 7 Page 1

To the rear of the dining room is a secondary dining room or living room. This floor is covered with replacement vinyl tiles and the walls are covered with replacement pressed vertical boards. The ceiling is covered with replacement drywall. The window casings are flush two-inches, and the crown molding is flush two-inches wide. A chimney flue protrudes from the south wall of this room.

A small utility room is located off the secondary dining room. The original floor is covered with vinyl tiles and carpet. Two of the walls are concrete block. The east wall has a window opening boarded over. Visible on the south wall are circular sawn fourteen inch wide boards. The ceiling is drywall.

To the rear of the secondary dining room is the kitchen. The replacement floor is vinyl tiles and the ceiling is drywall. The original walls are constructed of drywall and some are covered with pressed vertical boards. At the floor around the perimeter of the room is a shoe molding. The flush window casings are two inches wide, and the flush door casings are one inch wide. The exterior door features the original iron handle. A window opening was cut into the south wall providing shelf space.

East of the stair in the side shed roof addition is the family room. The pine floorboards are a replacement. The walls are clad with pressed vertical boards and the ceiling is covered with drywall. Around the perimeter of the room is a three-inch high replacement baseboard and an ovolo crown molding. The window casing is a beaded two-inch replacement board. The original flush door casing is two-and-a-half inches wide.

To the rear of the family room is a bedroom. The floor is covered with replacement vinyl tiles and the ceiling is covered with drywall. The walls are covered with replacement pressed vertical boards. The room has a three-inch square-edged baseboard, and a cyma reversa crown molding. The flush door casings are five inches wide. The doors in this room are plywood and the door knobs have been removed.

North of the bedroom is the utility room. The replacement floor is covered with carpet and vinyl tiles. The walls are covered with pressed vertical boards and the replacement ceiling is drywall. The flush window casings are three inches wide. A shower stall was installed in one corner of the room.

The second story is comprised of six bedrooms and one bathroom. The rooms in the side addition have carpeted floor and the walls are covered with pressed vertical boards. The two rooms in the main section of the house have lath and plaster walls. The ceiling is drywall, and the floor is covered with vinyl and carpet. The doors to each of these rooms are pressed vertical board. The rear west bedroom has a chimney flue protruding from the wall.

8. Significance

Inventory No. BA-1096

Period	Areas of Significance	Check and justify below		
<input type="checkbox"/> 1600-1699	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> health/medicine	<input type="checkbox"/> performing arts
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> archeology	<input type="checkbox"/> education	<input type="checkbox"/> industry	<input type="checkbox"/> philosophy
<input type="checkbox"/> 1800-1899	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> engineering	<input type="checkbox"/> invention	<input type="checkbox"/> politics/government
<input checked="" type="checkbox"/> 1900-1999	<input type="checkbox"/> art	<input type="checkbox"/> entertainment/ recreation	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 2000-	<input type="checkbox"/> commerce	<input type="checkbox"/> ethnic heritage	<input type="checkbox"/> law	<input type="checkbox"/> science
	<input type="checkbox"/> communications	<input type="checkbox"/> exploration/ settlement	<input type="checkbox"/> literature	<input type="checkbox"/> social history
	<input type="checkbox"/> community planning		<input type="checkbox"/> maritime industry	<input type="checkbox"/> transportation
	<input type="checkbox"/> conservation		<input type="checkbox"/> military	<input type="checkbox"/> other:

Specific dates 1900 ca. **Architect/Builder** unknown

Construction dates 1900 ca.

Evaluation for:

National Register Maryland Register not evaluated

Prepare a one-paragraph summary statement of significance addressing applicable criteria, followed by a narrative discussion of the history of the resource and its context. (For compliance reports, complete evaluation on a DOE Form - see manual.)

SIGNIFICANCE STATEMENT

The dwelling at 343 Hillen Road, constructed circa 1900, is significant as a contributing dwelling to the African-American neighborhood of East Towson. As the first documented African-American landholding community, East Towson began and was developed during the third quarter of the 19th century. The community was essentially fully developed by the late 1920s. This wood-frame vernacular house is typical of the vernacular dwellings common to the East Towson neighborhood.

HISTORY

The house at 343 Hillen Road was constructed circa 1900 in the East Towson neighborhood of Baltimore County. East Towson is associated with events that have made a significant contribution to the broad patterns of our history, specifically the pre-Civil War development of an African-American neighborhood in a predominately white community. The history of this property dates from the purchase of one-and-a-quarter acres of land by Daniel Harris in September 1853. This is believed to be the first documented African-American landholding in Towson, and is among the oldest such ethnic enclave in Baltimore County. Further, manumitted slaves and/or descendants of former slaves, many of who were owned by Charles Ridgely, populated the neighborhood. Hampered by the low economic status of the residents, development in the 19th century was slow, increasing after the turn of the 20th century. The setting of the property, building styles, and construction materials were guided by the limited economic status of the residents and their desire to establish a neighborhood of their own without the assistance of white architects, builders, and craftsmen. By 1927, the community was ninety-five percent improved with single-family dwellings, social buildings, a school, and religious structures. Many of the current homeowners and tenants living in the neighborhood are descendants of the first African-American residents.

East Towson as a whole is representative of an important phase of architectural development in Baltimore County, illustrating the dilution of popular architectural styles to more efficiently meet the needs of the neighborhood, and the builders' untrained abilities to execute the fashionable ornamentation. Thus, East Towson provided lower cost housing in a more suburban neighborhood, rather than the urban setting their economic status typically perpetuated.

The land on which 343 Hillen Road is located was originally owned by Daniel Payne during the mid-19th century. The Trustees to Payne sold the property to John Yellott in 1883. Two years later, the Yellotts sold the property to the Relief Association for Baltimore County. In 1897, the property was deeded to Mary Taylor. Taylor resided here for twenty-one years until she sold it to Mary Louise and Rachel Parker. The property exchanged hands five times between 1921 and 1948. At this time, Amy E. Davis purchased the dwelling from James B. and Bertha E. Wheatly. The Davis family resided at this residence for fifty-four years.

Maryland Historical Trust

Maryland Inventory of Historic Properties Form

Inventory No BA-1096

Name 343 Hillen Road

Continuation Sheet

Number 8 Page 1

CHAIN OF TITLE

- July 10, 1847: John R. Cockey and wife to Benjamin Payne
Land Records of Baltimore County,
Liber AWB 383 Folio 79
- June 1, 1883: Nicholas C. Burke, B. P. Butler, and S. P. Bosley, Trustees for Benjamin Payne to John Yellott
Land Records of Baltimore County,
Liber WMI 138, Folio 401
- August 14, 1885: John I. Yellott and Mary Yellott (wife) to The Relief Association of Baltimore County
Land Records of Baltimore County,
Liber WMI 147, Folio 591
- June 1, 1897: The Relief Association of Baltimore County to Mary Taylor (widow)
Land Records of Baltimore County,
Liber NBM 259, Folio 199
- December 4, 1918: Mary Taylor (widow) to Mary Louisa Parker and Rachel Parker
Land Records of Baltimore County,
Liber WPC 506, Folio 321
- September 24, 1921: Mary Louisa Parker, William Parker (husband) and Rachel Parker to Eliza P. Turner
Land Records of Baltimore County,
Liber WPC 543, Folio 376
- July 1, 1927: Eliza P. Turner to James C.L. Anderson
Land Records of Baltimore County
Liber WPC 772, Folio 211
- July 11, 1928: James C.L. Anderson to Mildred A. Johnson
Land Records Of Baltimore County
Liber WHM 659, Folio 43
- July 11, 1928: Mildred A. Johnson to James C.L. Anderson
Land Records of Baltimore County
Liber WHM 796, Folio 325
- November 29, 1938: James C.L. Anderson to James B. Wheatly and Bertha E. Wheatly (wife)
Land Records of Baltimore County
Liber CWB Jr. 1048, Folio 253
- February 3, 1948: James B. Wheatly and Bertha E. Wheatly (wife) to George W. Davis and Amy E. Davis (wife)
Land Records of Baltimore County
Liber 1648, Folio 167

Maryland Historical Trust
Maryland Inventory of
Historic Properties Form

Inventory No BA-1096

Name 343 Hillen Road

Continuation Sheet

Number 8 Page 2

September 20, 1991: Amy E. Davis to Amy E. Davis
Land Records of Baltimore County
Liber 8920, Folio 323

April 12, 1994: Amy E. Davis to Amy E. Davis
Land Records of Baltimore County
Liber 10483, Folio 206

9. Major Bibliographical References

Inventory No. BA-1096

See continuation sheet.

10. Geographical Data

Acreage of surveyed property .13 acres

Acreage of historical setting unknownQuadrangle name TowsonQuadrangle scale 1:24,000

Verbal boundary description and justification

The house is located at 343 Hillen Road in East Towson in the Ninth District of Baltimore County. It has historically been associated with Tax Map 70, Parcel 891 since its construction circa 1900.

11. Form Prepared By

name/title K. Baynard & J. Riggle, Architectural Historians

organization E.H.T. Traceries

date 9/16/02

street and number 1121 Fifth Street, NW

telephone 202/393-1199

city or town Washington

state DC zip code 20001

The Maryland Inventory of Historic Properties was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust
DHCD/DHCP
100 Community Place
Crownsville MD 21032
410-514-7600

Maryland Historical Trust
Maryland Inventory of
Historic Properties Form

Inventory No. BA-1096

Name 343 Hillen Road

Continuation Sheet

Number 9 Page 1

Atlas of Baltimore County, Maryland. Philadelphia, PA: G. M. Hopkins, 1877.

Baltimore County Historic Inventory.

Brooks, Neal A. and Eric G. Rockel. A History of Baltimore County. Towson, MD: Friends of the Towson Library, Inc., 1979.

Map of Baltimore County. Philadelphia, PA: G. W. Bromley, 1915.

Scharf, J. Thomas. History of Baltimore City and County From the Earliest Period to the Present Day: Including Biographical Sketches of Their Representative Men. Philadelphia, PA: Louis H. Everts, 1881. Reprinted by Higginson Book Company, Salem, MA.

Sidney, J. C. Map of the City and County of Baltimore, Maryland, from Original Surveys. Baltimore, MD: James M. Stephens, 1850.


East Towson: Planimetric Data



RA #: 1896
 Name: House, 343 Hillen Road
 East Towson
 Baltimore County



Prepared by:
 Baltimore County Office of Planning
 301 Bosley Avenue
 Towson, Maryland 21204
 June, 2001




Legend

- Study Area Boundary
- Paved Roads
- Unpaved Roads
- Paved Parking / Driveways
- Hydrographic Features
- Buildings
- Vegetation

Data Sources:
 Planimetric Data: Baltimore County DTI GIS Services Unit (1:2400)
 Parcel Boundaries: Baltimore County DTI GIS Services Unit (1:2400)
 Study Area: Baltimore County Office of Planning (1:2400)
 Coordinate System:
 - Maryland State Plane: NAD83/2011 Horizontal Datum
 - Elevations in Feet: NAVD83 Vertical Datum
 Date of Data Capture: March 1995
 Scale of Data Capture: 1" = 100'

BA-1096
 East Towson
 Towson, Maryland
 Towson USGS Quad Map
 Baltimore County



(BALTIMORE WEST)
 5662' SW

Mapped by the Army Map Service
 Edited and published by the Geological Survey
 Control by USGS, USC&GS, USCE, and Maryland
 Bureau of Control Surveys and Maps


Culture and drainage in part compiled from aerial photographs
 taken 1943. Topography by planetable surveys 1944
 Culture revised by the Geological Survey 1957

Polyconic projection. 1927 North American datum
 10,000-foot grid based on Maryland coordinate system
 1000-metre Universal Transverse Mercator grid ticks,
 zone 18, shown in blue

Red tint indicates areas in which only
 landmark buildings are shown

Revisions shown in purple compiled by the Geological Survey from
 aerial photographs taken 1966 and 1974. This information not
 field checked

Purple tint indicates extension of urban areas



UTM GRID AND 1974 MAGNETIC NORTH
 DECLINATION AT CENTER OF SHEET



BA-1096

HOUSE, 343 HILLEN ROAD

BALTIMORE COUNTY, MD

TRAILERIES

10/2001

MD-SHPO

SOUTHEAST CORNER

1 S13



BA-1096

HOUSE, 313 HILLEN ROAD

BALTIMORE COUNTY, MD

TRAILERIES

LD/2001

MD-SHPD

SOUTHWEST CORNER

2 #13



BA-1096

HOUSE, 343 HILLEN ROAD

BALTIMORE COUNTY, MD

TRAILERIES

10/2001

MD-SHPD

NORTHEAST CORNER

3 of 13



BA-1096

343 HILLEN ROAD

BALTIMORE COUNTY, MD

TRACERIES

9/2002

MD SHPO

HOUSE, NORTH ELEVATION

4 OF 13



BA-1096

343 HILLEN ROAD

BALTIMORE COUNTY, MD

TRACERIES

9/2002

MD SHPO

FIRST FLOOR LIVING ROOM, VIEW LOOKING SOUTHWEST

5 OF 13



BA-1096

343 HILLEN ROAD

BALTIMORE COUNTY, MD

TRACERIES

9/2002

MD SHPO

FIRST FLOOR STAIR, VIEW LOOKING NORTH

6 OF 13



BA-1096

343 HILLEN ROAD

BALTIMORE COUNTY, MD

TRACERIES

9/2002

MD SHPO

STAIR, VIEW LOOKING SOUTH

7 OF 13



BA-1096

343 HILLEN ROAD

BALTIMORE COUNTY, MD

TRACERIES

9/2002

MD SHPO

FIRST FLOOR DINING ROOM, VIEW LOOKING SOUTHWEST

8 OF 13



BA-1096

343 HILLEN ROAD

BALTIMORE COUNTY, MD

TRACERIES

9/2002

MD SHPO

FIRST FLOOR DINING ROOM, VIEW LOOKING NORTHWEST

9 OF 13



BA-1096

343 HILLEN ROAD

BALTIMORE COUNTY, MD

TRACERIE S

9/2002

MD SHPO

FIRST FLOOR UTILITY ROOM, VIEW LOOKING SOUTH/

10 OF 13



BA-1096

343 HILLEN ROAD

BALTIMORE COUNTY, MD

TRACERIES

9/2002

MD SHPO

FIRST FLOOR KITCHEN, VIEW LOOKING EAST

11 OF 13



BA-1096

343 HILLEN ROAD

BALTIMORE COUNTY, MD

TRACERIES

9/2002

MD SHPO

FIRST FLOOR BEDROOM, VIEW LOOKING SOUTH.

12 OF 13



BA-1096

343 HILLEN ROAD

BALTIMORE COUNTY, MD

TRACERIES

9/2002

MD SHPD

FIRST FLOOR DEN, VIEW LOOKING SOUTH

13 OF 13

MARYLAND HISTORICAL TRUST

INVENTORY FORM FOR STATE HISTORIC SITES SURVEY

1 NAME

HISTORIC

TAYLOR HOUSE

AND/OR COMMON

2 LOCATION

STREET & NUMBER

343 Hillen Road

CITY, TOWN

Towson

VICINITY OF Baltimore

CONGRESSIONAL DISTRICT

STATE

Maryland 21204

COUNTY

3 CLASSIFICATION

CATEGORY

DISTRICT
 BUILDING(S)
 STRUCTURE
 SITE
 OBJECT

OWNERSHIP

PUBLIC
 PRIVATE
 BOTH

PUBLIC ACQUISITION

IN PROCESS
 BEING CONSIDERED

STATUS

OCCUPIED
 UNOCCUPIED
 WORK IN PROGRESS

ACCESSIBLE

YES: RESTRICTED
 YES: UNRESTRICTED
 NO

PRESENT USE

AGRICULTURE MUSEUM
 COMMERCIAL PARK
 EDUCATIONAL PRIVATE RESIDENCE
 ENTERTAINMENT RELIGIOUS
 GOVERNMENT SCIENTIFIC
 INDUSTRIAL TRANSPORTATION
 MILITARY OTHER:

4 OWNER OF PROPERTY

NAME

Telephone #:

STREET & NUMBER

CITY, TOWN

VICINITY OF

STATE, zip code

5 LOCATION OF LEGAL DESCRIPTION

COURTHOUSE,
 REGISTRY OF DEEDS, ETC.

Liber #:

Folio #:

STREET & NUMBER

CITY, TOWN

STATE

6 REPRESENTATION IN EXISTING SURVEYS

TITLE

DATE

FEDERAL STATE COUNTY LOCAL

DEPOSITORY FOR
 SURVEY RECORDS

CITY, TOWN

STATE

7 DESCRIPTION

CONDITION

<input type="checkbox"/> EXCELLENT	<input type="checkbox"/> DETERIORATED
<input type="checkbox"/> GOOD	<input type="checkbox"/> RUINS
<input checked="" type="checkbox"/> FAIR	<input type="checkbox"/> UNEXPOSED

CHECK ONE

UNALTERED
 ALTERED

CHECK ONE

ORIGINAL SITE
 MOVED DATE _____

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

343 Eudowood Lane.

Shown as M. Taylor's house in 1898 atlas. Frame, vernacular style house, two storeys, gable roof, grey rubber shingles, two bays wide; wing on east. Fair condition.

CONTINUE ON SEPARATE SHEET IF NECESSARY

8 SIGNIFICANCE

PERIOD	AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW			
<input type="checkbox"/> PREHISTORIC	<input type="checkbox"/> ARCHEOLOGY-PREHISTORIC	<input type="checkbox"/> COMMUNITY PLANNING	<input type="checkbox"/> LANDSCAPE ARCHITECTURE	<input type="checkbox"/> RELIGION
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> ARCHEOLOGY-HISTORIC	<input type="checkbox"/> CONSERVATION	<input type="checkbox"/> LAW	<input type="checkbox"/> SCIENCE
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> AGRICULTURE	<input type="checkbox"/> ECONOMICS	<input type="checkbox"/> LITERATURE	<input type="checkbox"/> SCULPTURE
<input type="checkbox"/> 1600-1699	<input type="checkbox"/> ARCHITECTURE	<input type="checkbox"/> EDUCATION	<input type="checkbox"/> MILITARY	<input type="checkbox"/> SOCIAL/HUMANITARIAN
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> ART	<input type="checkbox"/> ENGINEERING	<input type="checkbox"/> MUSIC	<input type="checkbox"/> THEATER
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> COMMERCE	<input type="checkbox"/> EXPLORATION/SETTLEMENT	<input type="checkbox"/> PHILOSOPHY	<input type="checkbox"/> TRANSPORTATION
<input type="checkbox"/> 1900-	<input type="checkbox"/> COMMUNICATIONS	<input type="checkbox"/> INDUSTRY	<input type="checkbox"/> POLITICS/GOVERNMENT	<input type="checkbox"/> OTHER (SPECIFY)
		<input type="checkbox"/> INVENTION		

SPECIFIC DATES Before 1898

BUILDER/ARCHITECT

STATEMENT OF SIGNIFICANCE

MAJOR BIBLIOGRAPHICAL REFERENCES

CONTINUE ON SEPARATE SHEET IF NECESSARY

10 GEOGRAPHICAL DATA

ACREAGE OF NOMINATED PROPERTY _____

VERBAL BOUNDARY DESCRIPTION

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE COUNTY

STATE COUNTY

11 FORM PREPARED BY

NAME / TITLE

Mr. John McGrain

ORGANIZATION

Baltimore County Office of Planning & Zoning

DATE

5/78

STREET & NUMBER County Courts Bldg.

TELEPHONE

401 Bosley Avenue

823-1849

CITY OR TOWN

Towson

STATE

Maryland 21204

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature, to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 Supplement.

The Survey and Inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

RETURN TO: Maryland Historical Trust
The Shaw House, 21 State Circle
Annapolis, Maryland 21401
(301) 267-1438