

CE-22

For NCRS use only

received
date entered

30

National Register of Historic Places Inventory—Nomination Form

See instructions in *How to Complete National Register Forms*
Type all entries—complete applicable sections

1. Name

historic St. Stephens Episcopal Church

and or common

2. Location

street & number Maryland Route 282 not for publication

city, town Earleville vicinity of congressional district First

state Maryland code 24 county Cecil code 015

3. Classification

Category	Ownership	Status	Present Use	
<input type="checkbox"/> district	<input type="checkbox"/> public	<input checked="" type="checkbox"/> occupied	<input type="checkbox"/> agriculture	<input type="checkbox"/> museum
<input checked="" type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> unoccupied	<input type="checkbox"/> commercial	<input type="checkbox"/> park
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> work in progress	<input type="checkbox"/> educational	<input type="checkbox"/> private residence
<input type="checkbox"/> site	Public Acquisition	Accessible	<input type="checkbox"/> entertainment	<input checked="" type="checkbox"/> religious
<input type="checkbox"/> object	<input type="checkbox"/> in process	<input checked="" type="checkbox"/> yes: restricted	<input type="checkbox"/> government	<input type="checkbox"/> scientific
	<input type="checkbox"/> being considered	<input type="checkbox"/> yes: unrestricted	<input type="checkbox"/> industrial	<input type="checkbox"/> transportation
	N/A	<input type="checkbox"/> no	<input type="checkbox"/> military	<input type="checkbox"/> other:

4. Owner of Property

name St. Stephens Church, Attn: Mr. Preston Leighton

street & number 35 Snug Harbor Way

city, town Earleville vicinity of state Maryland 21919

5. Location of Legal Description

courthouse, registry of deeds, etc. Clerk of the Circuit Court

street & number Cecil County Courthouse

city, town Elkton, state Maryland

6. Representation in Existing Surveys

title Maryland Historical Trust
Historic Sites Survey has this property been determined eligible? yes no

date 1980 federal state county local

depository for survey records Maryland Historical Trust

city, town Annapolis state Maryland

Condition		Check one	Check one
excellent	<input type="checkbox"/> deteriorated	<input type="checkbox"/> unaltered	<input checked="" type="checkbox"/> original site
<input checked="" type="checkbox"/> good	<input type="checkbox"/> ruins	<input checked="" type="checkbox"/> altered	<input type="checkbox"/> moved date _____
<input type="checkbox"/> fair	<input type="checkbox"/> unexposed		

Describe the present and original (if known) physical appearance

DESCRIPTION SUMMARY

The single story rectangular stuccoed brick main block, three bays by one room, rests on a partially excavated fieldstone foundation and is covered by steeply pitched slate roof. Attached to the east gable end is a shorter single story one bay by one room rectangular block which contains the altar. A shed roof extends off the altar room's south side for the sacristy. The west gable end dominates the church structure with its four story bell tower with broach spire and patterned slate roof. The exterior surfaces of the church are uniformly covered with stucco that have been scored to imitate ashlar masonry. The Gothic Revival structure was built in 1870-1874 but incorporated the old walls of the earlier church of 1824 and 1735. A graveyard, which corresponds to the church's long history, surrounds the structure.

GENERAL DESCRIPTION

Saint Stephen's Church of North Sassafras Parish stands immediately north of Earleville, Maryland on the east side of Maryland Route 282. Earleville is a centrally located farming community in Cecil County's rural southernmost tidewater lands known as Sassafras Neck. The Gothic Revival church has a western exposure with the main gable on the east/west axis.

The west facade tower is flanked by two lancet windows that are bordered with raised brick surrounds. The sides of the surrounds have a crenelated brick pattern below the Gothic arch. The tower contains the main entrance which is naturally a Gothic arched opening with double doors with applied moldings. Directly above the entrance is a stained glass window that repeats the same Gothic arch and crenelated surround. Two openings exist between the previous window and tower room. These openings are rectangular louvered vents complete with crenelated surrounds. Moving upward, the next story is the bell room which has another Gothic arched opening which is surrounded by a red brick frame with corbelled brick arcade above the opening and a single brick crenelation below the frame. All the previously mentioned surrounds are plain red brick set against the stuccoed surface. The north and south sides of the tower are basically the same but the number of window openings differ. The first and third floors have a singular rectangular opening while the second floor has a larger Gothic arched opening. The fourth story tower room openings are the same as the main facade. The four sides of the steeple base have small triangular shaped ventilators which add to smoothing the transition between the square tower and octagonal steeple. The steeple is topped by a gold cross.

The north and south sides of the main block have three evenly spaced Gothic arched windows with the same crenelated brick surrounds and stained glass windows, which were replaced in 1963.

The east gable end is primarily covered with the altar room. A single flue brick stove stack rises against the northeast corner of the main block. The altar room has a Gothic arched opening on the north and east sides. The east end window is a large tri-partite Gothic window. The south side contains the scristy which has a Gothic arched door opening on its south wall.

8. Significance

CE-22

Period	Areas of Significance--Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input type="checkbox"/> community planning	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> education	<input type="checkbox"/> military	<input type="checkbox"/> social/
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	<input type="checkbox"/> humanitarian
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> commerce	<input type="checkbox"/> exploration/settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> theater
<input type="checkbox"/> 1900-	<input type="checkbox"/> communications	<input type="checkbox"/> industry	<input type="checkbox"/> politics/government	<input type="checkbox"/> transportation
		<input type="checkbox"/> invention		<input type="checkbox"/> other (specify)

Specific dates 1860-1870 Builder Architect Thomas Dixon, Architect

Statement of Significance (in one paragraph) Applicable Criteria: B, C

SIGNIFICANCE SUMMARY

The significance of St. Stephen's Church of North Sassafras Hundred in southern Cecil County is derived primarily from the architectural character of the structure. As a church remodeled in a highly ornamented but conservative interpretation of the High Victorian style, the building embodies the distinctive features of a period and type of architecture that, although popular in the United States in the 1870s and 1880s was not commonly used in the rural regions of Maryland, particularly those sections of the state which were a substantial distance from an urban center. The important features of St. Stephen's that characterize it are a stuccoed brick structure with exaggerated brick decoration surrounding the openings and delineating the bell tower and an interior dominated by exposed scissors trussing and Gothic arch motifs. The building achieves additional significance from association with Thomas Dixon, a Baltimore architect responsible for the design. St. Stephen's is the only known documented example of Dixon ecclesiastical designs located outside of a major urban center.

HISTORY AND SUPPORT

St. Stephen's Church of North Sassafras Hundred was organized in 1692 and represents a continual Episcopal congregation in Cecil County and the religious persuasion of most of the county's earliest residents. North Sassafras was one of the original parishes designated by a Maryland Act of Assembly. The history of the present church building began in the mid 1860s with the discussion of rebuilding and expanding an 1824 structure, which measured 30 x 40, with Thomas Dixon a Baltimore architect. The vestry minutes document the complete renovation of the earlier building.

". . . the roof and ceiling are to be taken off the present building, all of the doors and windows with their frames are to be taken out, the top part of the present walls are to be taken down to the height shown by the drawings (location unknown), the end wall is to be taken down and the present stairs and fittings removed. The new additions are to be made agreeable to the dimensions shown figured on the drawings . . ."

The new church was consecrated Friday, May 8, 1874 by Henry C. Lay, Bishop of Easton. The 1860-1870 church has incorporated into its walls the 1824 brick building which replaced the second structure that was built around 1735. The first church is recorded as being consecrated on March 25, 1706. The events associated with the church are countless but one of the more prominent occasions was the June 22, 1834 ordination of the Reverend William Douglas, the fifth black to receive Anglican Orders in America and the first to receive them south of the Mason-Dixon line.

United States Department of the Interior
 Heritage Conservation and Recreation Service

National Register of Historic Places
 Inventory—Nomination Form

For HCRS use only
received
date entered

Continuation sheet Item number 8 Page 2

St. Stephens Episcopal Church
 Earleville vicinity
 Cecil County, Maryland

HISTORY AND SUPPORT (Continued)

Thomas Dixon practiced in Baltimore in the second half of the nineteenth century. For some years he was in partnership with his brother James. The Dixons were responsible for the designs of several buildings in Baltimore, particularly several lavishly decorated Gothic influenced churches. Three more worthy examples of their work are the Mount Vernon Methodist Church located in the Mount Vernon National Historic Landmark District, the Mount Washington Presbyterian Church, and Westminster Church on Lafayette Square. The brothers also designed a number of Victorian houses in Mount Washington.

Throughout rural Maryland, the standard church structure erected in the late nineteenth century was a simple frame or brick building with Gothic decorative detailing. Rarely did these buildings receive such a concerted effort to be as stylish as the St. Stephens structure, particularly for a building of such small scale.

9. Major Bibliographical References

SLE CONTINUATION SHEET #3.

10. Geographical Data

Acreeage of nominated property 3.4 acres

Quadrangle name Earleville

Quadrangle scale 1:24,000

UMT References

A	1 8	4 2 0 9 6 0	4 3 6 4 1 8 0
	Zone	Easting	Northing

B				
	Zone	Easting	Northing	

C				
	Zone	Easting	Northing	

D				
	Zone	Easting	Northing	

E				
	Zone	Easting	Northing	

F				
	Zone	Easting	Northing	

G				
	Zone	Easting	Northing	

H				
	Zone	Easting	Northing	

Verbal boundary description and justification

For boundary description, see Continuation Sheet #3

For boundary justification, see Continuation Sheet #1

List all states and counties for properties overlapping state or county boundaries

state	code	county	code
N/A			

state	code	county	code

11. Form Prepared By

name/title Paul B. Touart, Historic Sites Surveyor

organization	<u>Cecil County Committee of the Maryland Historical Trust</u>	date	<u>11/24/80</u>
--------------	--	------	-----------------

street & number	<u>Cecil County Courthouse</u>	telephone	<u>(301)398-0200 ext. 150</u>
-----------------	--------------------------------	-----------	-------------------------------


city or town	<u>Elkton</u>	state	<u>Maryland 21921</u>
--------------	---------------	-------	-----------------------

12. State Historic Preservation Officer Certification

The evaluated significance of this property within the state is:

national
 state
 local

As the designated State Historic Preservation Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the Heritage Conservation and Recreation Service.

State Historic Preservation Officer signature		date	<u>3-18-82</u>
---	---	------	----------------

title	<u>STATE HISTORIC PRESERVATION OFFICER</u>	date	
-------	--	------	--

For HCRS use only

I hereby certify that this property is included in the National Register

date

Keeper of the National Register

Attest:

date

Chief of Registration

United States Department of the Interior
 Heritage Conservation and Recreation Service

National Register of Historic Places
 Inventory—Nomination Form

CE-22

For HCERS use only

received

date entered

Continuation sheet

Item number

9 and 10

Page

3

St. Stephens Episcopal Church
 Earleville vicinity
 Cecil County, Maryland

BIBLIOGRAPHY

St. Stephen's Vestry Books 1840-1886

Biographical Notes on Dixon on file at Baltimore Commission for Historic and
 Architectural Preservation, City Hall, Baltimore, Maryland

Maryland Historical Trust Historic Sites Inventory: Cecil County (CE-22.
 Paul Touart, suveyor. 1980.

VERBAL BOUNDARY DESCRIPTION


Beginning at a point at the intersection of old Maryland Route 282 and Glebe
 Road and running along said Glebe Road in a northeasterly direction for 300' to
 another intersection of parsonage driveway and Glebe Road and running in a southeasterly
 direction for another 300' to a point along the back edge of the church yard, thence in
 a southwesterly direction along the back edge of the church yard for 450' to a point
 along a common southern boundary line of parcel number 50, thence in a northwesterly
 direction along said common boundary and intersecting the curve in Route 282 for
 about 375' to a place of beginning being 3/5 of parcel number 49 as shown on Cecil
 County Tax Map number 56 and containing approximately 3.4 acres.



St. Stephens
Episcopal Church
Cecil Co
A 18/420760/4364780

43647

CE-22



St. Stephens
Episcopal Church
Cecil Co
A 18/420960/4364150

43641

CE-22

0806224508

Form 10-445
(5/62)

HISTORIC AMERICAN BUILDINGS SURVEY
INVENTORY **CE-22**

1. STATE Maryland
 COUNTY Cecil County
 TOWN Earleville VICINITY
 STREET NO. Rt. 283 and Glebe Rd.

ORIGINAL OWNER North Sasafra's Parish
 ORIGINAL USE Church Religious
 PRESENT OWNER Vestry of St. Stephens Church
 PRESENT USE Religious
 WALL CONSTRUCTION Brick
 NO. OF STORIES 1

2. NAME St. Stephens Church

DATE OR PERIOD 1874
 STYLE Gothic Revival
 ARCHITECT
 BUILDER

3. FOR LIBRARY OF CONGRESS USE

OPEN TO PUBLIC yes

4. NOTABLE FEATURES, HISTORICAL SIGNIFICANCE AND DESCRIPTION

St. Stephens Church, as it exists today, is largely the result of a major remodeling-rebuilding begun in 1870. It incorporates the walls of an earlier Church which was built in 1732 (remodeled in 1824). The present structure is of Gothic design with three lancet windows on each side being surrounded by brick quoins, set off from the yellow stucco walls (made to imitate ashlar masonry). The west facade has a tall square tower with octagonal steeple and contains four tiers of windows with the same brick quoins and stain glass. Flanking the tower are two tall narrow lancet windows with stain glass. The entrance is a double door of lancet shape on the west side of the tower.

The nave of the Church has a very steeply pitched "A" roof covered with slate. East of the nave is the sanctuary, which is lower than the nave, with a lean-to on its south side.

5. PHYSICAL CONDITION OF STRUCTURE

Endangered NO Interior Exterior good

6. LOCATION MAP (Plan Optional)



8. PUBLISHED SOURCES (Author, Title, Pages)
 INTERVIEWS, RECORDS, PHOTOS, ETC.

7. PHOTOGRAPH 2107

9. NAME, ADDRESS AND TITLE OF RECORDER

Michael Bourne
Maryland Historical Trust

DATE OF RECORD Jan. 8, 1968

SUPPLEMENTAL INFORMATION AND PHOTOGRAPHS MAY BE ADDED ON SHEET OF SAME SIZE

CE-22

585

CHARLOTTE W
DENNETT
RRC III/361
279.00A.
P 46

M 57 - P 1

P 10

P 45

HENRY W KNOCK III
NDS 21/61
1567A.
P. 11

P 41

P 68

P 48

GLEBE

582

57

P 50

P 51

P 7

P 1

P 1

P 1

P 1

P 1

P 1

P 1

P 1

P 1

P 1

M 57 - P 3


EARLEVILLE QUADRANGLE
CECIL COUNTY TAX MAP

NO. 56

ST. STEPHENS EPISCOPAL CHURCH

CE-22


CE-22



GRAVEYARD

UNMEASURED
FLOOR PLAN
AND SECTION





CE-22

St. Stephen's church

Earleville

OUTSIDE Looking AT Front



OUTSIDE - Showing SOUTH SIDE

CE-22

St. Stephen's church

Earleville



CE-22
St. Stephen's church
Earleville

OUTSIDE - Looking AT NORTH SIDE

1907

St. Paul's

St. Paul's Episcopal Church




CE-22

St. Stephen's church

Earleville

INTERIOR - Looking AT ALTAR.




Interior - from Loft Looking AT ALTAR AREA

CE-22

St Stephen's church

Earleville



INTERIOR - Looking AT Choir Loft.

CE-22

St. Stephen's Church

Earleville




Interior - looking left to front

CE-22

St. Stephen's Church

Earleville




Interior - Looking Down from "loft" AT SOUTH WALL

CE-22

St. Stephen's church

Earleville




Interior- LOOK AT NORTH WALL

CE 22

St. Stephen's church

Earleville



INTERIOR - LOOKING AT SOUTH WALL

CE-22

St. Stephen's Church

Earleville



St. Stephens
Earleville, Md.
Southwest Elevation
MOB/1968
NEG - MD. Hist Trust

CE - 22



St. Stephen's C-22



CE-22 St. Stephens

1/68 NAB



CE-22

St Stephen's church

Earleville



St. Stephens
Cecil Co.

MOA

CE-22

CE-22

1968

045 J