

**MARYLAND HISTORICAL TRUST
NR-ELIGIBILITY REVIEW FORM**

NR Eligible: yes
no

Property Name: Leister Farm, Leisterdale Farm (modern) Inventory Number: CARR-596

Address: 701 Houcksville Road City: Hampstead Zip Code: 21074

County: Carroll USGS Topographic Map: Hampstead

Owner: Carroll J. Leister et al

Tax Parcel Number: 53 Tax Map Number: 41 Tax Account ID Number: 009082

Project: Patmos Property Agency: Federal Communications Commission

Site visit by MHT Staff: no yes Name: _____ Date: _____

Eligibility recommended Eligibility **not** recommended

Criteria: A B C D Considerations: A B C D E F G None

Is the property located within a historic district? no yes Name of district: _____

Is district listed? no yes Determined eligible? no yes District Inventory Number: _____

Documentation on the property/district is presented in:

Description of Property and Eligibility Determination: (Use continuation sheet if necessary and attach map and photo)

The Leister House, constructed in 1907, is located at the end of a long gravel driveway at 701 Houcksville Rd. in Hampstead, Maryland. This property is still in use as an active farm. The farmhouse faces north and is set in a complex of farm buildings, some of which are historic. (For the purposes of this description all directions have been squared: the façade faces slightly west of true north.) The farmhouse is a two-and-one-half story brick structure, five bays wide by two bays long, with a slate gable roof and stone foundation. The brick bond pattern is six-course American and the slate on the roof has been painted. The farmhouse consists of two separate brick buildings, the main house to the north and a smaller one-story kitchen to the south featuring an interior chimney in its eastern gable. These two buildings are connected by a wood-framed hyphen which completes the structure and gives the building a T-shape. The Leister house is a well-preserved and distinctive example of early twentieth century farmhouse construction in Carroll County, and its site and surroundings still retain a large degree of historic integrity.

The primary façade of the Leister Farmhouse features a steeply pitched cross gable with a pointed arch window and a one-story porch with turned post columns. The pitch of the cross-gable lends an air of verticality to the house not generally found in buildings of its type. All windows located in the brick structures are 1/1 with segmental arches, white wood surrounds, and stone sills. The main entrance is located in the middle bay of the primary façade and is topped by a transom light and segmental arch. The wood-framed hyphen is set back one bay and enclosed on both

MARYLAND HISTORICAL TRUST REVIEW	
Eligibility recommended <input checked="" type="checkbox"/>	Eligibility not recommended <input type="checkbox"/>
Criteria: <input type="checkbox"/> A <input type="checkbox"/> B <input checked="" type="checkbox"/> C <input type="checkbox"/> D	Considerations: <input type="checkbox"/> A <input type="checkbox"/> B <input type="checkbox"/> C <input type="checkbox"/> D <input type="checkbox"/> E <input type="checkbox"/> F <input type="checkbox"/> G <input type="checkbox"/> None
Comments: _____	
_____ Reviewer, Office of Preservation Services	_____ Date
_____ Reviewer, NR program	_____ Date

MARYLAND HISTORICAL TRUST
NR-ELIBILITY REVIEW FORM

Continuation Sheet No. 1

CARR-596

its first and second floors. The eastern façade of the hyphen has been constructed of brick. A one-story porch featuring turned post columns projects to the west and extends across the length of the kitchen. Both the north and west porches have been rebuilt but the turned post columns of the earlier porches were retained.

Supporting agricultural structures are sited around the dwelling in all directions. A timber-framed hay barn (barrack) featuring wood pegged joinery, vertical board construction, and a standing seam gable roof is located to the northwest. This structure has been covered in metal siding on two sides. A brick gabled smokehouse featuring a vertical board door surmounted by a segmental brick arch lies to the southeast with a one-story wood-framed gable roofed "woodhouse" to its south. A massive German bank barn, which probably pre-dates the house and has since been covered in red metal siding, lies to the southwest. The bank barn is surrounded by several supporting structures including a milking parlor and silos. A series of additional one-story wood framed supporting structures, constructed since 1966, are located to the south. A one-story timber-framed building with wood pegged joinery, built on a stone foundation, and now covered in red metal siding lies to the northeast of the barn.

History. The farm at 701 Houcksville Road, now known as the Leisterdale Farm, has been associated with two prominent Carroll County families since the mid-19th century or before. The property was owned by two generations of the Houck family in the 19th century. Purchased by John U. Leister in 1897, it was being farmed by two of his grandsons in 2002.

The property that now constitutes the Leisterdale Farm is part of a land grant known as Landaff that was patented in 1801, incorporating several earlier land grants. In the second quarter of the mid-19th century, the farm was part of the extensive landholdings of William Houck, a member of the family for which Houcksville is named. William Houck died on March 4, 1854, leaving a widow, Lucy Houck, and eight children. One of the children, Elias Houck, is shown as the owner of the property on the 1862 Simon J. Martenet *Map of Carroll County* and the 1877 Lake, Griffing and Stevenson *Atlas of Carroll County*.

Elias Houck owned and farmed the property until his death in 1897. It was then sold to John U. Leister at a trustees' sale held on July 24, 1897. An advertisement for the sale described the property as "improved by a two-story brick dwelling with a back building, bank barn 40 x 100 feet, dairy and other necessary farm buildings. Spring of water near the house, good orchard with a due proportion of a meadow and about 20 acres of good timber and a stream of water running through the farm. Said farm is in a high state of cultivation.... It is one of the best hay and dairy farms in this county."¹ Leister purchased the farm for \$40 an acre. The deed was dated September 9, 1897. Leister's brother, Irvin Seymour Leister, owned an adjacent farm to the southeast (CARR-586).

The farmhouse and most, if not all, of the outbuildings were constructed in the period of Leister family ownership. According to Leister family members, the Houck farmhouse was located in a hollow to the southeast of the present farmhouse site. An 1866 plat in the possession of Stuart O. Leister, co-owner of the farm, includes a small sketch of the Houck farmhouse which bears no resemblance to the present farmhouse. However, the front door of the Houck farmhouse was installed in the Leister farmhouse as the door to the basement of the main block.²

The farmhouse was built for John U. Leister (1870-1933) and his wife Emma Brillhart Leister (1875-1936). According to their grandson, Stuart O. Leister, the current resident of the farmhouse, the farmhouse was built in 1907 by local German-born builder whose last name was Lang. He said Lang had also constructed two other nearby farmhouses: a house built on the adjacent Leister farm (CARR-586) and the farmhouse owned by C. William Robinson (Carroll County Tax Map 48, Parcel 2). Bricks were brought by wagon from Westminster and the mortar was made with sand from the creek on the property.

¹ Advertisement dated June 26 in unidentified newspaper clipping in scrapbook in possession of Stuart O. Leister, co-owner of Leisterdale Farm.

² Stuart O. Leister, Interview with Andrea F. Schoenfeld, EHT Traceries, Inc., June 19, 2002.

MARYLAND HISTORICAL TRUST
NR-ELIBILITY REVIEW FORM

Continuation Sheet No. 2

CARR-596

John U. Leister was described in his obituary in 1933 as "well-known and one of Hampstead district's most prominent farmers."³ In addition to farming, he was involved in a number of local businesses, serving on the board of directors of the First National Bank of Hampstead, the Hampstead Implement and Supply Company, the Hampstead Fertilizer Company and the Hampstead Milling Company. He was also a founding member of St. Mark's Lutheran Church in Hampstead.

According to Leister family tradition, John U. Leister built the extant older buildings on the farm including the bank barn, "barrack" (hay barn), smoke house, woodshed, and what is now known as the tractor shed. The tenant house was built in the early 1920s for the eldest son. As the bank barn is approximately the size of the barn described in the 1897 advertisement for the property, it is probable that at least the foundation predates the Leister ownership of the farm.

John U. Leister died in 1933 and his wife died in 1936. In August 1936, one of their sons, Sterling Jacob Leister, bought the farm and operated it with his wife Addie Virginia (Cullison) Leister. In March 1966, their sons Stuart O. Leister and Carroll Jacob Leister assumed the management of the farm. Sterling Jacob Leister served on the Carroll Soil Conservation District Board. He began contoured farming in 1948 and no-till farming in 1962. Stuart O. Leister has also served on the Carroll Soil Conservation District Board. The farm was operated as a dairy farm until 1996. The principal crops have been hay, soybeans and corn. Leisterdale Farm was entered in the Maryland Department of Agriculture Century Farm Program in 1998. The Century Farm Program recognizes farms that have been operated continuously by one family for 100 years or more. The Leisterdale Farm is one of nine Carroll County Century Farms out of a total of 112 Maryland farms that had been recognized by the program by 2002.

Significance. The farmhouse is significant as an example of German-influenced Carroll County farmhouse construction at the beginning of the 20th century. The outbuildings, the earliest of which may date from or include elements of 19th century Houck family farm buildings, include a bank barn, barrack (hay barn), smoke house, wood shed, tractor shed, a tenant house, and an early milking parlor which replaced a dairy building.

The Leisterdale farmhouse and its outbuildings illustrate more than a century of farming in Carroll County. While typical of the area in terms of size and products, it was also regarded within the community as a productive, well-run farm, as indicated by the 1897 advertisement, and 1933 obituary. The various outbuildings reflect agricultural practices and technologies spanning a century. The bank barn, designed for livestock and hay storage, almost certainly dates, at least in part, from the period of Houck ownership. It is typical of 19th century barns of the area. The adjacent building to the northeast of the barn, currently used as a tractor shed, was constructed at some time before the house and was used to house the workmen who built the house, according to Leister family tradition. The smokehouse and woodshed adjacent to the farmhouse are probably contemporaneous with it. The wood frame "barrack" northwest of the farmhouse was designed for hay storage at a time when horses were still used to haul hay. The rectangular building is bisected by a wagon way. The horse-drawn hay wagon entered through a central door on one side, the loose hay was unloaded into the lofts at either end of the building and the horse and wagon exited through the central door opposite the entrance. Later in the year, the hay was loaded onto wagons from the loft and hauled to Baltimore.

Later farm buildings illustrate 20th century developments in farming. About 1952, the dairy was replaced with a milking parlor, one of the first in Maryland, according to family tradition. (In a milking parlor, the cow goes to the milking machine instead of being milked while standing in a stanchion.) Early silos were replaced with more modern ones. Other buildings dating from the second half of the 20th century include a loafing shed to house cows in winter after they had been milked, and calf and steer sheds, a workshop and a trailer to provide additional housing.

³ Kenneth W. Betsh, ed., "Descendents of John Nicholas Leister 1731-1805, Carroll County, Maryland." Reading, Pennsylvania: Kenneth W. Betsh, 1994: 134 (in collection of the Historical Society of Carroll County).

MARYLAND HISTORICAL TRUST
NR-ELIBILITY REVIEW FORM

Continuation Sheet No. 3

CARR-596

Eligibility. The Leister Farm at 701 Houcksville Road, Hampstead does not meet National Register Criterion B for properties associated with individuals significant in our past. Criterion D, information potential, was not evaluated for this study but preliminary research did not produce any evidence that the farm is likely to yield information important in history or prehistory.

The Leister Farm is eligible to be nominated to the National Register under Criterion A as a property associated with a historic trend that made a significant contribution to the development of a community. Located in a rural community with a largely agricultural economy, the Leister farmhouse, together with its outbuildings, is strongly associated with the agricultural history of eastern Carroll County and exemplifies developments and changes in agricultural practices over the course of the 20th century. Based on Criterion A, the Leister Farm is National Register-eligible.

The Leister farmhouse and its historic farm outbuildings are also eligible under Criterion C as significant for their physical design and construction, embodying the distinctive characteristics of its type and period. The two-and-one-half story, gable-roof farmhouse, with its symmetrical main façade and cross gable, is an excellent example of the typical late 19th and early 20th century farmhouses in this part of Carroll County and reflects the German heritage of the community. The historic outbuildings illustrate construction techniques used in agricultural buildings at the turn of the 20th century in Carroll County and also reflect local building traditions. The circa-1952 milking parlor is an early example of a building form that developed in response to post World-War II innovations in dairy practices. Based on Criterion C, the Leister Farm is National Register-eligible.

Laura H. Hughes, Architectural
Historian

Prepared by: Andrea F. Schoenfeld, Historian

Date Prepared: June 2002

LEISTER FARM HOUSE

RESOURCE SKETCH MAP


HOUCKSVILLE ROAD

701 HOUCKSVILLE ROAD
HAMPSTEAD, MD
CARR-596
CARROLL COUNTY



CARR-596

*ACTUAL LENGTH OF DRIVEWAY
GREATER THAN SHOWN




3653 II NW
(MANCHESTER)

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

HAMPSTEAD QUADRANGLE
MARYLAND
7.5 MINUTE SERIES (TOPOGRAPHIC)



76°52'30" 341000m.E. 342 50' 343
37°30" HANOVER PA. 15 MI. MANCHESTER 2.8 MI.



LEISTER
FARM HOUSE
701 HUCKSVILLE
ROAD,
HAMPSTEAD,
CARROLL
COUNTY,
MD
CARR-596

TAPSCO 3.6 MI.
SVILLE 0.5 MI.



CARR-596

Leister Farm

701 Houchsville Road, Hampstead

Carroll County, Maryland

EHT Traceries

06/2002

MD SHPO

Looking south towards Leister Farm

to farm house, machinery shed (at end of drive), barn, horse barn
with tractor shed in foreground, fire shed, silos Photo 1 of 12



CARR-596

Leister Farm

701 Houchesville Road, Hampstead

Carroll County, MD

EHT Traceries

06/2002

MD SHPO

North elevation

Photo 2 of 12



CARR - 596

Leister Farm

701 Houchsville Rd, Hampstead

Carroll County, MD

EHT Traceries

06/2002

MD SAPO

Northwest corner

Photo 3 of 12



Carr-596

Leister Farm

701 Houchesville Road, Hampstead

Carroll County, MD

EHT Traceries

06/2002

MD SH PO

west elevation

Photo 4 of 12



CARR-596

Leister Farm

701 Houchsville Road, Hampstead

Carroll County, MD

EHT Traceries

06/2002

MD SHPO

west elevation - detail

Photo 5 of 12



CARR-596

Leister Farm

701 Houcksville Rd, Hampstead

Carroll County MD

EHT Traceries

06/2002

MD SHPO

South elevation

Photo 6 of 12



CARR - 596

Leister Farm

701 Houchesville Rd, Hagerstown

Carroll County MD

EHT Traces

MD SHPO

east elevation

Photo 7 of 12



CARR-596

Leister Farm

701 Houcksville Road, Hampstead

Carroll County, MD

EHT Traceries

06/2002

MD SHPO

Smokehouse, Western Elevation (Primary facade)

Photo 8 of 12



CARR-596

Leister Farm

701 Houcksville Road, Hampstead

Carroll County, MD

EHT Traverses

06/2002

MD SHPO

Barrick - Northern Elevation

Photo 9 of 12



CARR-596

Leister Farm

701 Hucksville Road, Hampstead

Carroll County, MD

EHT Traceries

06/2002

MD SHPO

Barrick - Southwestern Corner

Photo 10 of 12



CARR-596

Leister Farm

701 Hucksville Road, Hampstead

Carroll County, MD

EHT Tracings

06/2002

MD SHPO

Machinery Shed, Milking Parlor, Bank Barn, Tractor Shed
(from left to right) - Northeastern Elevation

Photo 11 of 12



CARR-596

Leister Farm

701 Houcksville Road, Hampstead

Carroll County, MD

EHT Traverses

06/2002

MD SHPO

Bank Barn Southeastern Corner

Photo 12 of 12

MARYLAND HISTORICAL TRUST
NR-ELIGIBILITY REVIEW FORM

NR Eligible: yes
no

Property Name: Houck/Leister Residence Inventory Number: CARR-596

Address: 701 Houcksville Road City: Hampstead Zip Code: 21074

County: Carroll USGS Topographic Map: Hampstead

Owner: Carroll Leister etal.

Tax Parcel Number: 41 Tax Map Number: 53 Tax Account ID Number: 08-009082

Project: MD 30 Hampstead Agency: SHA

Site visit by MHT Staff: no yes Name: _____ Date: _____

Eligibility recommended Eligibility not recommended

Criteria: A B C D Considerations: A B C D E F G None

Is the property located within a historic district? no yes Name of district: _____

Is district listed? no yes Determined eligible? no yes District Inventory Number: _____

Documentation on the property/district is presented in: MHT Inventory files

Description of Property and Eligibility Determination: *(Use continuation sheet if necessary and attach map and photo)*

The Leister House (a.k.a. Elias Houck Residence) was determined eligible for the National Register of Historic Places in 1979 under Criterion C for the architecture of the main dwelling and the barn (hay barrack), according to the significance statement (MHT form CARR-596, 1979). The dwelling is significant as a distinctive example of the form commonly used in Maryland rural domestic vernacular architecture from the mid-nineteenth to early twentieth centuries. Its massive brick construction and pronounced verticality set it apart from others of its type. It meets the requirements of Criterion C for listing in the Register.

It is also significant as an intact farmstead whose contributing elements, spanning the late nineteenth through the middle of the twentieth century, have considerable architectural merit. The farm also has great integrity and conveys a strong association with the agrarian history of Carroll County. It has been owned and farmed by three generations of the Leister family, the first generation of which arrived from Germany and built all but three of the pre-1950 structures on the site which contribute to its significance.

Prepared by: Rita M. Suffness

Date Prepared: October 3, 2001

MARYLAND HISTORICAL TRUST REVIEW	
Eligibility recommended <input checked="" type="checkbox"/>	Eligibility not recommended <input type="checkbox"/>
Criteria: <input type="checkbox"/> A <input type="checkbox"/> B <input checked="" type="checkbox"/> C <input type="checkbox"/> D	Considerations: <input type="checkbox"/> A <input type="checkbox"/> B <input type="checkbox"/> C <input type="checkbox"/> D <input type="checkbox"/> E <input type="checkbox"/> F <input type="checkbox"/> G <input type="checkbox"/> None
Comments: _____	
<u>Andrew Levin</u>	<u>01/03/02</u>
Reviewer, Office of Preservation Services	Date
<u>(Signature)</u>	<u>2/7/02</u>
Reviewer, NR program	Date

200104252

**Addendum to
MHT State Historic Sites Survey Inventory Form
CARR 596**

1. Name - Houck/Leister Residence

2. Location – 702 Houcksvile Road
Hampstead, MD
Carroll County
7th Congressional District

3. Classification

Category - buildings
Ownership – private
Public Acquisition - not applicable
Status - occupied
Accessible - restricted to exterior

4. Owner of Property

Carroll Leister, etal.

5. Location of Legal Description

Carroll County Tax Assessor
Winchester Exchange Bldg. - Main Street
Westminster, Maryland

6. Representation in Existing Historical Surveys

Documented by MHT historic sites surveyors in 1979 as CARR-596. Since that time changes have occurred to the property. It is no longer utilized as a dairy farm, as the current owners abandoned that practice in 1995. In addition, many non-contributing buildings have been constructed in the last few decades, including a pre-fabricated vinyl-sided dwelling. Although these relate to agricultural use of the farm, they do not contribute to its significance as a late nineteenth and early twentieth century farm because, with their modern materials and construction, they do not convey the same association with the past as do the original buildings.

**Addendum to
MHT State Historic Sites Survey Inventory Form
CARR 596
Page 2**

7. Description

Condition - Good
Altered
Original Site
Present Use - agricultural

Summary paragraph:

The farm is composed of ca. 16 buildings, with ca. six dating to the period that John and Anna Leister improved the property (1916-1936). These are the large, two and one-half story brick dwelling, constructed in 1916, with attached summer kitchen, meat house, wood house, garage, and tenant house (CARR-597). Three buildings predate their acquisition in 1896 (bank barn, hay barrack and tractor shed), and the remainder of the buildings have been constructed in the last three decades (vinyl sided pre-fabricated dwelling, heifer barn, calf nursery, two machine shed, two metal silos, and oil shed).

Description

House (1917)

The house is a two-and-a-half story brick structure, as described in the 1979 inventory form (CARR-596). Tenant House is described in CARR-597.

Contributing Resources - 9

Dwelling, with attached summer kitchen, meat house, wood house, garage, and tenant house (1916-1936)

Bank barn, hay barrack and tractor shed. (Pre-1896)

These buildings may date to the ownership of the previous owner, Elias Houck (as shown in 1877 An Illustrated Atlas of Carroll County). The grandchildren of the original owners, Carroll and Stewart Leister, reported that a farmhouse existed on the property when their grandparents moved to the farm in 1896. They had come from Germany, and settled in Carroll County, near Hampstead, before buying this property in 1896. The Houck dwelling has been destroyed. (Suffness, personal communication, October 2, 2001)

**Addendum to
MHT State Historic Sites Survey Inventory Form
CARR 596
Page 3**

Non-contributing Resources – 9

Pre-fabricated dwelling, cow barn, heifer barn, calf nursery, two machine sheds, two metal silos, and oil shed (Built since 1966).

8. Significance

See MHT Inventory forms CARR-596 and CARR-597.

Evaluation:

The Leister House (a.k.a. Elias Houck Residence) was determined eligible for the National Register of Historic Places in 1979 under Criterion C for the architecture of the main dwelling and the barn (hay barrack), according to the significance statement (MHT form CARR-596, 1979). It is also significant as an intact farmstead whose contributing elements, spanning the late nineteenth through the middle of the twentieth century, have considerable architectural merit. The farm also has great integrity and conveys a strong association with the agrarian history of Carroll County. It has been owned and farmed by three generations of the Leister family, the first generation of which arrived from Germany and built all but three of the pre-1950 structures on the site which contribute to its significance.

9. Major Bibliographical References -

Dornbusch Charles H. And J.K. Heyl.

1965 *Pennsylvania German Barns*, Vol. 31 Pennsylvania Folklore Society.
Allentown, Pa.

Getty, Joe.

1987 *Carroll's Heritage*, Essays on the Architecture of a Piedmont Maryland
County. The County Commissioners of Carroll County and the Historical
Society of County Co., Westminster, MD

Glassie, Henry.

1968 *Patterns in the Material Folk Culture of the Eastern United States*.
Philadelphia: University of Pennsylvania Press.

**Addendum to
MHT State Historic Sites Survey Inventory Form
CARR 596
Page 4**

Lake , Griffing and Stevenson
1877 *An Illustrated Atlas of Carroll County, Maryland.* Lake, Griffing and
Stevenson, Philadelphia.

Lee, Carol.
1982 *Legacy of the Land. 250 Years of Agriculture in Carroll County Maryland.*
The Carroll County Commissioners. Westminster, Maryland.

Lord, Arthur.
1975 *Pre-Revolutionary Agriculture of Lancaster County, Pennsylvania. Journal*
of the Lancaster County Historical Society Vol. 79, No. 1.

Martenet, Simon J.
1861 *Martenet's Map of Carroll County, Maryland* Simon J. Martenet, Baltimore

Noble, Allen G.
1984 *Wood, Brick and Stone: The North American Settlement Landscapes -*
Volumes One and Two. Amherst, MA: University of Massachusetts Press.

Pillsbury, Richard.
1977 *Patterns in the Folk and Vernacular House Forms of the Pennsylvania*
Cultural Region. Pioneer America, Vol. 9.

Rand Mc Nally.
1916 *Hampstead, Election District No.8, Carroll Co., Md.*

Tracey, Dr. Arthur G.
1937 Land Grants of Carroll County -- Some Things We Learn from Them.
The Times, May 28th.

10. Geographical Data -

Acreage: As developed by the Maryland Historical Trust in April 11, 1985, the historic boundary of the property encompasses roughly 120 acres.

Quadrangle name - Hampstead

Quadrangle scale - 1 to 24,000

**Addendum to
MHT State Historic Sites Survey Inventory Form
CARR 596
Page 5**

Verbal Boundary Description:

The oblong configuration of the historic site boundary encompasses ca. 120 acres, and provides a buffer around the cluster of farm buildings. The MHT personnel identified the significance of the property as primarily accruing to the architecture of the main dwelling and the barn, thus a boundary providing a setting for these buildings was deemed appropriate.

11. Form Prepared By:

**Rita M. Suffness/Senior Architectural Historian
MD. State Highway Administration
707 N. Calvert St.
Baltimore, MD 21202
410-545-8561**

October, 2001

CARR-596
Houck/Leister Residence
702 Houcksvile Road
Hampstead, MD

Maryland Historic Preservation Plan Historic Contexts

Organization: **Piedmont**

Chronological/Developmental Period (s):

Agricultural-Industrial Transition A. D. 1815-1870

Industrial/Urban Dominance, A.D. 1870-1930

Modern Period, AD 1930-Present

Prehistoric/Historic Period Theme (s): **Architecture/Agricultural**

Resource Type:

Category: **Buildings**

Historic Environment: **Rural**

Historic Function (s) and Use (s):

Domestic/single dwelling/residence (C), with summer kitchen

Domestic/single dwelling/tenant house(C)

Domestic/subsistence/ garage(C)

Domestic/subsistence/meat house (C)

Domestic/subsistence/wood house (C)

Agriculture/subsistence/outbuilding/bankbarn (C)

Agriculture/subsistence/outbuilding/tractor shed (C)

Agriculture/subsistence/hay barrack (C)


Agriculture/subsistence/heifer, cow, and calf nursery (NC)

Agriculture/subsistence/ dwelling (NC)

Agriculture/subsistence/ silos, oil sheds, barns (NC)

Known Design Source: **None**

CARR-596
Houck/Leister House
Hampstead
Carroll County, MD
Site Map
1"=200'





Carr 596
Hornb - Lester
Hampden
House with

Attended Summerhitch

1911

Support OCT 2001

DET 01 116 11111



Case 596

Houch / Lester House
Hampstead

Supper M.D. S.H.A.
Oct 2001

Dwelling, ca 1911

Newcomer

002 01111 201 10 150



Cave 596

Houch / Lester House

Hampstead

Suffren, MD SHA

View to South Oct, 2001

Suffren



Case 596

Houch / Leisler House

Hampshire

Supper most A OCT. 2001

Tenant House, ca 1916.



Case 596
Houb / Lister House
Hampstead

Approved OCT 2001

UCT 01 122 HNNC 295

Non-contributing outbuildings
except for track shed
(in front of site)



Carr 596

Horch Lester Horse
Hampstead

Supper in DSHA 10/2001

Hay Barrack, ca 1911
NE Corner

DET 07 116 4444

**MARYLAND HISTORICAL TRUST
DETERMINATION OF ELIGIBILITY FORM**

Property Name: Elias Houck House/Leister Farm Inventory Number: CARR-596
 Address: _____ Historic district: yes no
 City: _____ Zip Code: _____ County: Carroll
 USGS Quadrangle(s): Hampstead
 Property Owner: _____ Tax Account ID Number: _____
 Tax Map Parcel Number(s): _____ Tax Map Number: _____
 Project: _____ Agency: _____
 Agency Prepared By: _____
 Preparer's Name: _____ Date Prepared: _____
 Documentation is presented in: _____
 Preparer's Eligibility Recommendation: Eligibility recommended Eligibility not recommended
 Criteria: A B C D Considerations: A B C D E F G
Complete if the property is a contributing or non-contributing resource to a NR district/property:
 Name of the District/Property: _____
 Inventory Number: _____ Eligible: yes Listed: yes
 Site visit by MHT Staff yes no Name: _____ Date: _____

Description of Property and Justification: *(Please attach map and photo)*
 The Elias Houck Residence is significant as a distinctive example of a form commonly used in rural domestic vernacular architecture from the mid-nineteenth to the early twentieth centuries in the eastern United States. Its massive brick construction and pronounced verticality set it apart from others of its type. The house is in good condition and the sitting retains integrity, although adjacent structures do not for the most part.

MARYLAND HISTORICAL TRUST REVIEW	
Eligibility recommended <input checked="" type="checkbox"/>	Eligibility not recommended <input type="checkbox"/>
Criteria: <u>A</u> <u>B</u> <u>C</u> <u>D</u>	Considerations: <u>A</u> <u>B</u> <u>C</u> <u>D</u> <u>E</u> <u>F</u> <u>G</u>
MHT Comments: The Houck House was Federally nominated for the National Register of Historic Places.	
Reviewer, Office of Preservation Services	Date
Beth L. Savage	Monday, June 24, 1985
Reviewer, National Register Program	Date

MARYLAND HISTORICAL TRUST

INVENTORY FORM FOR STATE HISTORIC SITES SURVEY

1 NAME

HISTORIC

Elias Houck Residence

AND/OR COMMON

Leister Farm

2 LOCATION

STREET & NUMBER

701 ~~702~~-Houcksville Road

CITY, TOWN

Hampstead

___ VICINITY OF

CONGRESSIONAL DISTRICT

STATE

Maryland

COUNTY

Carroll

3 CLASSIFICATION

CATEGORY	OWNERSHIP	STATUS	PRESENT USE
<input type="checkbox"/> DISTRICT	<input type="checkbox"/> PUBLIC	<input checked="" type="checkbox"/> OCCUPIED	<input type="checkbox"/> AGRICULTURE <input type="checkbox"/> MUSEUM
<input checked="" type="checkbox"/> BUILDING(S)	<input checked="" type="checkbox"/> PRIVATE	<input type="checkbox"/> UNOCCUPIED	<input type="checkbox"/> COMMERCIAL <input type="checkbox"/> PARK
<input type="checkbox"/> STRUCTURE	<input type="checkbox"/> BOTH	<input type="checkbox"/> WORK IN PROGRESS	<input type="checkbox"/> EDUCATIONAL <input checked="" type="checkbox"/> PRIVATE RESIDENCE
<input type="checkbox"/> SITE	PUBLIC ACQUISITION	ACCESSIBLE	<input type="checkbox"/> ENTERTAINMENT <input type="checkbox"/> RELIGIOUS
<input type="checkbox"/> OBJECT	<input type="checkbox"/> IN PROCESS	<input type="checkbox"/> YES RESTRICTED	<input type="checkbox"/> GOVERNMENT <input type="checkbox"/> SCIENTIFIC
	<input type="checkbox"/> BEING CONSIDERED	<input type="checkbox"/> YES UNRESTRICTED	<input type="checkbox"/> INDUSTRIAL <input type="checkbox"/> TRANSPORTATION
		<input checked="" type="checkbox"/> NO	<input type="checkbox"/> MILITARY <input type="checkbox"/> OTHER

4 OWNER OF PROPERTY

NAME

Telephone #:

STREET & NUMBER

CITY, TOWN

___ VICINITY OF

STATE, zip code

5 LOCATION OF LEGAL DESCRIPTIONCOURTHOUSE,
REGISTRY OF DEEDS, ETC.

Liber #:

Folio #:

STREET & NUMBER

CITY, TOWN

STATE

6 REPRESENTATION IN EXISTING SURVEYS

TITLE

DATE

 FEDERAL STATE COUNTY LOCALDEPOSITORY FOR
SURVEY RECORDS

CITY, TOWN

STATE

7 DESCRIPTION

	CONDITION		CHECK ONE		CHECK ONE
<input checked="" type="checkbox"/>	EXCELLENT	<input type="checkbox"/>	DETERIORATED	<input type="checkbox"/>	UNALTERED
<input type="checkbox"/>	GOOD	<input type="checkbox"/>	RUINS	<input checked="" type="checkbox"/>	ALTERED
<input type="checkbox"/>	FAIR	<input type="checkbox"/>	UNEXPOSED	<input type="checkbox"/>	ORIGINAL SITE
				<input type="checkbox"/>	MOVED DATE _____

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

This is a large 2 1/2 story brick farmhouse, five bays wide by two deep, with a brick kitchen at the rear connected by a hyphen. The principal (north) facade has a central entrance surmounted by a transom and flanked on either side by two large 1/1 sash windows; five 1/1 windows on the second floor are aligned over the first-floor openings. The west gable has two large 1/1 sash windows on both the first and second floors, with two smaller, similar windows in the attic and a pair of casements lighting the cellar. Brickwork is six-course bond with segmental arches over all the aforementioned openings. The slate roof has a steeply-pitched central cross gable, with a pointed-arch sash window. A pair of corbeled interior chimneys rises from the ridge. A one-story porch with turned posts spans the north facade; the porch floor is supported on brick piers, with wooden latticework between them.

A heavy timber framed barn, probably contemporary with the house, lies to the northeast.

CONTINUE ON SEPARATE SHEET IF NECESSARY

8. SIGNIFICANCE

CARR-596

PERIOD	AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW				
<input type="checkbox"/> PREHISTORIC	<input type="checkbox"/> ARCHEOLOGY-PREHISTORIC	<input type="checkbox"/> COMMUNITY PLANNING	<input type="checkbox"/> LANDSCAPE ARCHITECTURE	<input type="checkbox"/> RELIGION	
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> ARCHEOLOGY-HISTORIC	<input type="checkbox"/> CONSERVATION	<input type="checkbox"/> LAW	<input type="checkbox"/> SCIENCE	
<input type="checkbox"/> 1500-1599	<input checked="" type="checkbox"/> AGRICULTURE	<input type="checkbox"/> ECONOMICS	<input type="checkbox"/> LITERATURE	<input type="checkbox"/> SCULPTURE	
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> ARCHITECTURE	<input type="checkbox"/> EDUCATION	<input type="checkbox"/> MILITARY	<input type="checkbox"/> SOCIAL/HUMANITARIAN	
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> ART	<input type="checkbox"/> ENGINEERING	<input type="checkbox"/> MUSIC	<input type="checkbox"/> THEATER	
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> COMMERCE	<input type="checkbox"/> EXPLORATION/SETTLEMENT	<input type="checkbox"/> PHILOSOPHY	<input type="checkbox"/> TRANSPORTATION	
<input type="checkbox"/> 1900-	<input type="checkbox"/> COMMUNICATIONS	<input type="checkbox"/> INDUSTRY	<input type="checkbox"/> POLITICS/GOVERNMENT	<input type="checkbox"/> OTHER (SPECIFY)	
		<input type="checkbox"/> INVENTION			

SPECIFIC DATES

BUILDER/ARCHITECT

STATEMENT OF SIGNIFICANCE

This building is significant as a distinctive example of the form commonly used in Maryland rural domestic vernacular architecture from the mid-nineteenth to early twentieth centuries; its massive brick construction and pronounced verticality set it apart from others of its type. The house is in excellent condition, and its site retains a great deal of its integrity.

CONTINUE ON SEPARATE SHEET IF NECESSARY

9 MAJOR BIBLIOGRAPHICAL REFERENCES

appears as the residence of Elias Houck on Martenet's 1862 Map of Carroll County, Maryland.

CONTINUE ON SEPARATE SHEET IF NECESSARY

10 GEOGRAPHICAL DATA

ACREAGE OF NOMINATED PROPERTY _____

VERBAL BOUNDARY DESCRIPTION

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE	COUNTY
STATE	COUNTY

11 FORM PREPARED BY

NAME / TITLE

Peter E. Kurtze and Peggy Bruns Weissman, Historic Sites Surveyors _____
ORGANIZATION DATE

Maryland Historical Trust _____
STREET & NUMBER TELEPHONE

21 State Circle _____
CITY OR TOWN STATE 269-2438


Annapolis _____ Maryland 21401

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature, to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 Supplement.

The Survey and Inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

RETURN TO: Maryland Historical Trust
 The Shaw House, 21 State Circle
 Annapolis, Maryland 21401
 (301) 267-1438

22 m





Elias Honck / Heister Farm CARR-596
701 ~~702~~ Houchsville Rd.
Hampstead, Carroll Co., Md.