

F-1-140
Careytown Survey District
Doubs vicinity
Private

Ca. 1901-1921

The Careytown Survey District consists of five frame two-story dwellings built about 1901-1921 on the west side of Pleasant View Road about 1/4 mile south of Doubs. The houses are mostly in the vernacular style based on German building traditions of the mid-18th century into the early 20th century which are characterized by three-bay elevations, two-story perpendicular rear wings, one-story porches, and, by the late 19th century, central cross gables on the principal elevations. Two of the five houses in Careytown have cross gables and three have rear wings. The only exception in style and form in the district is a Four Square type house, the latest of the houses, with a hipped roof, irregular bays, tapered piers with brick bases on the main elevation porch, and a second story screened sleeping porch on the rear elevation. All of the houses have been altered, usually with modern artificial siding and replacement windows and doors, although one house retains its original german siding on the main section. Several have modern additions to the rear and side elevations. The houses are attributed by local tradition to John Carey, a local builder in the Doubs area, the source of the district's unofficial name. The district is moderately significant as an example of a small housing development of the early 20th century and for the vernacular architecture of the houses. The Four Square house is also notable for the virtually unaltered sleeping porch, a common element in early 20th century houses which is often enclosed in later years.

F-1-140
Careytown Survey District
Doubs
Frederick County

HISTORIC CONTEXT:

MARYLAND COMPREHENSIVE HISTORIC PRESERVATION PLAN DATA

Geographic Organization: Piedmont
(Harford, Baltimore, Carroll, Frederick, Howard, Montgomery
Counties, and Baltimore City)

Chronological/Development Period:
Industrial/Urban Dominance, A.D. 1870-1930

Prehistoric/Historic Period Themes:
Architecture, Landscape Architecture and Community Planning

Resource Types:

Category: District

Historic Environment: Rural

Historic Function & Use
Domestic/single dwelling/residence
Domestic/secondary structure/other dependencies

Known Design Source: None

Maryland Historical Trust State Historic Sites Inventory Form

MARYLAND INVENTORY OF
HISTORIC PROPERTIES

Magi No.

DOE yes no

1. Name (indicate preferred name)

historic Careytown Survey District

and/or common

2. Location

street & number 2236-2312 Pleasant View Road not for publicationcity, town Doubs vicinity of congressional district 6th

state Maryland county Frederick

3. Classification

Category	Ownership	Status	Present Use	
<input checked="" type="checkbox"/> district	<input type="checkbox"/> public	<input checked="" type="checkbox"/> occupied	<input type="checkbox"/> agriculture	<input type="checkbox"/> museum
<input type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> unoccupied	<input type="checkbox"/> commercial	<input type="checkbox"/> park
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> work in progress	<input type="checkbox"/> educational	<input checked="" type="checkbox"/> private residence
<input type="checkbox"/> site	Public Acquisition	Accessible	<input type="checkbox"/> entertainment	<input type="checkbox"/> religious
<input type="checkbox"/> object	<input type="checkbox"/> in process	<input checked="" type="checkbox"/> yes: restricted	<input type="checkbox"/> government	<input type="checkbox"/> scientific
	<input type="checkbox"/> being considered	<input type="checkbox"/> yes: unrestricted	<input type="checkbox"/> industrial	<input type="checkbox"/> transportation
	<input checked="" type="checkbox"/> not applicable	<input type="checkbox"/> no	<input type="checkbox"/> military	<input type="checkbox"/> other:

4. Owner of Property (give names and mailing addresses of all owners)

name See Section 7

street & number telephone no.:

city, town state and zip code

5. Location of Legal Description

courthouse, registry of deeds, etc. Frederick County Courthouse liber

street & number 100 W. Patrick Street folio

city, town Frederick state MD 21701

6. Representation in Existing Historical Surveys

title MHT Inventory of Historic Properties F-1-140

date June 1982 federal state county local

repository for survey records Md. SHPO

city, town Crownsville state Md.

7. Description

Condition		Check one	Check one	
<input checked="" type="checkbox"/> excellent	<input type="checkbox"/> deteriorated	<input type="checkbox"/> unaltered	<input checked="" type="checkbox"/> original site	
<input checked="" type="checkbox"/> good	<input type="checkbox"/> ruins	<input checked="" type="checkbox"/> altered	<input type="checkbox"/> moved	date of move _____
<input type="checkbox"/> fair	<input type="checkbox"/> unexposed			

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

CONTRIBUTING RESOURCE COUNT: 5

The Careytown Survey District consists of five frame two-story dwellings built from about 1901 to 1921 on the west side of Pleasant View Road about one quarter mile south of Doubs, Frederick County, Maryland. Four of the houses have been altered with the addition of modern artificial siding, one retaining its original german siding, and are, with one exception, in the vernacular style common to Frederick County in the late 19th century, with roots in the German building traditions established in the mid-18th century. The exception is a Four Square house which follows the nationally occurring form popularized in the late 1890's and early 1900's through architectural and builders' pattern books and the catalog buildings of companies such as the Sears, Roebuck & Company. Each of the houses has small outbuildings, most of which are non-contributing, and are used as garages and storage sheds. One house has a contributing frame summer kitchen of about the same date as the main structure. Dates for the houses in the survey district are based on architectural details and land records.

Two of the four vernacular houses have cross gables on the principal elevations and three have a two-story rear wing, adhering to the usual L-shaped plan of German-influenced domestic buildings. The one without a full rear wing has a shed addition on the rear. All five of the houses have one-story porches on the main facades and the characteristic two-level porch of the German vernacular houses is discernible, although most have been altered with full or partial enclosures of the rear porches. The Four Square house has an integral second-story screened sleeping porch, a common element of the type which in this case has not been altered by enclosure.

In the 1982 survey which identified the survey district, a sixth house was included at the south end of the district. This house, 2222 Pleasant View Road, was not included in the district in this survey because of its distance from the other five houses and the heavy intervening foliage. It has also been much altered in terms of its exterior, with modern wood shingle siding.

Following are brief descriptions of the houses in the survey district:

2236 Pleasant View Road: The two-story frame house has a cross gable on the east elevation with asbestos shingle siding and a one-story porch. The porch has elaborate pierced and scroll-sawn trim and brackets with turned columns. The three-bay facade has segmental arched openings and louvred shutters. The sash is 1/1 replacements with small infill sections above each sash. The door has a segmental arched, three-light transom and sidelights. The door is a modern replacement. The cross gable has a 2/2 Gothic arched window. The roof is standing seam metal and the original interior end chimneys have been removed. The north gable end has an exterior concrete block flue. The sash on the north and south gable ends is 2/2 and appears to be original. The two-story rear wing extends from the northwest corner of the main section. Land records indicate that the house was

8. Significance

Period	Areas of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input type="checkbox"/> community planning	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> education	<input type="checkbox"/> military	<input type="checkbox"/> social/ humanitarian
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	<input type="checkbox"/> theater
<input type="checkbox"/> 1800-1899	<input type="checkbox"/> commerce	<input type="checkbox"/> exploration/settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> transportation
<input checked="" type="checkbox"/> 1900-	<input type="checkbox"/> communications	<input type="checkbox"/> industry	<input type="checkbox"/> politics/government	<input type="checkbox"/> other (specify)
		<input type="checkbox"/> invention		

Specific dates C. 1901- C. 1921 **Builder/Architect**

check: Applicable Criteria: A B C D
and/or
Applicable Exception: A B C D E F G

Level of Significance: national state local

Prepare both a summary paragraph of significance and a general statement of history and support.

The Careytown Survey District is moderately significant as an example of an early 20th century housing development built on part of the Michael farm, a large family holding between Doubs and Point of Rocks. The houses are attributed by local tradition to the builder John Carey, one of several Carey brothers whose family settled in the area of Doubs and Adamstown in the late 18th century. At least two of the houses in the district were built for two of the Carey brothers, probably as rental properties. These connections with the Careys gave the group of houses the unofficial designation of "Careytown". The district is minimally significant in architecture for the vernacular style of most of the houses, which reflect the German influence in their general plans and exterior features and also the typical mid and late 20th century alterations of artificial siding and roofing, additions, and replacement doors and windows. The influence of national architectural styles of the early 20th century is reflected in the presence of a Four Square type house which retains an original sleeping porch in virtually unaltered form, although the rest of the house has modern siding and a large addition on two elevations. A Four Square house of similar design in Doubs (F-1-182) is also thought to have been built by John Carey.

The context of small housing groups such as Careytown in Frederick County as a whole is difficult to analyze, as many such districts appeared from at least the beginning of the 19th century well into the 20th century and were demolished or expanded with non-contributing buildings in modern housing developments. Those that had fully developed plans such as Rosemont near Brunswick achieved the appearance of planned early 20th century suburbs. Careytown exemplifies the type of loosely organized groups of houses which were usually located on the main roads at the edges of large farms, from which the land was purchased or subdivided by the owner for speculative rental properties or for associated family houses. Nearby is the Pleasant View Survey District (F-1-139), a late 19th century settlement of freed slaves from Moreland (F-1-164), a large plantation adjacent to the settlement. Where Pleasant View eventually had a church and a school, two characteristics of a community, Careytown was never envisioned as a community center, but more as an outlying residential group associated with the village of Doubs.

9. Major Bibliographical References

Survey No. F-1-140

Grove, William J. History of Carrollton Manor, Frederick: Marken & Bielfeld, Inc. 1928, p. 142-143
Land Records of Frederick County
Whalen, Ms. Roger, personal interview, June 7, 1993

10. Geographical Data

Acreeage of nominated property 8 acres

Quadrangle name Buckeystown, Md.-Va.

Quadrangle scale 1:24000

UTM References do NOT complete UTM references

A

--	--	--	--	--	--	--	--	--	--

Zone Easting Northing

B

--	--	--	--	--	--	--	--	--	--

Zone Easting Northing

C

--	--	--	--	--	--	--	--	--	--

D

--	--	--	--	--	--	--	--	--	--

E

--	--	--	--	--	--	--	--	--	--

F

--	--	--	--	--	--	--	--	--	--

G

--	--	--	--	--	--	--	--	--	--

H

--	--	--	--	--	--	--	--	--	--

Verbal boundary description and justification

Approximately 8 acres as shown on the attached quad map section.

List all states and counties for properties overlapping state or county boundaries

state	code	county	code
state	code	county	code

11. Form Prepared By

name/title Janet L. Davis, Historic Sites Surveyor

organization Frederick County Planning & Zoning Dept. date June 1993

street & number 12 E. Church Street telephone 696-2958

city or town Frederick state MD 21701

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust
Shaw House
21 State Circle
Annapolis, Maryland 21401
(301) 269-2438

BRUNYARD
100 COMMUNITY PLACE
CROWNSVILLE, MD 21032-2001
514-7600

7.1 Description (Continued)

probably built about 1901 by James Carey, possibly as a rental property. In 1914, it was sold to Walter H. and Myra N. DeLauter, who retained the property until 1953. Since 1954, it has been owned by William E. and Ruth M. Davis.

2240 Pleasant View Road: This house also has a three-bay east elevation with a cross gable and a one-story porch. The exterior is covered with vinyl siding. The porch has Tuscan columns and the center entrance has a transom and sidelights with a four-panel door. The windows have 1/1 replacement sash and modern louvred shutters. The central gable window has a Gothic arch. The gable roof is covered with composition material and a modern exterior brick chimney is located on the south elevation. Instead of the usual two-story rear wing, this house has a one-story shed addition on the west elevation. A modern deck extends from the addition. Built about 1904 by Jacob R. Carey, one of five Carey brothers including the James Carey mentioned previously, the house was undoubtedly an investment property and was sold in 1925. The six subsequent owners up to the present included John W. and Almira K. Talbott, from 1928 to 1982.

2244 Pleasant View Road: The Four Square form of this house sets it apart from the rest of the houses in the survey district. Built about 1921, probably by David and Mary Specht, it remained in their possession until 1959. It has a hipped composition roof with a dormer in the east elevation. The irregularly spaced three-bay facade has a one-story porch with tapered square piers set on brick bases. The exterior is covered with vinyl siding and the windows are 6/6 replacements with modern shutters. Flanking the door in the south bay is a smaller, multiple paned window. The door has a glazed upper panel. At the southwest corner of the house is the integral second story sleeping porch, a common feature in early 20th century houses reflecting then-current ideas about health and the benefits of open-air sleeping areas. A modern one-story addition extends from the west elevation onto the north elevation.

2306 Pleasant View Road: This is the only house in the survey district which still has its original german siding. It has three bays and a one-story porch on the east elevation and a two-story rear wing. The wing has vinyl siding and replacement doors and windows. The center entrance has a four-panel door with glazed upper sections. The windows are 2/2 with replacement shutters. The porch has replaced posts on brick bases supporting the roof. The main roof is covered with standing seam metal and one interior chimney on the north gable end remains in place, the southern chimney having been removed. The house was probably built between April and November 1901 by Clara and Horace H. Smith and was then sold to Alfred Pearson. In 1917, the Smiths repurchased the property and five owners have held the property since, including Florence Spalding from 1925 to 1943 and Joseph and Hilda Talbott from 1943 to 1974. It has been in the Bartlett family's possession since 1974.

2312 Pleasant View Road: The northernmost house in the survey district was built about 1901 by Ella and Charles G. Murray. It has a three-bay east elevation with a one-story porch. The exterior is now covered with vinyl siding and the roof is standing seam metal. The original interior end chimneys

7.2 Description (Continued)

have been removed. The windows have 1/1 replacement sash. The center entrance has a stained glass transom which is not original to the house. The door has a glazed upper panel. The porch has turned columns with scroll sawn brackets. The exposed foundation has been replaced or covered on the exterior by concrete block. The two-story rear wing has a modern shed addition and a screened porch on its west elevation. A modern swimming pool is located just behind the house. The frame summer kitchen is located near the southwest corner of the house and has vertical board and board and batten siding. The roof is covered with modern corrugated metal and the brick exterior chimney is located on the south gable end. The interior of the summer kitchen is whitewashed. A plat of the property filed with a 1977 deed identifies the building as a smokehouse, but the interior does not appear to have the heavily smoke-blackened surfaces found in smokehouses of the period.

Owners' Addresses:

2236 Pleasant View Road	William E. & Ruth M. Davis 2236 Pleasant View Road Adamstown, MD 21710
2240 Pleasant View Road	Fred J. & Sharon M. Remsburg 2240 Pleasant View Road Adamstown, MD 21710
2244 Pleasant View Road	Charles S. & Mary C. Lightbown 2244 Pleasant View Road Adamstown, MD 21710
2306 Pleasant View Road	Jay E. & Claudia L. Bartlett 2306 Pleasant View Road Adamstown, MD 21710
2312 Pleasant View Road	Donald A. & Frances H. Beverage 2312 Pleasant View Road Adamstown, MD 21710

Careytown S.D.

Liber/Folio	Grantee	Grantor	Lot Size, Description, Other Information, Original Tracts	Cost	Miscellaneous
2312 Pleasant View Rd. 1196/846 22 apr 83	Donald C. & Frances H. Beverage	Martha L. Rozell (Formerly known as Martha L. Hocken)	2.334A.	\$79,000	
1177/263 15 June 82	Martha L. Hocken	Robert G. & Martha L. Hocken	2.334A.		
1031/851 5 Oct 77	Robert G. & Martha L. Hocken	William R. & Virginia J. Roonty	2.334A. plat filed w/ deed Shows house, well, smokehouse, pool, hog pen, steel, grass		
625/57 11 Sept 59	William R. & Virginia J. Roonty	Edna R. Whipp widow	2A., 42 p.		
340/559 16 Nov 22	Edna R. & Charles E. Whipp	Annie M. Whipp widow, et al (John Whipp died 9 Nov 21)	2A., 42 p.	\$1800	
HWB 300/232 1 apr 12	John Newton Whipp	Ella E. & Charles S. Murray	2A., 42 p.	\$1350	
DHH 11/244 17 apr 01	Ella E. Murray	John L. & Mary C. Michael	2A., 42 p.	\$101.81	
AF 1/461 31 Mar 1880	John L. Michael	Eyra Michael	60 @., 18 p.	\$1202.25	
2306 Pleasant View Rd. 969/312 12 Sept 75	Jay Elwin Bartlett & Claudia L. Bartlett, wife	Edgar E. & Mary Jane Bartlett	150 sq. p.		
946/847 30 Aug 74	Edgar E. Bartlett et ux	Hilda V. Salliot			

Lot Size, Description,
Other Information,
Original Tracts

Liber/Folio	Grantee	Grantor	Lot Size, Description, Other Information, Original Tracts	Cost	Miscellaneous
2306 Pleasant View Rd. 439/151 17 Jul 43	Joseph M. & Hilda V. Talbot	(Cont.) Florence Spalding	150 sq. ft.		
352/268 26 Mar 25	Florence Spalding	John W. & Addie J. Hickman			
326/362 25 Jan 19	John W. Hick- man	Clara M. & Horace H. Smith	150 sq. ft.		
322/331 22 Aug 17	Clara M. & Horace H. Smith	Alfred Pearson et ux	150 sq. ft.		
DHH 11/678 4 Nov 01	Alfred Pearson	Clara M. & Horace H. Smith	150 sq. ft., conveys to Pearson also a R of W over the alley to the property retained by grantor	\$725	
DHH 11/255 17 Apr 01	Clara M. Smith	John L. & Mary E. Michael	4 a.	\$200	
AF 1/461 31 Mar 1880	John L. Michael	Eva Michael			
2244 Pleasant View Rd. 1323/46 13 Feb 86	Charles S. & Mary C. Lighthouse	Charles S. Lighthouse	3 R. 27 sq. ft.		
1105/159 7 Jan 80	Charles S. Lighthouse	Brant A. Bein- stein	3 R. 27 sq. ft.	\$50,500	
1099/534 23 Oct 79	Brant A. Beinstein	Joseph S. Welly assignee in mortgage default by George W. Mowery	3 R. 27 sq. ft.	\$39,050.	1091/82 - foreclosure Equity No. 29314

Care - 1900 S. D. p. 3

Liber/Folio	Grantee	Grantor	Lot Size, Description, Other Information, Original Tracts	Cost	Miscellaneous
2244 Pleasant View Rd. cont 932/947 2 Mar 74	George W. + Patricia L. Maury	George W. Maury	3 R., 27 sq. p.		
808/744 23 Jul 69	George W. Maury	Donald E. Johnson, Adm. of Veterans Affairs	3 R., 27 sq. p.		
808/742 11 Aug 69	Donald E. Johnson	Frank Klotoff, trustee	3 R., 27 sq. p.	\$11,070	Civil Case No. 20493, U.S. Dist Court U.S. vs. George D. Schetzky
680/199 6 Feb 63 mortgage	George W. + Ethel I. Schetzky	J. S. Gleason Jr. Adm. of Veterans Affairs	3 R., 27 sq. p.	\$10,500	
679/302 5 Feb 63	George W. + Ethel I. Schetzky	Charles I. + Carolyn I. Jones, Sr.	3 R., 27 sq. p.		
617/434 4 May 59	Charles I. + Carolyn I. Jones, Sr.	David M. + Mary B. Specht	3 R., 27 sq. p. or 0.918 a.		Rof W. 335 p. 2 12' in common
335/526 10 May 21	David M. + Mary B. Specht	Jacob R. + Lavinia C. Carey	3 R., 27 sq. p. Reserving a Rof W 12' wide extending 15.78 p., intended to be conveyed to use said Rof W.		in flow road to Specht with the right
STH 265/450 7 Apr 04	Jacob R. Carey	Clara M. Smith	3 a. 8 1/2 sq. p. with Rof W.	\$200	
DHH 11/255 17 Apr 01	Clara M. Smith	John L. + Mary E. Michael			

Careytown S.D. p. 4

Liber/Folio	Grantee	Grantor	Lot Size, Description, Other Information, Original Tracts	Cost	Miscellaneous
2240 Pleasant View Rd. 1667/567 31 Aug 90	Fred & Sharon M. Benschung	Allison Chipunoi Lalo	2 a., 21 1/2 sq. p. 2240 Pleasant View Rd.	\$186,500	
1510/888 24 Aug 88	Allison Chipunoi Lalo	Joyce Graham & Allison Chipunoi Lalo (mother & daughter)	2 a., 21 1/2 sq. p.		
1383/890 15 Dec. 86	Joyce Graham & Allison Chipunoi Lalo	Ronald E. & Jeanmarie Bartlett	2 a., 21 1/2 sq. p.	\$105,000	
1168/898 7 Apr 82	Ronald E. & Jeanmarie Bartlett	William W. & Albert L. Talbott attys in fact for Almira K. Talbott	2 a., 21 1/2 sq. p.		
366/281 2 Apr 28	John W. & Almira K. Talbott	Carrie M. Mosslung, widow	2 a., 21 1/2 sq. p.		
352/50 17 Jan 25	Carrie M. Mosslung	Jacob R. & Laurina C. Carey	2 a., 21 1/2 sq. p.		
265/450 7 Apr 24	Jacob R. Carey et ux	Clara M. & Horace H. Smith	3 a., 8 1/2 sq. p.	\$200	
2236 Pleasant View Rd. 539/443 27 Nov 54	William E. & Ruth M. Davis	William L. & Martha C. Summers	9 a.		
522/41 31 Jul 53	William L. Summers et ux	Myra K. DeLauter widow	9 a.		
308/575 26 May 14	Walter H. De Lauter & Myra M. DeLauter	John W. Carey, atty for the heirs of James Carey	9 a.		
DHH 11/346 13 May 01	James & Carey	John L. Michael	10 1/2 a.	\$375	AF 1/461 31 Mar 1880 John L. Mich Brom Ezra Muehler

F-1-140

Maryland Historical Trust State Historic Sites Inventory Form

1. Name (indicate preferred name)

historic

and/or common Group of Six Frame Houses

2. Location

street & number West side Pleasant View Rd., south of Doubs not for publicationcity, town Doubs X vicinity of congressional district

state Maryland county Frederick

3. Classification

Category	Ownership	Status	Present Use	
<u> </u> district	<u> </u> public	<u> X </u> occupied	<u> </u> agriculture	<u> </u> museum
<u> X </u> building(s)	<u> X </u> private	<u> </u> unoccupied	<u> </u> commercial	<u> </u> park
<u> </u> structure	<u> </u> both	<u> </u> work in progress	<u> </u> educational	<u> X </u> private residence
<u> </u> site	Public Acquisition	Accessible	<u> </u> entertainment	<u> </u> religious
<u> </u> object	<u> </u> in process	<u> </u> yes: restricted	<u> </u> government	<u> </u> scientific
	<u> </u> being considered	<u> X </u> yes: unrestricted	<u> </u> industrial	<u> </u> transportation
	<u> X </u> not applicable	<u> </u> no	<u> </u> military	<u> </u> other:

4. Owner of Property (give names and mailing addresses of all owners)

name

street & number telephone no.:

city, town state and zip code

5. Location of Legal Description

courthouse, registry of deeds, etc. liber

street & number folio

city, town state

6. Representation in Existing Historical Surveys

title

date federal state county local

repository for survey records

city, town state

7. Description

Survey No. F-1-140

Condition		Check one	Check one
<input type="checkbox"/> excellent	<input type="checkbox"/> deteriorated	<input type="checkbox"/> unaltered	<input checked="" type="checkbox"/> original site
<input type="checkbox"/> good	<input type="checkbox"/> ruins	<input checked="" type="checkbox"/> altered	<input type="checkbox"/> moved date of move _____
<input checked="" type="checkbox"/> fair	<input type="checkbox"/> unexposed		

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

This small group of six frame houses, now covered with various types of siding, lines the west side of Pleasant View Road, south of the town of Doubs. They are generally similar in design and orientation to the road, and appear to date from the late 19th or early 20th century. Most are 2½ stories high, gable roofed rectangular blocks, three bays wide with a central doorway cross gable, end chimneys, and porch. These are typical of the I-house as built in Maryland during this period.

The house at 2236 Pleasant View Road, near the south end of the group, is typical of most of these houses and is also the most elaborate and best preserved of the group. It features a porch with unusually fine East-lake ornamentation, a pointed arch window in its cross gable, and slightly curved window and door openings. One house in the group represents another house form typical of this period, the cubical, pyramidal or hip roofed two story frame house, usually three bays wide.

8. Significance

Survey No. F-1-140

Period	Areas of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input type="checkbox"/> community planning	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> education	<input type="checkbox"/> military	<input type="checkbox"/> social/
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	<input type="checkbox"/> humanitarian
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> commerce	<input type="checkbox"/> exploration/settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> theater
<input checked="" type="checkbox"/> 1900-	<input type="checkbox"/> communications	<input type="checkbox"/> industry	<input type="checkbox"/> politics/government	<input type="checkbox"/> transportation
		<input type="checkbox"/> invention		<input type="checkbox"/> other (specify)

Specific dates	Builder/Architect
check: Applicable Criteria: <input type="checkbox"/> A <input type="checkbox"/> B <input type="checkbox"/> C <input type="checkbox"/> D and/or Applicable Exception: <input type="checkbox"/> A <input type="checkbox"/> B <input type="checkbox"/> C <input type="checkbox"/> D <input type="checkbox"/> E <input type="checkbox"/> F <input type="checkbox"/> G	
Level of Significance: <input type="checkbox"/> national <input type="checkbox"/> state <input checked="" type="checkbox"/> local	

Prepare both a summary paragraph of significance and a general statement of history and support.

This group of houses is significant architecturally as a representative group of large and substantial late 19th century vernacular houses. The houses are almost completely of one type, the Gothic influenced frame I-house with center gable, as built throughout Maryland during this period. These examples are generally larger and slightly more elaborate than the average I-house of this period; the best of the group is at 2236 Pleasant View Road, which has a fine Eastlake porch and other good architectural details.

This group is similar to some of the houses built in the nearby town of Doubs during the 1870's and 1880's (see F-1-133). The houses are not shown on the 1873 Lake atlas of the county, but are seen on a 1913 U.S.G.S. topographic map of the county.

9. Major Bibliographical References

Survey No. F-1-140

Lake, D.J., Atlas of Frederick County, Maryland, 1873.
Maryland Geological Survey, Atlas of Frederick County (topographic maps), 1913.

10. Geographical Data

Acreage of nominated property _____

Quadrangle name _____

Quadrangle scale _____

UTM References do NOT complete UTM references

A	<input type="text"/>	<input type="text"/>	<input type="text"/>
	Zone	Easting	Northing

B	<input type="text"/>	<input type="text"/>	<input type="text"/>
	Zone	Easting	Northing

C	<input type="text"/>	<input type="text"/>	<input type="text"/>
---	----------------------	----------------------	----------------------

D	<input type="text"/>	<input type="text"/>	<input type="text"/>
---	----------------------	----------------------	----------------------

E	<input type="text"/>	<input type="text"/>	<input type="text"/>
---	----------------------	----------------------	----------------------

F	<input type="text"/>	<input type="text"/>	<input type="text"/>
---	----------------------	----------------------	----------------------

G	<input type="text"/>	<input type="text"/>	<input type="text"/>
---	----------------------	----------------------	----------------------

H	<input type="text"/>	<input type="text"/>	<input type="text"/>
---	----------------------	----------------------	----------------------

Verbal boundary description and justification

List all states and counties for properties overlapping state or county boundaries

state	code	county	code
-------	------	--------	------

state	code	county	code
-------	------	--------	------

11. Form Prepared By

name/title Peggy Bruns Weissman, Architectural Historian

organization Maryland Historical Trust date June 1982


street & number 21 State Circle telephone (301) 269-2438

city or town Annapolis state Maryland 21401

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust
Shaw House
21 State Circle
Annapolis, Maryland 21401
(301) 269-2438



Pleasant View Road



F-1-140
Careytown Survey District
Frederick County

Janet Davis
June 4, 1993
Not to Scale

4353
4352
17'30"
4351
POINT OF ROCKS 2.2 MI
4349
520 000
FEET
4348

F-1-140
GROUP OF SIX
FRAME HOUSES

Pleasant View

Doubs Sch

Tuscarora

Fish Hatchery

Tuscarora

Forest Grove Ch

BALTIMORE AND OHIO RIVER
CANAL
Nolands Island

MARYLAND VIRGINIA

600 000 FEET



F-1-140

Cokeytown Survey District

Frederick County

Photo: Janet Davis

June 1993

Neg. loc.: Md. SHPO, Crownsville, Md

2312 Pleasant View Rd., East elevation

1/6



F. 1-140

Coreytown Survey District

Frederick County

Photo: Janet Davis

June 1993

Neg. loc.: Md. SHPO, Crownsville, Md

2306 Pleasant View Rd., east elevation

2/6



F. 1-140

Carey town Survey District

Frederick County

Photo: Janet Davis

June 1993

Neg. loc.: Md. SHPO, Crownsville, Md.

2244 Pleasant View Rd., northeast corner view

3/6



F 1-140

Carey town Survey District

Frederick County

Photo: Janet Davis

June 1993

Neg. loc.: Md. SHPO, Crownsville, Md.

2244 Pleasant View Rd. Southwest corner
view with second floor sleeping porch

4/6



F-1-140

Careytown Survey District

Frederick County

Photo: Janet Davis

June 1993

Neq. loc.: Md. S490, Crownsville, Md

2240 Pleasant View Rd., north elevation

5/6



F-1-140

Careytown Survey District

Frederick County

Photo: Janet Davis

June 1993

Neg. loc.: Md. SHPO, Crownsville, Md

2236 Pleasant View Rd., east elevation

6/6



F-1-140

Group of Six Frame Houses
East elevation

Peggy Bruns Weissman

June 1982