

**Maryland Historical Trust**  
**Maryland Inventory of Historic Properties Form**  
**Intercounty Connector Project**

DOE \_\_\_yes \_\_\_no

**1. Name:** (indicate preferred name)

historic Caleb and Catherine Adams Property

and/or common Lucille Foster

**2. Location:**

street &amp; number 14601 Good Hope Road \_\_\_ not for publication

city, town Cloverly  vicinity of congressional district

state Maryland county Montgomery

**3. Classification:**

Category	Ownership	Status	Present Use
<input type="checkbox"/> district	<input type="checkbox"/> public	<input checked="" type="checkbox"/> occupied	<input type="checkbox"/> agriculture <input type="checkbox"/> museum
<input checked="" type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> unoccupied	<input type="checkbox"/> commercial <input type="checkbox"/> park
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> work in progress	<input type="checkbox"/> education <input checked="" type="checkbox"/> private
<input type="checkbox"/> site	<b>Public Acquisition</b>	<b>Accessible</b>	<input type="checkbox"/> entertainment residence
<input type="checkbox"/> object	<input type="checkbox"/> in process	<input type="checkbox"/> yes: restricted	<input type="checkbox"/> government religious
	<input type="checkbox"/> being considered	<input type="checkbox"/> yes: unrestricted	<input type="checkbox"/> industrial scientific
	<input checked="" type="checkbox"/> not applicable	<input checked="" type="checkbox"/> no	<input type="checkbox"/> military other:
			<input type="checkbox"/> transportation

**4. Owner of Property:** (give names and mailing addresses of all owners)

name Lucille Foster

street &amp; number 14601 Good Hope Road

telephone no.:

city, town Silver Spring

state and zip code MD 20905

**5. Location of Legal Description**

Land Records Office of Montgomery County

liber 13871

street &amp; number 50 Maryland Avenue

folio 467

city, town Rockville

state MD

**6. Representation in Existing Historical Surveys**

title

date \_\_\_federal \_\_\_state \_\_\_county \_\_\_local

depository for survey records

city, town

state

## 7. Description

Survey No. M:28-50(PACS E11.32)

Condition		Check one	Check one	
<input checked="" type="checkbox"/> excellent	<input type="checkbox"/> deteriorated	<input type="checkbox"/> unaltered	<input checked="" type="checkbox"/> original site	
<input type="checkbox"/> good	<input type="checkbox"/> ruins	<input checked="" type="checkbox"/> altered	<input type="checkbox"/> moved	date of move _____
<input type="checkbox"/> fair	<input type="checkbox"/> unexposed			

Resource Count: 2

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

The Adams Property is a 2-story, 2-bay cottage on the south side of Good Hope Road in the Cloverly vicinity, Montgomery County. According to tax records, the house was constructed in 1927. The building is rectangular in plan, with a shed roof front porch, a 1-story hipped rear addition and exposed rafter ends.

The structure has a side-gable roof, with a central brick chimney. It is of wood-frame construction with asbestos shingle siding, and it has a stuccoed concrete block foundation. The windows are 6/1 double-hung. The house has a shed roof porch on the front elevation. The original porch posts were replaced with four small wood posts on a concrete slab. The porch has been screened.

The entrance on the front, or north facade is located in the second bay. It is a wood panel door. The first bay on the first story is a triple 6/1 double-hung window. The second story has two single 6/1 double-hung windows aligned over the first story openings.

The east elevation has a symmetrical fenestration pattern with two bays on both the first and second stories and a centered bay in the gable end. The first story has a pair of 6/1 double-hung windows and a single 6/1 double-hung window. The second story has two 6/1 double-hung windows, while the attic level has a single 6/6 double-hung window.

The rear, or south elevation has a full-width, 1-story hipped roof addition. The addition has a pair of 6/6 double-hung windows, a single 6/6 double-hung window and a wood paneled door. The addition has a concrete block foundation and concrete steps lead to the entry. The second story has two 6/1 double-hung windows.

The west elevation has three symmetrical bays. The first bay on the first story is a single 6/1 double-hung window, while the third bay is a projecting bay with a plate glass window and a shed roof. The second bay is  $\frac{1}{2}$ -story lower than the previous bay. The first floor bay is a 4-light paneled door at grade level. The first and third bays on the second story are single 6/1 double-hung windows, while the second bay is a 6/1 double-hung window located between the first and second floor level. A single 6/6 double-hung window is located in the gable end on the attic level.

Typical elements of the circa 1920s cottage, including a Bungalow fenestration pattern, 6/1 double-hung windows and exposed rafter ends are evident in this structure. Alterations to the property include the hipped roof addition to the rear elevation.

There is one outbuilding associated with this property. The outbuilding is a  $1\frac{1}{2}$ -story garage, with a front-gable roof covered with asphalt shingles. Constructed circa 1920, it is of wood-frame construction with German wood siding. The structure is located south of the house at the end of a small circular driveway.

The property is located on the south side of Good Hope Road, with residential property to the south, east and west and Good Hope Road to the north. The lot gradually slopes from the front of the lot to the southwest corner. The property's setting retains its integrity despite the construction of a circa 1970 house immediately east of the house.



CONTINUATION SHEET

MARYLAND HISTORICAL TRUST

STATE HISTORIC SITES INVENTORY FORM

RESOURCE NAME: Caleb and Catherine Adams Property

SURVEY NO.: M: 28-50 (PACS E11.32)

ADDRESS: 14601 Good Hope Road, Cloverly vicinity, Montgomery County, Maryland

8. Significance (Continued)

and hipped roof frame cottages were developed in the early to mid-twentieth century. Front gable and hipped roof cottages are primarily one to one-and-a-half-stories tall, 3 bays wide and several rooms deep. Side-gable and cross-gable structures are usually two to two-and-a-half-stories tall, are typically two to three bays in width and vary from one to three rooms deep. They usually include a porch covered with a shed roof. Porches are supported by posts often containing machine-produced Victorian ornamentation. Some cottages feature ornamentation drawn from Craftsman style or Colonial Revival architecture (Gottfried and Jennings 1988, viii-xv).

NATIONAL REGISTER EVALUATION:

Constructed in 1927, the Caleb and Catherine Adams Property is not eligible for the National Register of Historic Places. The property is not eligible under Criterion A, as research conducted indicates no association with any historic events or trends significant in the development of national, state or local history. Historic research indicates that the property has no association with persons who have made specific contributions to history, and therefore, it does not meet Criterion B. It is not eligible under Criterion C, as it is an example of a common building type, which lacks individual architectural significance. In addition, the building suffers from a loss of material and architectural integrity. The exterior of the house has been covered with asbestos shingles, the front porch columns were replaced and a 1-story addition was constructed on the rear elevation. Finally, the structure has no known potential to yield important information, and therefore, is not eligible under Criterion D.

MARYLAND HISTORICAL TRUST

Eligibility recommended \_\_\_\_\_ Eligibility Not Recommended \_\_\_\_\_ X

Comments: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Reviewer, OPS: E. Hannold/K. Williams Date: 11/25/1996

Reviewer, NR Program: [Signature] Date: 3/2/02

---

## 9. Major Bibliographical References Survey No.M:28-50(PACS E11.32)

---

See Continuation Sheet

---

## 10. Geographical Data

---

Acreeage of nominated property 1.05 hectare (2.6 acres)

Quadrangle name Beltsville, MD

Quadrangle scale 1:24,000

Verbal boundary description and justification

---

List all states and counties for properties overlapping state or county boundaries

state	code	county	code
-------	------	--------	------

state	code	county	code
-------	------	--------	------

---

---

## 11. Form Prepared By

---

name/title Caroline Hall/Tim Tamburrino

organization P.A.C. Spero & Company

date December 1996

street & number 40 W. Chesapeake Avenue, Suite 412

telephone (410) 296-1635

city or town Baltimore

state Maryland

---

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposed only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust  
DHCP/DHCD  
100 Community Place  
Crownsville, MD 21032-2023  
(410) 514-7600

CONTINUATION SHEET

MARYLAND HISTORICAL TRUST

STATE HISTORIC SITES INVENTORY FORM

RESOURCE NAME: Caleb and Catherine Adams Property

SURVEY NO.: M: 28-50 (PACS E11.32)

ADDRESS: 14601 Good Hope Road, Cloverly vicinity, Montgomery County, Maryland

---

## 9. Major Bibliographical References (Continued)

---

- Boyd, T.H.S. The History of Montgomery County, Maryland, From its Earliest Settlement in 1650 to 1879. Baltimore: Regional Publishing Company, 1968.
- Brugger, Robert A. Maryland, A Middle Temperament 1634-1980. Baltimore and London: Johns Hopkins University Press, 1988.
- Coleman, Margaret Marshall. Montgomery County: A Pictorial History. Norfolk and Virginia Beach: The Donning Company Publishers, 1984, rev. 1990.
- Daniels, Lee A. "Burtonsville: A town of the past trapped between the future." Washington Post. no date.
- Dixon-Williams, Gail. "Originally Burtons, this suburb has come a long way from 1800's." Burtonsville Gazette, 14 September 1994: A-4.
- Farquhar, Roger Brooke. Old Homes and History of Montgomery County, Maryland. Washington: Judd and Detweiler, Inc., 1962.
- raci, Ron, Vicki Walker, and Linda Donnary. Old Building Survey of the Burtonsville Area. Burtonsville, Maryland: Burtonsville Bicentennial Committee, 1976.
- Gottfried, Herbert and Jennings, Jan. American Vernacular Design, 1870-1940. Ames, Iowa: Iowa State University Press, 1988.
- Hiebert, Ray Eldon, and Richard K. MacMaster. A Grateful Remembrance: the Story of Montgomery County, Maryland. Rockville, Maryland: Montgomery County Government and the Montgomery County Historical Society, 1976.
- Hopkins, G.M. Atlas of 15 Miles Around Washington including County of Montgomery, Maryland. Philadelphia: G.M. Hopkins, 1879; reprint, Rockville, Maryland: Montgomery County Historical Society, 1975.
- Land Records of Montgomery County, Maryland.
- Martenet, Simon J. Martenet and Bond's Map of Montgomery County, Maryland. Baltimore, Maryland: Simon J. Martenet, 1865; reprint, Rockville, Maryland: Montgomery County Historical Society.
- Maryland-National Capital Park and Planning Commission. Historic Resources of the Eastern Montgomery County Master Plan Areas. Silver Spring: M-NCPPC, 1995.
- Tindall, George Brown. America: A Narrative History. 2 vols. New York: W.W. Norton & Company, Inc., 1984.

CONTINUATION SHEET

MARYLAND HISTORICAL TRUST

STATE HISTORIC SITES INVENTORY FORM


RESOURCE NAME: Caleb and Catherine Adams

SURVEY NO.: M: 28-50 (PACS E11.32)

ADDRESS: 14601 Good Hope Road, Cloverly vicinity, Montgomery County, Maryland

10. Geographical Data (Continued)

Resource Sketch Map:



CONTINUATION SHEET

MARYLAND HISTORICAL TRUST

STATE HISTORIC SITES INVENTORY FORM

RESOURCE NAME: Caleb and Catherine Adams Property

SURVEY NO.: M: 28-50 (PACS E11.32)

ADDRESS: 14601 Good Hope Road, Cloverly vicinity, Montgomery County, Maryland

Maryland Comprehensive Historic Preservation Plan Data Sheet

Historic Context:

MARYLAND COMPREHENSIVE PRESERVATION PLAN DATA

Geographic Organization:

Piedmont

Chronological/Developmental Period Theme (s):

Industrial/Urban Dominance A.D. 1870-1930

Prehistoric/Historic Period Theme(s):

Architecture

RESOURCE TYPE:

Category (see Section 3 of survey form):

Building

Historic Environment (urban, suburban, village, or rural):

Suburban

Historic Function(s) and Use(s):

Private Residence

Known Design Source (write none if unknown):

None

Preparer:

P.A.C. Spero & Company

December 1996





1. Mi 28-50
2. Caleb and Catherine Adams Property
3. Montgomery
4. Tim Tamburino
5. July 1996
6. P.A.C. Spero & Company, 40 W. Chesapeake Ave, Suite 412, Towson MD 21204
7. 14601 Good Hope Road, Front elevation
8. 1 of 5



1. M: 28-50
2. Caleb and Catherine Adams Property
3. Montgomery
4. Tim Tamburino
5. July 1996
6. P.A.C. Spool Company, 40 W. Chesapeake  
Ave, Suite 412, Towson MD 21204
7. 14601 Good Hope Road, front and north  
elevations
8. 2 of 5



1. M: 28-50
2. Celeb and Catherine Adams Property
3. Montgomery
4. Tim Tamburino
5. July 1996
6. P.A.C. Sperry & Company, 46 W. Chesapeake Ave., Suite 412, Towson MD, 21204
7. 14601 Good Hope Road, near elevation
8. 3 of 5



1. M: 28-50
2. Caleb and Catherine Adams Property
3. Montgomery
4. Tim Tamburino
5. July 1996
6. P.A.C. Spool Company, 40 W. Chesapeake Ave, Suite 412, Towson MD 21204
7. 14601 Good Hope Road, South elevation
8. 4 of 5



1. M. 28-50
2. Caleb and Catherine Adams Property
3. Montgomery
4. Tim Tamburino
5. July 1996
6. P.A.C. Spers & Company, 40 W Chesapeake Ave, Suite 412, Towson MD 21204
7. 14601 Good Hope Road, garage
8. 5 of 5