

United States Department of the Interior
National Park Service

For NPS use only

National Register of Historic Places Inventory—Nomination Form

received

date entered

See instructions in *How to Complete National Register Forms*
Type all entries—complete applicable sections

1. Name

historic Sunnyside (preferred)

and or common Michael Stone House/Turner House

2. Location

street & number 16005 Dr. Bowen Road (Maryland Route 233) N/A not for publication

city, town Aquasco N/A vicinity of Fourth Congressional District

state Maryland code 24 county Prince George's code 033

3. Classification

| Category | Ownership | Status | Present Use |
|---|--|--|---|
| <input type="checkbox"/> district | <input type="checkbox"/> public | <input checked="" type="checkbox"/> occupied | <input type="checkbox"/> agriculture |
| <input checked="" type="checkbox"/> building(s) | <input checked="" type="checkbox"/> private | <input type="checkbox"/> unoccupied | <input type="checkbox"/> commercial |
| <input type="checkbox"/> structure | <input type="checkbox"/> both | <input type="checkbox"/> work in progress | <input type="checkbox"/> educational |
| <input type="checkbox"/> site | Public Acquisition | Accessible | <input checked="" type="checkbox"/> private residence |
| <input type="checkbox"/> object | <input type="checkbox"/> in process | <input type="checkbox"/> yes: restricted | <input type="checkbox"/> entertainment |
| | <input type="checkbox"/> being considered | <input type="checkbox"/> yes: unrestricted | <input type="checkbox"/> government |
| | <input checked="" type="checkbox"/> not applicable | <input checked="" type="checkbox"/> no | <input type="checkbox"/> industrial |
| | | | <input type="checkbox"/> military |
| | | | <input type="checkbox"/> museum |
| | | | <input type="checkbox"/> park |
| | | | <input type="checkbox"/> religious |
| | | | <input type="checkbox"/> scientific |
| | | | <input type="checkbox"/> transportation |
| | | | <input type="checkbox"/> other: |

4. Owner of Property

name Mr. and Mrs. Covington Stanwick (Monique)

street & number 16005 Dr. Bowen Road

city, town Aquasco N/A vicinity of state Maryland 20608

5. Location of Legal Description

courthouse, registry of deeds, etc. Prince George's County Courthouse

street & number Main Street

city, town Upper Marlboro state Maryland 20772

6. Representation in Existing Surveys

title Maryland Historical Trust
Historical Sites Inventory has this property been determined eligible? yes no

date 1986 federal state county local

depository for survey records Maryland Historical Trust

city, town Annapolis state Maryland 21401

7. Description

| | | | |
|---|---------------------------------------|---|--|
| Condition | | Check one | Check one |
| <input checked="" type="checkbox"/> excellent | <input type="checkbox"/> deteriorated | <input type="checkbox"/> unaltered | <input checked="" type="checkbox"/> original site |
| <input type="checkbox"/> good | <input type="checkbox"/> ruins | <input checked="" type="checkbox"/> altered | <input type="checkbox"/> moved date <u> N/A </u> |
| <input type="checkbox"/> fair | <input type="checkbox"/> unexposed | | |

Describe the present and original (if known) physical appearance

| | | |
|---------------------|-------------------------|--|
| Number of Resources | | Number of previously listed National Register properties included in this nomination: <u> 0 </u> |
| Contributing | Noncontributing | |
| <u> 3 </u> | <u> 0 </u> buildings | Original and historical functions and uses: residential and agricultural |
| <u> 0 </u> | <u> 0 </u> sites | |
| <u> 0 </u> | <u> 0 </u> structures | |
| <u> 0 </u> | <u> 0 </u> objects | |
| <u> 3 </u> | <u> 0 </u> Total | |

DESCRIPTION SUMMARY

Sunnyside is a gable roofed, two-story frame "I" house of five-by-one-bays, with a center hall and north and south parlors, resting on a brick foundation. The building dates to 1844, although structural evidence points to mid-nineteenth century alterations¹ to create its present appearance. It is likely that the house was originally three bays wide, two stories in height composed of a side hall with a north parlor. In the mid-nineteenth century it gained a balancing two story addition to the south. The interior of the house is largely original fabric, including vernacular mantels with Federal style influences, flooring, doors and wall plaster. Doors and windows have late-nineteenth century plain board surrounds with bull's-eye corner blocks. On the exterior, shutters and siding are historic. An old cedar shingle roof was replaced by a new one in 1982. A one-story frame summer kitchen with a massive brick chimney and stone foundation, dating to the eighteenth century,² is connected to the house by a nineteenth century one-story enclosed passage. Two outbuildings on the property, a meat house and a corn crib, probably date to the construction of the main block.

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

Sunnyside

Continuation sheet Prince George's County, MD Item number

7

Page 1

| |
|------------------|
| For NPS use only |
| received |
| Date entered |

GENERAL DESCRIPTION

Sunnyside is located approximately 500 yards west of Aquasco Road in Aquasco, Maryland. The house can be seen from Dr. Bowen and Aquasco Roads over open fields. It is reached by a gravel drive from Dr. Bowen Road, which passes approximately 500 feet north of its north gable end. The house is situated on 21.25 acres and is a highly visible landmark in the village of Aquasco.

The main block of the house is five-by-two bays, measuring 18' 4" x 42' 5". The five-bay east (main) entrance facade has central entrance through a four panel door with a three-light transom. Door and transom have a very narrow wood surround. Windows on the facade are 6/6 double-hung-sash, having the same narrow surround as the entrance, wooden sills and black-painted louvered wooden shutters. The center bay is set apart from the north and south bays by a wide inter-bay space. The first story of the east face is sheltered by a five-bay hipped roof screened entrance porch. The wood shingle porch roof is supported on chamfered wood posts with jigsaw brackets. There is a plain frieze and boxed cornice with crown molding. The porch floor is wooden, reached by three steps, and is supported on brick piers, with wood lattice in the interval between piers.

The house is covered with lapped horizontal wood siding with corner boards. The seam visible on the rear facade, indicating the addition to the building of two south bays, is not visible in the siding on the front facade. The front siding was probably applied after the date of the addition. The roof is covered with cedar shingles, added in 1982 to replace an earlier cedar shake covering. There is a crown molded boxed wood cornice with modest returns and raking boards in the gable ends. The building rests on a brick foundation.

The two bay north gable end of the main block has a centered brick chimney laid in American bond, with corbelled second story weathering. Two small four-light windows flank the chimney at attic level. The gables have a plain board raking cornice and small, crown molded cornice returns. The south gable end is identical to the north gable end, with the addition of a 6/6 double hung sash window on the second level, east of the chimney.

The five bay west or rear elevation of the main block has the same fenestration on the second floor as the front facade. A seam between the third and fourth bay has a corner board, indicating that the building once ended after the third bay, and that the fourth and fifth (south) bays were a later addition. (This evidence is borne out by differing moldings in the second story bedrooms and the presence of a crown molded cornice in the older north parlor and the hall, but not in the south parlor.) A one-story shed roof enclosed porch extends across the first three bays of the first story. Probably enclosed in the early twentieth century,³ it rests on a brick foundation, and has wall, window, cornice and roof treatment similar to that

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

| |
|------------------|
| For NPS use only |
| received |
| date entered |

Sunnyside

Continuation sheet Prince George's County, MD Item number 7 Page 2

GENERAL DESCRIPTION (continued)

of the main block. A center entrance is covered by a modern storm door of vertical boards protecting an old board and batten door. Iron spindles for hinges protect from the door frame.

A lower, narrower one-story lean-to addition, dating from the mid-nineteenth century⁴ extends across the fourth and fifth bay of the main block and continues as a passageway connecting to the summer kitchen, approximately 20 feet south of the house. This connector or passageway has a cedar shingle, gable roof and is covered with random width roughly hewn wood siding. It has a boxed wood cornice and rests on a brick foundation. The rear entrance in its third bay also has a modern wooden storm door protecting an old board and batten door.

The one story frame summer kitchen, dating from the 18th century, is two-by-one bays and measures 14' 2" x 22' 3". The gable roof is wood shingled, the roof ridge is perpendicular to that of the main house and the passageway. The building is covered with random width, roughly hewn horizontal wood siding, and has corner boards. It rests on a high random fieldstone and brick foundation. There is a massive freestanding brick chimney on the west gable end, laid in American bond and having a high corbelled weathering. There is a boxed wooden cornice on north and south facades and a plain board raking cornice on the gable ends. The passageway meets the summer kitchen at its northeast corner and is fitted over the summer kitchen's northeast roof edge. A central entrance to the summer kitchen on the south facade, reached by a flight of wood stairs, also is covered by a modern vertical board storm door, protecting an old board and batten door. A patch in the siding by the door indicates that it has been altered to a smaller size. The building has foundation windows, probably added when the modern basement was dug.

The house interior has a center hall with a north and south parlor. The open run stair rises along the north wall of the hall, and has simple rectangular balusters and a rectangular newel post. The stair has a winder to the left, and the enclosed second flight crosses the west (rear) wall of the hall. Interior door and window surrounds are wide plain wood moldings with bull's-eye cornerblocks. A high surround incorporates the main entrance and transom. The north parlor and the hall have a crown molded cornice. There are wide plain baseboards throughout the house. The flooring, moldings and most of the plaster work is original fabric. The mantels in the north and south parlors are simple, mid-nineteenth century adaptations of Federal and Greek stylistic elements. Both have rectangular openings flanked by pilasters on base blocks which support a long, narrow mantel shelf. Both have a wide banded frieze. The more detailed north parlor mantel has pilasters with an oval profile, scroll brackets supporting the mantel shelf, and a rectangular panel centered in the frieze, having a convex "X" design. Both north and south parlors have a shallow rear room formed by the enclosed porch additions on the rear of the building. The door opposite the main entrance leads to a

PG:87B-21

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

| |
|------------------|
| For NPS use only |
| received |
| date entered |

Sunnyside

Continuation sheet Prince George's County, MD

Item number

7

Page 3

GENERAL DESCRIPTION (continued)

bathroom, located in the larger rear addition. Doors throughout the main block are four-panel, with brass handles and box locks except for the three rear entrances which are old board and batten doors with wooden bolts and iron strap hinges.

The second floor of the main block has a narrow central hall with a north and south bedroom. A center bedroom was converted into a bath during the 1940s. The north bedroom has simple architrave surrounds around the door and windows. These are probably the earliest of the building, dating before the addition of the south bedroom and the dining room. There are plain baseboards throughout. The hall and south bedroom have the moldings with corner blocks used on the first floor. The mantels in the bedrooms are identical. They have pilasters in low relief, a plain frieze and long narrow mantel shelf. The fire box opening is smaller than that of the wooden mantel. The infill is black-painted cement over the brick.

The short, enclosed stair flight to the third story is steep and narrow and winds from north on the second story to east on the third story. The third story has a central hall with a closet directly across from the stairwell, and a north and south room. The original horsehair plaster and whitewash on the finished third floor was replaced by the present owners with wallboard, keeping the original appearance of the rooms.

The kitchen has been located in the connecting passage between the house and the summer kitchen since the 1940s. There is a step down in floor level to this section of the house. Wide unlapped wood siding covers the north and west walls of the room to about half their height, with plastering above the siding. The lapped siding of the summer kitchen is visible on the south wall of the room. The rear exit, on the west wall, is of vertical boards with strap hinges and a wooden bolt.

There are two entrances into the summer kitchen in the south wall of the passage. Both are of vertical board. The lower east door is entrance to a small pantry and the basement stairway. Traditionally, a dirt root cellar was located beneath this building. A full cellar now extends beneath the summer kitchen and the passageway. The west door enters into the room originally used for the kitchen. A large brick fireplace in the west wall has a hand hewn load bearing beam over the fire box opening. There are original iron fixtures for hanging cooking pots in the fireplace. This fireplace had been closed and walled over, and was reopened by the present owners. A three by three foot iron block found in the fireplace is believed to have been used for heat storage.

United States Department of the Interior
National Park Service

PG:-87B-21

National Register of Historic Places
Inventory—Nomination Form

For NPS use only

received

date entered

Sunnyside

Continuation sheet Prince George's County, MD Item number 7 Page 4

GENERAL DESCRIPTION (continued)

The interior walls of the summer kitchen have exposed hand hewn studs and corner braces, infilled with brick nogging that has been covered with plaster. The wall between the kitchen and the pantry is covered with unlapped wood siding. The ceiling has exposed hand-hewn beams also infilled with plaster. A trap door to a two-room loft is in the ceiling by the center dividing wall. An exterior door in the south wall of the room is of vertical boards with three wide horizontal cross boards. The door has iron strap hinges and a wooden bolt.

Outbuildings on the surrounding property include a one-by-one-bay frame, gable-roof meat house southwest of the dwelling. The meat house probably dates to the time of the house construction. It is set high on a rough brick, stone and cement foundation; and rests on a hand-hewn sill. It measures 10 feet 2 inches square and is covered by wide unpainted siding with a narrow overlap. There are corner boards, and narrower siding in the upper gable ends. The wood shingle roof has a boxed cornice on the east and west and raking boards on the north and south gables. The east side center entrance is of vertical boards with iron strap hinges.

Northwest of the house, close to Dr. Bowen Road and the gravel entrance drive is a large two-by-one-bay gable-roof frame outbuilding supposed to have been used for a corncrib. It also is nineteenth century in date and probably dates to the construction of the house. The structure is set high on brick piers and log sections. Its structure is of heavy hand-hewn timbers which are jointed and pegged. The building measures 20 feet by 12 feet. The exterior is covered with wide horizontal wood siding having a narrow overlap. The siding is unpainted but is coated with kreosote. There are square cut nails in some timbers. The roof is covered with corrugated metal. The boxed cornice has a wide overhang on the north and south facades. The east and west gable ends have a very narrow raking cornice board. There is a central double entrance on the south facade, having doors of vertical boards and iron strap hinges, separated by a center post. A barn originally adjoining the corn crib was destroyed by a bulldozer during the widening of Dr. Bowen Road. It is possible that the corn crib was moved or re-positioned at that time.

¹The exact date of the alterations is unknown. According to family tradition, the house was enlarged when the family became so large, more space was needed. According to U.S. Census records, the Stone Family had two young children in 1850. By 1860, the family had six children. It is probable that the house was enlarged by 1860 or shortly thereafter.

²The exact date of this building is unknown. According to family tradition it is eighteenth century. Its architectural characteristics, such as brick nogged interior walls and massive freestanding end chimney, point to such a date.

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

For NPS use only
received
date entered

Sunnyside

Continuation sheet Prince George's County, MD Item number 7 Page 5


GENERAL DESCRIPTION (continued)

³A former resident of Sunnyside, Grace Stone Craycroft, born in 1896, had early memories of the rear porch before it was enclosed. This suggests that date of its enclosure to be ca. 1900.

⁴According to family tradition, Dr. Stone used this passage as his medical office. This places its date prior to his death in 1877.

United States Department of the Interior
National Park Service

PG:87B-21

National Register of Historic Places
Inventory—Nomination FormContinuation sheet Sunnyside
Prince George's County, MD Item number 8 Page 6

HISTORY AND SUPPORT

The village of Aquasco, in the southeast corner of Prince George's County, formed along the main road from Charles County to Upper Marlboro in the early nineteenth century. The area had been characterized by large tobacco farms served by shipping on the Patuxent River, two miles to the east, throughout the eighteenth century.³ The village, called Woodville in the nineteenth century, was populated in 1850 by small scale farmers and farm laborers, a miller, a cooper, several merchants, a blacksmith, two physicians, a tavern keeper, postmaster, school teacher and a minister.⁴

Michael J. Stone acquired 50 acres in Aquasco, in 1844, shortly after his marriage to Susan Somervell.⁵ He probably built Sunnyside shortly after he bought the property. An eighteenth century two-by-one-bay, gable roof one-story building with a freestanding west chimney was on the property at the time of Stone's purchase. According to family tradition the Stones used the building as a summer kitchen with slave quarters above.⁶

Stone probably initially built a three-by-one-bay dwelling with a stair hall and north parlor on the first story and one bedroom above. A seam on the exterior of the house and differing interior moldings in the second floor bedrooms indicates this early house plan. The 1850 U.S. Census shows Stone and his wife having two young children. By 1860 the family had six children.⁷ It is probable that in the late 1850s or early 60s the house was expanded to its present appearance, including a south dining room with a bedroom above, a finished two-room third story and an enclosed passage between the house and the summer kitchen. The passage, according to family tradition, was used as Stone's office.

There are few "I" houses dating to the mid-19th century extant in the county.⁸ The degree of preservation of the interior and exterior detail at Sunnyside make it exceptional. The existence of a small 18th century dwelling in good repair as well as two mid-19th century outbuildings on the property makes it exemplary of 18th through mid-19th century construction methods and building style.

Dr. Stone had been born in Charles County, just south of Aquasco. His father, Michael Jennifer Stone (1747-1812), had served in Maryland's House of Delegates, was a member of the State's Constitutional Convention in 1788 and was elected to the United State's first Congress, 1789-1791. Stone's uncle, Thomas Stone (1743-1787) also had a distinguished political career and was a signer of the Declaration of Independence for Maryland.⁹

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form



Continuation sheet Sunnyside Prince George's County, MD Item number 8 Page 7

HISTORY AND SUPPORT (continued)

Dr. Stone was a prominent and respected member of the community, not only for his family's history. He practiced medicine in Aquasco beginning with his residence there in 1844. He served as Prince George's County's first school examiner from 1868 through his death in 1877.¹⁰ As examiner, he reported to the Board of County School Commissioners on the physical condition of school buildings and the level of teaching in the classrooms. Stone had also amassed a considerable personal estate. In 1860 he owned stocks and bonds valued at \$10,000.¹¹ He lost part of his estate at the close of the Civil War because he had been a slave holder, but in 1876, shortly before his death, his personal estate was worth \$8,200.¹²

Of the Stone's children, only one daughter married.¹³ The Stone siblings resided at Sunnyside throughout their lives, remaining prominent members of the small Aquasco community. Stone's son, Thomas S. Stone (1850-1919) continued as school examiner from his father's death through 1903.¹⁴

After the death of Eleanor Stone in 1948, Sunnyside was left to less closely connected family members. Finally, in 1980, it was sold out of the family.

Sunnyside has had few structural changes since the mid-nineteenth century addition. The rear lean-to porches were enclosed, and the door at the rear of the entrance hall opens into a bathroom instead of the outdoors. The small middle bedroom on the second floor was also converted to a bathroom. During remodeling in the 1940s a modern kitchen was put into the passage between the house and summer kitchen.¹⁵ Probably at the same time a partial basement reinforced with concrete was dug beneath the eighteenth century summer kitchen and the passage. This basement contains the "physical plant" for the house.

¹Fifty Years of Progress, 1900-1950, Prince George's County Public Schools, Annual Report, Prince George's County Board of Education, pg. 1, 15.

²Dielman File, Maryland Historical Society, 201 W. Monument Street, Baltimore, Maryland. File information from the Congressional Biographical Directory, pg. 1576.

³Woodville/Aquasco Historic District; Maryland Historical Trust, State Historic Sites Inventory Form, 1984. Available at Historic Preservation Commission Offices, Room 4010, County Administration Building, Upper Marlboro, Maryland.

⁴United States Census, Prince George's County, Maryland, 1850, Aquasco District #8.

United States Department of the Interior
National Park ServiceNational Register of Historic Places
Continuation SheetSection number 8 Page 8Sunnyside
Prince George's County, Maryland

HISTORY AND SUPPORT (continued)

⁵Prince George's County Land Records, JBB 4:21; and **Windfall of Inherited Treasures**, Betty Carney Taussig, Windfall Publishing Co., Inc., Box 469, Annapolis, Maryland 21404.

⁶Dove's Nest and Dove's Perch are 17th Century tract names for the land Sunnyside is situated on. The 1798 Federal Direct Tax listed Samuel Cave owning 87.5 acres of Dove's Nest and Dove's Perch, improved by a frame dwelling of 24 by 16 feet and having a brick chimney. The exact measurements of the Sunnyside kitchen are 14'2" by 22'3". This is a fairly close match. A definite link between the Samuel Cave property and Sunnyside has not been possible to establish, however.

⁷United States Census, Prince George's County, 1850 and 1860, Aquasco District #8.

⁸Sunnyside was constructed as a 2/3rd "I" house in the 1840s, and was enlarged to a full "I" house by 1860. One other dwelling, the Digges-Sasscer House, P.G. #79-18, constructed in 1845, began as a 2/3rds "I" and had the addition of a west parlor and upper bedroom. Located in Upper Marlboro, the Digges-Sasscer House is in excellent condition. Information on the preservation of its interior detail is not available. The Crandall-Rothstein House, P.G. #79-27, also located in upper Marlboro, was constructed during the 1840s as a low two story 2/3rds "I" house. It had a later 19th century two story north addition, and a one story west addition, giving it a center hall, four parlor plan. The house is in marginal condition and has a great deal of extant interior detail, of mixed date because of its many additions. A third example, P.G. #79-19a, the Turner House, also is located in Upper Marlboro. It was constructed in the early 1850s as an "I" house, and later had the addition of two south parlors, giving it a center hall, four parlor plan. The Turner house has been restored by its owners and is in good condition. There was little interior detail left to restore, because the house had stood vacant and was vandalized before its restoration. The Catherine Gardner House, P.G. #87A-14, located in Baden, is a five bay "I" house constructed in the late 1830s. It is not known if it was originally constructed as a full "I" house. It is in fair condition and appears unoccupied. Two other dwellings, constructed as full "I" houses, are close in date to Sunnyside. P.G. #77-6, Mt. Clare, is located on Woodyard Road. Constructed in the 1850s, it has a center front cross gable and Italianate cornice bracketing, making it a more stylish dwelling than Sunnyside. The final dwelling, P.G. #61-5, the Jones-Hoyert House, dates to 1837. It has had the addition of a two story west wing and a two story 20th century entrance portico. Its Greek Revival stair, with bracketing and turned balusters, is more elaborate than the simple boxed stair at Sunnyside.

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**



Continuation sheet Sunnyside Prince George's County, MD Item number 8 Page 9

HISTORY AND SUPPORT (continued)

⁹Dielman File, op. cit.

¹⁰Fifty Years of Progress, op. cit.

¹¹United States Census, Prince George's County, 1860, Aquasco, District #8.

¹²Land Records of Prince George's County, Tax Assessment, 1876, Aquasco District, Vol. 11056, available Maryland State Archives.


¹³Conversation with Mrs. Joseph K. Taussig, April 1986.

¹⁴Fifty Years of Progress, op. cit.

¹⁵Conversation with Mrs. Joseph K. Taussig, April 1986.

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**



Sunnyside

Continuation sheet Prince George's County, MD Item number 8 Page 10

CHAIN OF TITLE:

5580:322
Sept. 13, 1982
Deed

Betty Carney Taussig to Covington P. Stanwick. For \$10.00 grantor conveys that parcel containing 21.25 acres, a part of parcel conveyed to grantor by 5456:820. Also grants option to purchase remainder of property.

5456:820
Sept. 22, 1981
Deed

Betty Carney Taussig. Division into two parcels property received from Joseph Kneffler Taussig, per. rep. of Estate of Anna Lee Craycroft Turner. Mrs. Turner's will, CMH 4:481, conveyed 49 acres excepting 4 acres, conveyed 696:307, and 2.7 acres, conveyed 3181:388.

2981:624
May 25, 1964
Deed

Paul L. and Naisby W. Herring to Anna Lee Craycroft Turner. Grantors convey 46 acres described in immediately prior deed.

2981:621
May 20, 1964
Deed

Anna Lee and Jeremiah Turner to Paul L. Herring. Grantors convey parcel described in will of Dr. Michael J. Stone, W.A.J. Jr. 1:122. Stone left entire estate to Susan Ann Stone, his wife.

G.S.O. 1:388
April 5, 1948
Will

Will of Nellie B. Stone, last surviving sibling left estate to Anna Lee Craycroft Turner. Conveyed all that parcel described in two deeds, J.B.B. 4:21 and H.B. 3:301.

J.B. 1:602
1899
Will

Will of Susan Ann Stone left estate to Thomas Somerville Stone in trust for her children.

H.B. 3:301
April 18, 1870
Deed

John T. W. Compton and Mary S. Compton to Michael J. Stone. For \$200 grantors convey a part of "Dove's Nest" or "Gravel Walk", containing five acres. This deed formalized a previous improperly executed sale.

J.B.B. 4:21
17 Dec. 1844
Deed

George Morton and Ellen H. Morton to Michael Jenifer Stone. For \$925.87 grantors convey that parcel adjoining Woodville, south of John B. Thomas property and north of W. Bowling's lot. 51 and 7/16 acres, part of a tract known as "William and Mary."

**United States Department of the Interior
National Park Service**

PG: 87B-21

**National Register of Historic Places
Inventory—Nomination Form**

For NPS use only
received
date entered

Sunnyside

Continuation sheet Prince George's County, MD Item number 10 Page 11

GEOGRAPHICAL DATA:

Boundary Description: Beginning at a point where the southern side of Dr. Bowen Road intersects with the west side of Route 381, thence south on Route 381 S. 05° 08' 44" E. 360.22 feet to a point, thence leaving Route 381 and running the following courses and distances: S. 64° 24' 25" W. 248.34 feet; thence S. 78° 20' 34" W. 126.27 feet as shown in the deed to Joel T. Antonioli, et ux (Liber 4421, folio 698) to a point; thence N. 14° 08' 58" W. 52.26 feet to a point; thence S. 80° 20' 37" W. 989.25 feet to an iron pipe set as shown in the deed of Warner E. Waybright, et ux (Liber 3924 folio 787), thence N. 58° 25' 30" W. 182.40 feet as shown in the deed of John W. Yerkie, et ux (Liber 4768 folio 741), thence N. 03° 22' 51" E. 796.26 feet to Dr. Bowen Road, thence following the south side of said Dr. Bowen Road east 1400.71 feet to the point of beginning, containing 21.250 acres, more or less.

Boundary Justification: The 21.25 acres incorporates the built historic resources and the two long vistas of the house from the roadway, particularly from Aquasco Road to the west. The acreage retains the historic setting of the complex. Sunnyside stood on a 50 acre parcel since its construction in 1844. It always has been and remains a highly visible landmark in Aquasco. It is visible across open fields, traveling north or south on Aquasco Road or east and west on Dr. Bowen Road. The vista is an important feature of the property's significance. When the property was sold in 1980, over half of the property, covering the westmost portions, was retained by the former owner.

9. Major Bibliographical References

PG:87B-21

See footnotes in Section 8 beginning on Continuation Sheet No. 7

10. Geographical Data

Acreeage of nominated property 21.25 acres

Quadrangle name Benedict, MD

Quadrangle scale 1:24000

UTM References

A

| | | | | | | | | | | | | | | |
|------|---------|---|---|----------|---|---|---|---|---|---|---|---|---|---|
| 1 | 8 | 3 | 4 | 9 | 2 | 6 | 0 | 4 | 2 | 7 | 2 | 0 | 1 | 0 |
| Zone | Easting | | | Northing | | | | | | | | | | |

B

| | | | | | | | | | | | | | | |
|------|---------|---|---|----------|---|---|---|---|---|---|---|---|---|---|
| 1 | 8 | 3 | 4 | 9 | 7 | 3 | 0 | 4 | 2 | 7 | 1 | 9 | 6 | 0 |
| Zone | Easting | | | Northing | | | | | | | | | | |

C

| | | | | | | | | | | | | | | |
|------|---------|---|---|----------|---|---|---|---|---|---|---|---|---|---|
| 1 | 8 | 3 | 4 | 9 | 7 | 2 | 0 | 4 | 2 | 7 | 1 | 8 | 0 | 0 |
| Zone | Easting | | | Northing | | | | | | | | | | |

D

| | | | | | | | | | | | | | | |
|------|---------|---|---|----------|---|---|---|---|---|---|---|---|---|---|
| 1 | 8 | 3 | 4 | 9 | 2 | 5 | 0 | 4 | 2 | 7 | 1 | 8 | 3 | 0 |
| Zone | Easting | | | Northing | | | | | | | | | | |

E

| | | | | | | | | | | | | | | |
|------|---------|--|--|----------|--|--|--|--|--|--|--|--|--|--|
| | | | | | | | | | | | | | | |
| Zone | Easting | | | Northing | | | | | | | | | | |

F

| | | | | | | | | | | | | | | |
|------|---------|--|--|----------|--|--|--|--|--|--|--|--|--|--|
| | | | | | | | | | | | | | | |
| Zone | Easting | | | Northing | | | | | | | | | | |

G

| | | | | | | | | | | | | | | |
|------|---------|--|--|----------|--|--|--|--|--|--|--|--|--|--|
| | | | | | | | | | | | | | | |
| Zone | Easting | | | Northing | | | | | | | | | | |

H

| | | | | | | | | | | | | | | |
|------|---------|--|--|----------|--|--|--|--|--|--|--|--|--|--|
| | | | | | | | | | | | | | | |
| Zone | Easting | | | Northing | | | | | | | | | | |

Verbal boundary description and justification

See Continuation Sheet No. 11.

List all states and counties for properties overlapping state or county boundaries

| state | N/A | code | county | code |
|-------|-----|------|--------|------|
| state | | code | county | code |

11. Form Prepared By


name/title Marina King, Architectural Historian
 organization Historic Preservation Commission, Room 4010
c/o County Planning Division date September 1986
 street & number 14741 Gov. Oden Bowie Drive telephone (301) 952-3520
 city or town Upper Marlboro state Maryland 20772

12. State Historic Preservation Officer Certification

The evaluated significance of this property within the state is:

national state local

As the designated State Historic Preservation Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the National Park Service.

State Historic Preservation Officer signature  date 4-22-87
 title STATE HISTORIC PRESERVATION OFFICER date

For NPS use only

I hereby certify that this property is included in the National Register

date

Keeper of the National Register

Attest:

date

Chief of Registration

PRINCE GEORGE'S COUNTY
HISTORIC SITES SUMMARY SHEET

P.G. County Survey # 87B-21 Date 1844

Building Name Sunnyside or Michael Stone House

Location Rte. 381 and Dr. Bowen Rd. (SW sector)

Open to Public yes x no

Sunnyside is a two-story, five-bay frame house with gable roof. There is an exterior chimney at each end of the house. A one-story passageway at the south gable end leads to the old one-story kitchen, which has a large fireplace centered in its west wall. A five-bay, one-story porch on the west side of the house has been enclosed. Originally the house was one room deep. The stairway which leads from the center hall to the second floor and attic is partly enclosed, narrow and steep.

Dr. Michael Jenifer Stone, nephew of Thomas Stone, the Signer, of Habre d'Aventure in Charles County, had this house built in 1844. The present owner has papers which show the purchase of the construction materials.

This is a fine example of a mid-19th century southern Prince George's County farmhouse: exterior chimneys, one room deep to allow for air circulation, and boxed staircase.

MARYLAND HISTORICAL TRUST

P.G. 87B 21

INVENTORY FORM FOR STATE HISTORIC SITES SURVEY

1 NAME

HISTORIC

Sunnyside

AND/OR COMMON

Michael Stone House / Turner House

2 LOCATION

STREET & NUMBER

southwest sector of the intersec tion of Rte.381 & Dr.Bowen Rd.

CITY, TOWN

Aquasco

___ VICINITY OF

CONGRESSIONAL DISTRICT

STATE

Maryland

COUNTY

P.G.

3 CLASSIFICATION

| CATEGORY | OWNERSHIP | STATUS | PRESENT USE |
|---|---|--|--|
| <input type="checkbox"/> DISTRICT | <input type="checkbox"/> PUBLIC | <input checked="" type="checkbox"/> OCCUPIED | <input type="checkbox"/> AGRICULTURE <input type="checkbox"/> MUSEUM |
| <input checked="" type="checkbox"/> BUILDING(S) | <input checked="" type="checkbox"/> PRIVATE | <input type="checkbox"/> UNOCCUPIED | <input type="checkbox"/> COMMERCIAL <input type="checkbox"/> PARK |
| <input type="checkbox"/> STRUCTURE | <input type="checkbox"/> BOTH | <input type="checkbox"/> WORK IN PROGRESS | <input type="checkbox"/> EDUCATIONAL <input checked="" type="checkbox"/> PRIVATE RESIDENCE |
| <input type="checkbox"/> SITE | <input type="checkbox"/> PUBLIC ACQUISITION | <input type="checkbox"/> ACCESSIBLE | <input type="checkbox"/> ENTERTAINMENT <input type="checkbox"/> RELIGIOUS |
| <input type="checkbox"/> OBJECT | <input type="checkbox"/> IN PROCESS | <input type="checkbox"/> YES: RESTRICTED | <input type="checkbox"/> GOVERNMENT <input type="checkbox"/> SCIENTIFIC |
| | <input type="checkbox"/> BEING CONSIDERED | <input type="checkbox"/> YES: UNRESTRICTED | <input type="checkbox"/> INDUSTRIAL <input type="checkbox"/> TRANSPORTATION |
| | | <input checked="" type="checkbox"/> NO | <input type="checkbox"/> MILITARY <input type="checkbox"/> OTHER |

4 OWNER OF PROPERTY

NAME

Anna Lee Turner (Mrs. J.E.)

Telephone #: 301-579-6783

STREET & NUMBER

CITY, TOWN

Aquasco

___ VICINITY OF

Maryland

STATE, zip code

5 LOCATION OF LEGAL DESCRIPTION

COURTHOUSE, REGISTRY OF DEEDS, ETC.

Courthouse, Upper Marlboro

Liber #: Will, GSO-1, Folio #: 388

STREET & NUMBER

CITY, TOWN

STATE Maryland

6 REPRESENTATION IN EXISTING SURVEYS

TITLE

not in HABS

DATE

___ FEDERAL ___ STATE ___ COUNTY ___ LOCAL

DEPOSITORY FOR SURVEY RECORDS

CITY, TOWN

STATE

7 DESCRIPTION

| | | | |
|---|---------------------------------------|---|---|
| CONDITION | | CHECK ONE | CHECK ONE |
| <input checked="" type="checkbox"/> EXCELLENT | <input type="checkbox"/> DETERIORATED | <input type="checkbox"/> UNALTERED | <input checked="" type="checkbox"/> ORIGINAL SITE |
| <input type="checkbox"/> GOOD | <input type="checkbox"/> RUINS | <input checked="" type="checkbox"/> ALTERED | <input type="checkbox"/> MOVED DATE _____ |
| <input type="checkbox"/> FAIR | <input type="checkbox"/> UNEXPOSED | | |

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

This house is a two story, five bay, frame house with gable roof. There is an exterior chimney at each end of the house at the ridge. A one story passageway at the south gable end leads to the old one story kitchen. The old kitchen has a large fireplace centered in its west wall. A five bay, one story porch on the west side of the house has been enclosed. Originally the house was one room deep. The stairway leads from the center hall to the second floor and attic. The stairs are partly enclosed, are narrow and steep.

CONTINUE ON SEPARATE SHEET IF NECESSARY

8 SIGNIFICANCE

PG:87B-21

| PERIOD | AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW | | | |
|---|--|---|---|--|
| <input type="checkbox"/> PREHISTORIC | <input type="checkbox"/> ARCHEOLOGY-PREHISTORIC | <input type="checkbox"/> COMMUNITY PLANNING | <input type="checkbox"/> LANDSCAPE ARCHITECTURE | <input type="checkbox"/> RELIGION |
| <input type="checkbox"/> 1400-1499 | <input type="checkbox"/> ARCHEOLOGY-HISTORIC | <input type="checkbox"/> CONSERVATION | <input type="checkbox"/> LAW | <input type="checkbox"/> SCIENCE |
| <input type="checkbox"/> 1500-1599 | <input type="checkbox"/> AGRICULTURE | <input type="checkbox"/> ECONOMICS | <input type="checkbox"/> LITERATURE | <input type="checkbox"/> SCULPTURE |
| <input type="checkbox"/> 1600-1699 | <input checked="" type="checkbox"/> ARCHITECTURE | <input type="checkbox"/> EDUCATION | <input type="checkbox"/> MILITARY | <input type="checkbox"/> SOCIAL/HUMANITARIAN |
| <input type="checkbox"/> 1700-1799 | <input type="checkbox"/> ART | <input type="checkbox"/> ENGINEERING | <input type="checkbox"/> MUSIC | <input type="checkbox"/> THEATER |
| <input checked="" type="checkbox"/> 1800-1899 | <input type="checkbox"/> COMMERCE | <input type="checkbox"/> EXPLORATION/SETTLEMENT | <input type="checkbox"/> PHILOSOPHY | <input type="checkbox"/> TRANSPORTATION |
| <input type="checkbox"/> 1900- | <input type="checkbox"/> COMMUNICATIONS | <input type="checkbox"/> INDUSTRY | <input type="checkbox"/> POLITICS/GOVERNMENT | <input type="checkbox"/> OTHER (SPECIFY) |
| | <input type="checkbox"/> INVENTION | | | |

x local history

SPECIFIC DATES 1844

BUILDER/ARCHITECT

STATEMENT OF SIGNIFICANCE

Dr. Michael Stone, nephew of Thomas Stone, the Signer, of Habre d'Aventure in Charles County, had this house built in 1844. The present owner has papers which show the purchase of the construction materials.

This is a fine example of the mid-19th century southern Prince George's County farmhouse: exterior chimneys, one room deep to allow for air circulation, and boxed staircase.

9 MAJOR BIBLIOGRAPHICAL REFERENCES

Interview with Mr. and Mrs. J.E. Turner, Nov. 1973
Unpublished family papers in their possession.

CONTINUE ON SEPARATE SHEET IF NECESSARY

10 GEOGRAPHICAL DATA

ACREAGE OF NOMINATED PROPERTY _____

VERBAL BOUNDARY DESCRIPTION

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

| STATE | COUNTY |
|-------|--------|
| STATE | COUNTY |

11 FORM PREPARED BY

NAME / TITLE
Mrs. Margaret Cook

| | |
|------------------------------------|--------------|
| ORGANIZATION | DATE |
| P.G.C. Historical & Cultural Trust | August 1978 |
| STREET & NUMBER | TELEPHONE |
| 5621 Delaware Drive | 301-839-3638 |
| CITY OR TOWN | STATE |
| Oxon Hill | Md. 20021 |

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature, to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 Supplement.

The Survey and Inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

RETURN TO: Maryland Historical Trust
The Shaw House, 21 State Circle
Annapolis, Maryland 21401
(301) 267-1438

1705325404
PG # 87B-2-1

MARYLAND HISTORICAL TRUST WORKSHEET

NOMINATION FORM
for the
NATIONAL REGISTER OF HISTORIC PLACES, NATIONAL PARKS SERVICE

SEE INSTRUCTIONS

| | | | | | | |
|---|-------------------------------------|---|--|---|---|--|
| 1. NAME | | | | | | |
| COMMON: | | | | | | |
| AND/OR HISTORIC: Dr. Michael Jenifer Stone House | | | | | | |
| 2. LOCATION | | | | | | |
| STREET AND NUMBER: Dr. Bowen Road | | | | | | |
| CITY OR TOWN: Aquasco | | | | | | |
| STATE: Maryland | | | COUNTY: Prince George's | | | |
| 3. CLASSIFICATION | | | | | | |
| CATEGORY (Check One) | | OWNERSHIP | | STATUS | ACCESSIBLE TO THE PUBLIC | |
| <input type="checkbox"/> District <input checked="" type="checkbox"/> Building <input type="checkbox"/> Site <input type="checkbox"/> Structure <input type="checkbox"/> Object | | <input type="checkbox"/> Public <input checked="" type="checkbox"/> Private <input type="checkbox"/> Both | | Public Acquisition: <input type="checkbox"/> In Process <input type="checkbox"/> Being Considered | <input checked="" type="checkbox"/> Occupied <input type="checkbox"/> Unoccupied <input type="checkbox"/> Preservation work in progress | Yes: <input type="checkbox"/> Restricted <input type="checkbox"/> Unrestricted <input checked="" type="checkbox"/> No |
| PRESENT USE (Check One or More as Appropriate) | | | | | | |
| <input type="checkbox"/> Agricultural | <input type="checkbox"/> Government | <input type="checkbox"/> Park | <input type="checkbox"/> Transportation | <input type="checkbox"/> Comments | | |
| <input type="checkbox"/> Commercial | <input type="checkbox"/> Industrial | <input checked="" type="checkbox"/> Private Residence | <input type="checkbox"/> Other (Specify) | _____ | | |
| <input type="checkbox"/> Educational | <input type="checkbox"/> Military | <input type="checkbox"/> Religious | _____ | _____ | | |
| <input type="checkbox"/> Entertainment | <input type="checkbox"/> Museum | <input type="checkbox"/> Scientific | _____ | _____ | | |
| 4. OWNER OF PROPERTY | | | | | | |
| OWNER'S NAME: Anna Turner | | | | | | |
| STREET AND NUMBER: Dr. Bowen Road | | | | | | |
| CITY OR TOWN: Aquasco | | | STATE: Maryland | | | |
| 5. LOCATION OF LEGAL DESCRIPTION | | | | | | |
| COURTHOUSE, REGISTRY OF DEEDS, ETC: Prince George's County Courthouse | | | | | | |
| STREET AND NUMBER: | | | | | | |
| CITY OR TOWN: Upper Marlboro | | | STATE: Maryland | | | |
| Title Reference of Current Deed (Book & Pg. #): | | | | | | |
| 6. REPRESENTATION IN EXISTING SURVEYS | | | | | | |
| TITLE OF SURVEY: Historic Sites in the Bi-County Region | | | | | | |
| DATE OF SURVEY: 1969 <input type="checkbox"/> Federal <input type="checkbox"/> State <input checked="" type="checkbox"/> County <input type="checkbox"/> Local | | | | | | |
| DEPOSITORY FOR SURVEY RECORDS: The Maryland-National Capital Park and Planning Commission | | | | | | |
| STREET AND NUMBER: 8787 Georgia Avenue | | | | | | |
| CITY OR TOWN: Silver Spring | | | STATE: Maryland | | | |

7. DESCRIPTION

| | | | | | | |
|-----------|---|--|--------------------------------|---|--------------------------------|------------------------------------|
| CONDITION | (Check One) | | | | | |
| | <input type="checkbox"/> Excellent | <input checked="" type="checkbox"/> Good | <input type="checkbox"/> Fair | <input type="checkbox"/> Deteriorated | <input type="checkbox"/> Ruins | <input type="checkbox"/> Unexposed |
| | (Check One) | | | (Check One) | | |
| | <input checked="" type="checkbox"/> Altered | <input type="checkbox"/> Unaltered | <input type="checkbox"/> Moved | <input checked="" type="checkbox"/> Original Site | | |

DESCRIBE THE PRESENT AND ORIGINAL (if known) PHYSICAL APPEARANCE

The house is a two story, frame structure with two story, external brick chimneys with free-standing stacks. The main facade is five bays with a transom lighted central doorway. The windows are 6/6 double hung sash. Across the front is a one story porch with square posts and bracketed cornice.

On the east end is a one story wing built in several sections. It comprises a pantry and the old out-kitchen connected to the house with an enclosed kitchen (formerly just a passage). The kitchen has an external brick chimney with free-standing stack. The sheathing, like that on the house, is weatherboarding.

In plan, the house has a central hall and flanking parlors. The mantelpieces are heavily carved, with brackets supporting the shelves.

SEE INSTRUCTIONS

8. SIGNIFICANCE

PERIOD (Check One or More as Appropriate)

- Pre-Columbian 16th Century 18th Century 20th Century
- 15th Century 17th Century 19th Century

SPECIFIC DATE(S) (If Applicable and Known) 1840

AREAS OF SIGNIFICANCE (Check One or More as Appropriate)

- | | | | |
|---|--------------------------------------|---|--|
| <input type="checkbox"/> Aboriginal | <input type="checkbox"/> Education | <input type="checkbox"/> Political | <input type="checkbox"/> Urban Planning |
| <input type="checkbox"/> Prehistoric | <input type="checkbox"/> Engineering | <input type="checkbox"/> Religion/Phi- | <input type="checkbox"/> Other (Specify) |
| <input type="checkbox"/> Historic | <input type="checkbox"/> Industry | losophy | _____ |
| <input type="checkbox"/> Agriculture | <input type="checkbox"/> Invention | <input type="checkbox"/> Science | _____ |
| <input type="checkbox"/> Architecture | <input type="checkbox"/> Landscape | <input type="checkbox"/> Sculpture | _____ |
| <input type="checkbox"/> Art | Architecture | <input type="checkbox"/> Social/Human- | _____ |
| <input type="checkbox"/> Commerce | <input type="checkbox"/> Literature | itorian | _____ |
| <input type="checkbox"/> Communications | <input type="checkbox"/> Military | <input type="checkbox"/> Theater | _____ |
| <input type="checkbox"/> Conservation | <input type="checkbox"/> Music | <input type="checkbox"/> Transportation | _____ |

STATEMENT OF SIGNIFICANCE

[Empty space for statement of significance]

SEE INST. INSTRUCTIONS

9. MAJOR BIBLIOGRAPHICAL REFERENCES

10. GEOGRAPHICAL DATA

| LATITUDE AND LONGITUDE COORDINATES DEFINING A RECTANGLE LOCATING THE PROPERTY | | | O R | LATITUDE AND LONGITUDE COORDINATES DEFINING THE CENTER POINT OF A PROPERTY OF LESS THAN TEN ACRES | | |
|--|-------------------------|-------------------------|--------|---|-------------------------|--|
| CORNER | LATITUDE | LONGITUDE | | LATITUDE | LONGITUDE | |
| | Degrees Minutes Seconds | Degrees Minutes Seconds | | Degrees Minutes Seconds | Degrees Minutes Seconds | |
| NW | ° ' " | ° ' " | | ° ' " | ° ' " | |
| NE | ° ' " | ° ' " | | ° ' " | ° ' " | |
| SE | ° ' " | ° ' " | | ° ' " | ° ' " | |
| SW | ° ' " | ° ' " | | ° ' " | ° ' " | |

APPROXIMATE ACREAGE OF NOMINATED PROPERTY:

Acreeage Justification:

SEE INSTRUCTIONS

11. FORM PREPARED BY

NAME AND TITLE:
Christopher Owens, Park Historian

ORGANIZATION: M-NCPPC DATE: 3 June 74

STREET AND NUMBER:
8787 Georgia Avenue



CITY OR TOWN: Silver Spring STATE: Maryland

12. State Liaison Officer Review: (Office Use Only)

Significance of this property is:

National State Local

Signature _____



"SUNNYSIDE" (THE MICHAEL J. STONE HOUSE)
RESIDENCE OF MR. AND MRS. C.P. STANWICK
16005 DR. BOWEN ROAD, AQUASCO, MARYLAND

SUNNYSIDE PG:87B-21
Prince George's County
Maryland

MARK ANDRICH
MARCH 1984

YOUNG ACRES

LOT 2

8899

HOWARD W LEAF
3016/267
75.68 A.
P. 69



SUNNYSIDE

PG:87B-21

Prince George's County,
Maryland

sketch map

1987

NETL

SAMUEL
L. CANTER
2.71 A
P. 78

1.54 A
P. 27
P. 30

WILLIAM C GOAD
2475/230
9.60 A
P. 33

2 A. 2.30
35

corn crib

house

meat house

BETTY C TAUSSIG
5456/620
22.04 A
P. 45

VESTHY OF ST PAUL
ST. MARY'S
P. 55

JOHN J. MORALES
5594/888
7.21 A.
P. 57

ELEANOR F. CAR
4277/590
7.00 A.
P. 06

JOHN W. YERKES, JR.
4768/741
69.22 A.
P. 47


5.00 A
P. 84

1 A.
P. 73

5454
/ 482
1.75 A.
P. 49

7.172 A P. 63

P. 112



SUNNYSIDE
PG (87B-21)

DR. BOWEN

ROAD

AQUASCO

ROAD

ST. MARYS

ST

PHILLIPS

ROAD

EAGLE

CHURCH

RD

NECK

WELLS

CREEK

AQUASCO DIST.


No. 8.

Prince George County

Scale 1/4 Inches to the Mile.

BUSINESS NOTICE.


Frank A. Ward & Co.
Dealers in Dry Goods, Groceries, Boots and Shoes, Ready-made Clothing, Hats, Caps, and Notions, Queensware, Hardware, Medicines, etc.
Horse Head P.O. Md.



WOODVILLE
AQUASCO P.O.


Scale 20 Rods per Inch
Entered according to Act of Congress in the year 1878 by G.M. Hopkins, in the Office of the Librarian of Congress at Washington D.C.


PATUXENT RIVER PARK



PG: 87B-21
ADC of Alexandria, Inc., 1993

209133





PG: 87B-21
Sunnyside (Michael Stone House, Turner House)
Benedict Quad, 1953, PR 1974

Swanson

John Wesley Ch

Aquasco

Summerville Creek

Kennedy

Stanley

Drag Strip

Line
PRINCE GEORGES CO
CHARLES CO

Creek

BM

189

160

180

164

160

180

170

160

160

BM

180

160

160

100

100

160

160

100

102

24

74

2

1

47

40

R



P.G.#87B-21

Sunnyside
Aquasco, Prince George's County, MD
Marina King
February 1986
East elevation
Neg: MD Hist. Trust, Annapolis, MD



P.G. #87B-21

Sunnyside
Aquasco, Prince George's County, MD
Marina King
February 1986
West elevation
Neg: MD Hist. Trust, Annapolis, MD



P.G.#87B-21

Sunnyside
Aquasco, Prince George's County, MD
Marina King
February 1986
Main block, south elevation
Breezeway, east elevation
Neg: Md. Hist. Trust, Annapolis, MD



P.G.87B-21

Sunnyside

Aquasco, Prince George's County, MD

Marina King

February 1986

Summer Kitchen, southeast elevation

Neg: Md. Hist. Trust, Annapolis, MD



P.G. #87B-21

Sunnyside
Aquasco, Prince George's County, MD
Marina King
February 1986
West elevation, 18th c. wing
Neg: MD Hist. Trust, Annapolis, MD



P.G. #87B-21

Sunnyside

Aquasco, Prince George's County, MD

Marina King

February 1986

North elevation

Neg: MD Hist. Trust, Annapolis, MD



P.G. #87B-21

Sunnyside
Aquasco, Prince George's County, MD
Marina King
February 1986
Main entrance
Neg: MD Hist. Trust, Annapolis, MD



P. G. #87B-21

Sunnyside
Aquasco, Prince George's County, MD
Marina King
February 1986
Stair hall
Neg: MD Hist. Trust, Annapolis, MD



P.G.#87B-21

Sunnyside
Aquasco, Prince George's County, MD
Marina King
February 1986
Mantel, north bed room
Neg: MD Hist. Trust, Annapolis, MD



106

P.G. #87B-21

Sunnyside
Aquasco, Prince George's County, MD
Marina King
February 1986
Dining room
Neg: MD Hist. Trust, Annapolis, MD



P.G. #87B-21

Sunnyside
Aquasco, Prince George's County, MD
Marina King
February 1986
Stair hall
Neg: MD Hist. Trust, Annapolis, MD



P.G. #87B-21

Sunnyside

Aquasco, Prince George's County, MD

Marina King

February 1986

Mantel, dining room

Neg: MD Hist. Trust, Annapolis, MD



P.G.#87B-21

Sunnyside
Aquasco, Prince George's County, MD
Marina King February 1986
Mantel, north bed room
Neg: MD Hist. Trust, Annapolis, MD



P.G.#87B-21

Sunnyside
Aqua~~x~~co, Prince George's County, MD
Marina King
February 1986
South exits from kitchen to 18th c.
wing
Neg: MD Hist. Trust, Annapolis, MD




P.G.#87B-21

Sunnyside
Aquasco, Prince George's County, MD
Marina King
Feb 1986
Kitchen wing, southwest elevation
Neg: MD Hist. Trust, Annapolis, MD



P.G.#87B-21

Sunnyside
Aquasco, Prince George's County, MD
Marina King
February 1986
Corn crib, southeast elevation
Neg: Md. Hist. Trust, Annapolis, MD



P.G. #87B-21

Sunnyside
Aquasco, Prince George's County, MD
Marina King
February 1986
West exit from kitchen
Neg: MD Hist. Trust, Annapolis, MD



P.G. #87B-21

Sunnyside
Aquasco, Prince George's County, MD
Marina King
February 1986
South exits from kitchen to 18th c. wing
Neg: MD Hist. Trust, Annapolis, MD



P.G. #87B-21

Sunnyside
Aquasco, Prince George's County, MD
Marina King
February 1986
Meat house
Neg: MD Hist. Trust, Annapolis, MD



P.G. #87B-21

Sunnyside
Aquasco, Prince George's County, MD
Marina King
February 1986
Corn crib, detail
Neg: MD Hist. Trust, Annapolis, MD



P. G. #87B-21

Sunnyside
Aquasco, Prince George's County, MD
Marina King
February 1986
Stair to third level
Neg: MD Hist. Trust, Annapolis, MD



NAME DR. STONE HSE # 878-21

LOCATION DR. BOWEN Rd AQUASCO, Md

FACADE NE

PHOTO TAKEN 6/3/74 MDWYER