

Form 10-300
(July 1969)

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

(Type all entries - complete applicable sections)

| | |
|----------------------|------|
| STATE: Maryland | |
| COUNTY: Worcester | |
| FOR NPS USE ONLY | |
| ENTRY NUMBER | DATE |
| | |

1. NAME

COMMON: Genesar

AND/OR HISTORIC: Genezir

2. LOCATION

STREET AND NUMBER:
Maryland Route 611, 9 miles south of U.S. Rt. 50 (west 100 yds)

CITY OR TOWN:
Berlin

STATE: Maryland

| | | |
|------------|----------------------|-------------|
| CODE 24 | COUNTY: Worcester | CODE 047 |
|------------|----------------------|-------------|

3. CLASSIFICATION

| CATEGORY (Check One) | OWNERSHIP | STATUS | ACCESSIBLE TO THE PUBLIC |
|---|--|--|---|
| <input type="checkbox"/> District <input type="checkbox"/> Site <input type="checkbox"/> Object <input checked="" type="checkbox"/> Building <input type="checkbox"/> Structure | <input type="checkbox"/> Public <input checked="" type="checkbox"/> Private <input type="checkbox"/> Both | Public Acquisition: <input type="checkbox"/> In Process <input type="checkbox"/> Being Considered <input type="checkbox"/> Occupied <input type="checkbox"/> Unoccupied <input checked="" type="checkbox"/> Preservation work in progress | Yes: <input type="checkbox"/> Restricted <input type="checkbox"/> Unrestricted <input checked="" type="checkbox"/> No |
| PRESENT USE (Check One or More as Appropriate) | | | |
| <input type="checkbox"/> Agricultural <input type="checkbox"/> Commercial <input type="checkbox"/> Educational <input type="checkbox"/> Entertainment | <input type="checkbox"/> Government <input type="checkbox"/> Industrial <input type="checkbox"/> Military <input type="checkbox"/> Museum | <input type="checkbox"/> Pork <input type="checkbox"/> Private Residence <input type="checkbox"/> Religious <input type="checkbox"/> Scientific | <input type="checkbox"/> Transportation <input checked="" type="checkbox"/> Other (Specify) Vacant <input type="checkbox"/> Comments |

4. OWNER OF PROPERTY

OWNER'S NAME:
Mr. & Mrs. Donald F. Humphrey

STREET AND NUMBER:
2601 Mason Street

CITY OR TOWN: Wheaton

STATE: Maryland

CODE: 24

5. LOCATION OF LEGAL DESCRIPTION

COURTHOUSE, REGISTRY OF DEEDS, ETC.:
Worcester County Courthouse

STREET AND NUMBER:
West Market Street

CITY OR TOWN: Snow Hill

STATE: Maryland

CODE: 24

6. REPRESENTATION IN EXISTING SURVEYS

TITLE OF SURVEY:
Historic American Buildings Survey

DATE OF SURVEY: 1963

Federal State County Local

DEPOSITORY FOR SURVEY RECORDS:
Library of Congress

STREET AND NUMBER:

CITY OR TOWN: Washington

STATE: Dist. of Columbia

CODE: 11

SEE INSTRUCTIONS

STATE: Maryland

COUNTY: Worcester

ENTRY NUMBER

DATE

FOR NPS USE ONLY

7. DESCRIPTION

| | | | | | | |
|--|------------------------------------|---|-------------------------------|--|---|------------------------------------|
| CONDITION | (Check One) | | | | | |
| | <input type="checkbox"/> Excellent | <input type="checkbox"/> Good | <input type="checkbox"/> Fair | <input checked="" type="checkbox"/> Deteriorated | <input type="checkbox"/> Ruins | <input type="checkbox"/> Unexposed |
| | (Check One) | | | (Check One) | | |
| | <input type="checkbox"/> Altered | <input checked="" type="checkbox"/> Unaltered | | <input type="checkbox"/> Moved | <input checked="" type="checkbox"/> Original Site | |
| DESCRIBE THE PRESENT AND ORIGINAL (If known) PHYSICAL APPEARANCE | | | | | | |
| <p>On the north side of Stephen Decatur Memorial Road, Maryland Route 611, on Lower Sinepuxent Neck in Worcester County, approximately nine miles south of United States Route 50, stands a two-and-one-half story brick building on "Genesar" tract. The house is in very poor condition but is being stabilized for future restoration.</p> <p>The Architectural Historian and authority on transitional Maryland architecture, Dr. Henry Chandler Forman, FAIA, frequently cites this building as having some of the most unique pattern brickwork diapering in Maryland. It has extensive diamond and chevron glazed brickwork patterns, which are covered with a nineteenth century thin coat of stucco. As transitional architecture, it represents the hold-over forms of mediaeval work and the earliest development towards the more formal Georgian ideals in plan and design. Dr. Forman records drawings of the unique interior woodwork which has been removed. Because of these unusual architectural features it is considered an important early Maryland building.</p> <p>Its 1971 appearance is little more than a ruin. The south facade is braced with poles extending from a trench in front of the house to the second floor level. A portion of brickwork in the east corner has fallen away, from the ground level to the roof; only a few frames remain at the windows and doors. Temporary supports have been installed to deter further decay. Large portions of the main cornice remain in place and the chimneys are structurally sound above the roof.</p> <p>Originally, the south facade, forty-five feet in length, had four bays at the first floor level and three bays at the second floor level, symmetrically placed. The two center bays of the first story were formerly doors, one leading into the stair passage, the other into the "Great Room". The first story of the north side was similar, but had only two windows on the second story. It had one small window at the stair landing level.</p> <p>Each gable end, 19 feet 3 1/2 inches wide, had small windows at the first and second floor levels flanking the fireplaces at each floor level. On the gable at the attic floor level there is a projecting belt course, above which is glazed diapering. The "A" roof, pitched 51 degrees, has a "kick" to the eave. Originally there were three dormers on the south front, matching the one existing dormer on the north side of the roof.</p> <p>The interior originally had two large rooms, approximately 15 feet by 16 feet and 18 feet by 16 feet, opening from either</p> <p style="text-align: center;">-see continuation sheet-</p> | | | | | | |

SEE INSTRUCTIONS

3. SIGNIFICANCE

PERIOD (Check One or More as Appropriate)

- | | | | |
|--|---------------------------------------|--|---------------------------------------|
| <input type="checkbox"/> Pre-Columbian | <input type="checkbox"/> 16th Century | <input checked="" type="checkbox"/> 18th Century | <input type="checkbox"/> 20th Century |
| <input type="checkbox"/> 15th Century | <input type="checkbox"/> 17th Century | <input type="checkbox"/> 19th Century | |

SPECIFIC DATE(S) (If Applicable and Known)

AREAS OF SIGNIFICANCE (Check One or More as Appropriate)

- | | | | |
|--|---|---|---|
| <input type="checkbox"/> Aboriginal | <input type="checkbox"/> Education | <input checked="" type="checkbox"/> Political | <input type="checkbox"/> Urban Planning |
| <input type="checkbox"/> Prehistoric | <input type="checkbox"/> Engineering | <input type="checkbox"/> Religion/Philosophy | <input checked="" type="checkbox"/> Other (Specify) |
| <input type="checkbox"/> Historic | <input type="checkbox"/> Industry | <input type="checkbox"/> Science | <u>Archaeology</u> |
| <input type="checkbox"/> Agriculture | <input type="checkbox"/> Invention | <input type="checkbox"/> Sculpture | _____ |
| <input checked="" type="checkbox"/> Architecture | <input type="checkbox"/> Landscape Architecture | <input type="checkbox"/> Social/Humanitarian | _____ |
| <input type="checkbox"/> Art | <input type="checkbox"/> Literature | <input type="checkbox"/> Theater | _____ |
| <input type="checkbox"/> Commerce | <input type="checkbox"/> Military | <input type="checkbox"/> Transportation | _____ |
| <input type="checkbox"/> Communications | <input type="checkbox"/> Music | | _____ |
| <input type="checkbox"/> Conservation | | | _____ |

STATEMENT OF SIGNIFICANCE

The house is the only currently known structure of its type on the Eastern Shore of Maryland. It is in very poor condition and is in danger of vandals and the elements. The present owner plans to form an organization to restore the building. It is only two miles from the visitors' center of the Assateague National Seashore, therefore the structure could be a potential tourist attraction as well as a creditable addition to the annual Maryland House and Garden Pilgrimage.

The original Genezir land patent, consisting of 2,200 acres was granted to Colonel William Stevens in 1676. He was appointed one of the eight commanders of the Eastern Shore in 1665; one of eight justices for Somerset County in 1666, which county then consisted of the present counties of Somerset, Worcester, and Wicomico. In 1669, he was the representative for Somerset County to the Maryland General Assembly. He is sometimes referred to as the first citizen of Somerset County. Although a member of the Church of England, he was partially responsible for the introduction of Presbyterianism in Maryland. He resided at his plantation "Rehoboth", on the Pocomoke River.

In 1681, Colonel Stevens sold Genezir to Edward Whaley and Charles Ratcliffe, who in turn divided the land into two equal parts of 1,100 acres each, Ratcliffe taking possession of the part on which the house now stands. Charles Ratcliffe left his dwelling plantation (700 acres) to his son Charles Jr. in 1696, who later left it to his only daughter, Elizabeth (1709).

John Purnell and Elizabeth Ratcliffe were married in 1719, thus bringing the property into the Purnell family. It is believed that the present brick house was constructed during this period, c. 1732. In 1754 John Purnell willed the property to his son Zadock, who at his death, willed it to his daughter, Sally M. Spence, and after her death, to his grandson, Zadock Spence. In 1867 it was sold to Zadock P. Henry, in

-see continuation sheet-

SEE INSTRUCTIONS

9. MAJOR BIBLIOGRAPHICAL REFERENCES

Recorder: Michael Bourne June 1970

Sources:

Forman, Henry Chandlee. Early Manor and Plantation Houses of Maryland. Easton, Maryland: the author, 1934.

Forman, Henry Chandlee. "Genesar on 'The Sea Board Side.'" Maryland Historical Magazine. Vol. L (March 1955), 1-10.

10. GEOGRAPHICAL DATA

| LATITUDE AND LONGITUDE COORDINATES DEFINING A RECTANGLE LOCATING THE PROPERTY | | | O R | LATITUDE AND LONGITUDE COORDINATES DEFINING THE CENTER POINT OF A PROPERTY IF LESS THAN TEN ACRES | | |
|--|-------------------------|-------------------------|--------|---|-------------------------|--|
| CORNER | LATITUDE | LONGITUDE | | LATITUDE | LONGITUDE | |
| | Degrees Minutes Seconds | Degrees Minutes Seconds | | Degrees Minutes Seconds | Degrees Minutes Seconds | |
| NW | 38° 14' 09" | 75° 11' 28" | | | | |
| NE | 38° 14' 09" | 75° 11' 18" | | | | |
| SE | 38° 14' 01" | 75° 11' 18" | | | | |
| SW | 38° 14' 01" | 75° 11' 18" | | | | |

APPROXIMATE ACREAGE OF NOMINATED PROPERTY: 16 acres

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

| STATE: | CODE | COUNTY | CODE |
|--------|------|---------|------|
| | | | |
| STATE: | CODE | COUNTY: | CODE |
| | | | |
| STATE: | CODE | COUNTY: | CODE |
| | | | |
| STATE: | CODE | COUNTY: | CODE |
| | | | |

11. FORM PREPARED BY

NAME AND TITLE:
Mrs. Preston Parish, Keeper of the Maryland Register

ORGANIZATION: Maryland Historical Trust DATE: July 2, 1971

STREET AND NUMBER:
94 College Avenue

CITY OR TOWN: Annapolis STATE: Maryland CODE: 24

12. STATE LIAISON OFFICER CERTIFICATION NATIONAL REGISTER VERIFICATION

As the designated State Liaison Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the National Park Service. The recommended level of significance of this nomination is:

National State Local

Name Orlando Ridout IV
Orlando Ridout IV

Title State Liaison Officer for Maryland

Date July 6, 1971

I hereby certify that this property is included in the National Register.

Chief, Office of Archeology and Historic Preservation

Date _____

ATTEST:

Keeper of The National Register

Date _____

SEE INSTRUCTIONS

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

| | |
|---------------------|------|
| STATE Maryland | |
| COUNTY Worcester | |
| FOR NPS USE ONLY | |
| ENTRY NUMBER | DATE |
| | |

(Continuation Sheet)

(Number all entries)

Genesar

#6. REPRESENTATION IN EXISTING SURVEYS continued

Maryland Register of historic sites and landmarks

1969

Maryland Historical Trust
94 College Avenue

Annapolis, Maryland 21401 Code: 24

Perry, Shaw, and Hepburn Survey

1951

Maryland Historical Trust
94 College Avenue

Annapolis, Maryland 21401 Code: 24

#7. DESCRIPTION continued.

side of a central passage from which a staircase rises. The ceiling joists were exposed with molded edges. There was probably a partition parallel with the front of the fireplace, creating closets beside the fireplace, which would have been lighted by the small windows in the gable wall, according to local practice. The second story rooms had similar treatment but had plaster ceilings, as the beams are unmolded. Photographs and drawings are extant for the "Great Room Chamber" (second story west room), which had three walls with raised paneling. The fireplace wall was plastered, with closet doors and a Federal style mantel.

The main staircase was enclosed, creating a need for the small window recently discovered beneath the stucco on the north facade. The brick wall is one brick thinner in the east corner, and formerly had a small enclosed winding staircase. The small windows were placed so that each closet and passage had a source of light.

In the early nineteenth century, the east staircase was removed. At the same time the enclosure of the central staircase was removed and it was refitted with Federal style spandrels and balustrade. The fireplaces appear to have been altered and

(1 of 2 continuation sheets)

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

(Continuation Sheet)

MHT WO-3

| | |
|---------------------|------|
| STATE Maryland | |
| COUNTY Worcester | |
| FOR NPS USE ONLY | |
| ENTRY NUMBER | DATE |
| | |

(Number all entries)

Genesar

#7. DESCRIPTION continued

the decorative ceiling beams covered with a board ceiling. The two exterior doors in the "Great Room" were bricked-up, made into windows, and trimmed accordingly. Several of the small gable windows were also bricked-up. An ornate moulded cornice with dentils and swags was installed on the south facade, as it appears today.

At the East end of the house lie the foundations of an early kitchen. Photographs taken in the 1930s show a brick structure of later date than the main house.

#8. SIGNIFICANCE continued

whose family it remained until 1939.

The present owner purchased a few acres and the house in 1966 from the Lamar Corporation.

#9. MAJOR BIBLIOGRAPHICAL REFERENCES continued

Forman, Henry Chandlee. Tidewater Maryland Architecture and Gardens. New York: Bonanza Books, 1956.

Torrence, Clayton. Old Somerset on the Eastern Shore of Maryland. reprint. Baltimore: Regional Publishing, 1966.

Worcester County Land Records. Worcester County Courthouse, Snow Hill, Maryland.

Works Progress Administration. Maryland A Guide to the Old Line State. New York: Oxford, 1940.

Worcester County Tax Assessors map #50, Parcel 27. Liber FWH 233 folio 153, Liber FNH 206 folio 603.

5960 / SW
(BERLIN)

484

OCEAN CITY 8 MI. 10'

486

1 330 000 FEET 487



WO-3
Geneser
USGS
Tingles Island Quad

SINEPUXANT

| | | | |
|---|--|--|--|
| 1. STATE Maryland COUNTY Worcester County TOWN Worcester VICINITY STREET NO. Sinepuxent Neck, east of Berlin ORIGINAL OWNER Purnell Family ORIGINAL USE Dwelling PRESENT OWNER Mr. & Mrs. Donald F. Humphrey PRESENT USE Vacant WALL CONSTRUCTION Brick NO. OF STORIES 2-1/2 | | HISTORIC AMERICAN BUILDINGS SURVEY INVENTORY WO - 3 | |
| 2. NAME Genesar (Genezir) DATE OR PERIOD 1732 STYLE Transitional ARCHITECT BUILDER | | 3. FOR LIBRARY OF CONGRESS USE | |
| 4. NOTABLE FEATURES, HISTORICAL SIGNIFICANCE AND DESCRIPTION OPEN TO PUBLIC <u>NO</u> <p>East of Berlin, at the end of Sinepuxent Neck, stands "Genesar" or "Genezir". It is a 2-1/2 story brick structure, four bays wide and two bays deep, in very poor condition.</p> <p>The unusual diamond-shaped parallelogram and chevron brickwork patters, called "diapering" extend to all facades. The glazed headers are a green-black color laid in Flemish bond partially hidden by stucco. The brick chimney caps are handsome.</p> <p>The architectural writer, Mr. Henry Chandlee Forman, frequently cites this building as having some of the most unique examples of patterned brickwork in Maryland. In the "transition" style of architecture, it represents the hold-over forms of mediaeval work and the earliest development towards the more formal Georgian ideas in plan and design. Forman records drawings of its unique interior woodwork which has been taken away by vandals.</p> <p>The sash and doors are missing. The interior has little of the woodwork left. The two central bays of the first floor</p> <p style="text-align: center;">(continued on reverse side)</p> | | | |
| 5. PHYSICAL CONDITION OF STRUCTURE Endangered Interior Exterior | | | |
| 6. LOCATION MAP (Plan Optional) | | 7. PHOTOGRAPH | |
| 8. PUBLISHED SOURCES (Author, Title, Pages) INTERVIEWS, RECORDS, PHOTOS, ETC. Forman, Henry Chandlee - Early Manor and Plantation Houses of Maryland, 1934, page 141. Also Tidewater Maryland Architecture and Gardens, 1956, page 3 | | 9. NAME, ADDRESS AND TITLE OF RECORDER Michael O. Bourne Maryland Historical Trust DATE OF RECORD January 22, 1968 | |

SUPPLEMENTAL INFORMATION AND PHOTOGRAPHS MAY BE ADDED ON SHEET OF SAME SIZE

were doors, leading into a stair hall and living room. There were two small windows on each gable-end. There are only three remaining windows on the second floor, and evidence of three dormers in the roof on the front of the house.




The house recently has been purchased and the present owner hopes to restore it.

Patented in 1676 to William Stevens, it was assigned to Edward Whaley and Charles Ratcliffe in 1679. John Purnell married Elizabeth Ratcliffe - Charles' sister - and the widow of Edward Whaley. Purnell is supposed to have built the house around 1732. It passed to the Henry family in 1867 and remained in that family until 1939.

Drawings to scale available upon written request.

GENESAR

MEASURED DRAWINGS OF GENESAR, BERMH VENTURE, WINDFESTER COUNTY, MARYLAND WERE PREPARED BY STUDENTS OF FLORIDA A & M UNIVERSITY DURING THE WINTER OF 1960. FELLOWSHIP WAS AWARDED BY RICHARD C. CHASINSKI, MURKIN AND ASSTO-CATES AND ROT MASSESWELL, WARD BATHINGTON, D.C. OFFICE. THE DRAWINGS WERE COMPLETED UNDER THE DIRECTION OF ASSISTANT PROFESSOR GRANT V. GENOVA, FLORIDA A & M UNIVERSITY BY STUDENT ARCHITECTS JOHN BARTCHEL, DENISE BERKANT, KENI JOHNSON, MARZEL MANTREI, MARK, NUSSEL MOULTY, JOE MARROE, DAVID OGLE, JED SANTIAGO, FURNO BROWN, AND STEVEN TENACE.




GENESAR PROJECT INFO
 Prepared by: JOHN BARTCHEL, DENISE BERKANT, KENI JOHNSON, MARZEL MANTREI, MARK, NUSSEL MOULTY, JOE MARROE, DAVID OGLE, JED SANTIAGO, FURNO BROWN, AND STEVEN TENACE.
 Date: 1963
 Scale: 1/4" = 1 mile
 Drawing No. 1 of 13 sheets


A

1

2




FIRST FLOOR PLAN




| | | | |
|---|--|---------------------------------|---|
| DRAWN BY: JES SANTARONE 1980 GENESAR PROJECT 1980 SURVEY OF BUILDINGS AND INTERIOR FINISHES WORKING DRAWING NO. 100-24 | GENESAR BERLIN VICINITY, WORCESTER COUNTY, MARYLAND | SHEET NO. 100-24 METRIC 1:25 | METRIC AMERICAN BUILDINGS SURVEY SHEET 2 OF 12 SHEETS |
|---|--|---------------------------------|---|

3




SECOND FLOOR PLAN




| | | | |
|--|--|---------------------------------|---|
| DRAWN BY: W.B. JOHNSON 1980 GENESAR PROJECT 1980 SURVEY OF BUILDINGS AND INTERIOR FINISHES WORKING DRAWING NO. 100-24 | GENESAR BERLIN VICINITY, WORCESTER COUNTY, MARYLAND | SHEET NO. 100-24 METRIC 1:25 | METRIC AMERICAN BUILDINGS SURVEY SHEET 3 OF 12 SHEETS |
|--|--|---------------------------------|---|



4




THIRD FLOOR PLAN




DESIGNED BY JOHN H. BACHELOR 1990
 GENESAR PROJECT 1990
 GENESAR
 BERLIN VICINITY, WORCESTER COUNTY, MARYLAND
 HISTORIC AMERICAN BUILDINGS SURVEY
 SHEET 4 OF 13 SHEETS

5



MATERIALS
 FOUNDATION: BRICK
 WALLS: BRICK PARTIALLY COVERED WITH STUCCO
 ROOFING: CEDAR SHAKES

EAST ELEVATION



DESIGNED BY J. F. MURPHY 1990
 GENESAR PROJECT 1990
 GENESAR
 BERLIN VICINITY, WORCESTER COUNTY, MARYLAND
 HISTORIC AMERICAN BUILDINGS SURVEY
 SHEET 5 OF 13 SHEETS



6




WEST ELEVATION




MATERIALS
 FOUNDATION - BRICK
 WALLS - BRICK PARTIALLY COVERED WITH STUCCO, ENGLISH BOND WEST WALL
 ROOFING - CEDAR SHINGLES

GENESAR PROJECT #190
 GENESAR
 BERLIN VICTORY, WORCESTER COUNTY, MARYLAND

7




NORTH ELEVATION



SOUTH ELEVATION


MATERIALS
 FOUNDATION - BRICK
 WALLS - BRICK PARTIALLY COVERED WITH STUCCO
 NORTH WALL FLEMISH BOND
 ROOFING - CEDAR SHINGLES



GENESAR PROJECT #190
 GENESAR
 BERLIN VICTORY, WORCESTER COUNTY, MARYLAND



8




SECTION A A
LONGITUDINAL SECTION

FEET 3/8" = 1'-0"
METERS 1:32

STEPHEN M. TERACE 1980
 GENESAR PROJECT 1980
 HISTORIC AMERICAN ARCHITECTURAL SURVEY
 SHEET 8 OF 13 SHEETS


9




SECTION B-B
TRANSVERSE SECTION

FEET 3/8" = 1'-0"
METERS 1:32

DAVID R. ORLE 1980
 GENESAR PROJECT 1980
 HISTORIC AMERICAN ARCHITECTURAL SURVEY
 SHEET 9 OF 13 SHEETS




10




| | | |
|---|---|---|
| <p>RUSSELL MOBLEY 1980 GENESAR PROJECT 1980 <small>DESIGN OF ARCHITECTURE AND INTERIOR DECORATION 1000 NORTH WASHINGTON STREET, WASHINGTON, D.C. 20004 (202) 638-1000</small></p> | <p>GENESAR <small>GENESAR PROJECT 1980 1000 NORTH WASHINGTON STREET, WASHINGTON, D.C. 20004 (202) 638-1000</small></p> | <p>HISTORIC AMERICAN BUILDINGS SURVEY SHEET 10 OF 15 SHEETS</p> |
|---|---|---|


11



| | | |
|---|---|---|
| <p>RUSSELL MOBLEY / DRAWN BY: DAVID O. ORLE, JR. GENESAR PROJECT 1980 <small>DESIGN OF ARCHITECTURE AND INTERIOR DECORATION 1000 NORTH WASHINGTON STREET, WASHINGTON, D.C. 20004 (202) 638-1000</small></p> | <p>GENESAR <small>GENESAR PROJECT 1980 1000 NORTH WASHINGTON STREET, WASHINGTON, D.C. 20004 (202) 638-1000</small></p> | <p>HISTORIC AMERICAN BUILDINGS SURVEY SHEET 11 OF 15 SHEETS</p> |
|---|---|---|



12



EAST CORNICE PROFILE
FULL SCALE


WINDOW JAMB MOLDINGS
FULL SCALE

DOOR JAMB MOLDINGS
FULL SCALE

CLOSET MOLDING
FULL SCALE

| | | | |
|---|--|---|---|
| DESIGNED BY RUSSEL MOBLEY 1980 DRUSTORE DRAFTSMAN | TITLE AND DATE OF THIS SHEET GENESAR | SHEET NO. MD-24 | HISTORIC AMERICAN BUILDINGS SURVEY MAY 12 OF 15 SHEETS |
| GENESAR PROJECT 1980 SERIES OF ARCHITECTURAL AND HISTORICAL DRAWINGS FOR THE HISTORIC PRESERVATION OF THIS BUILDING | | BERLIN VICINITY, WORCESTER COUNTY, MARYLAND | |

13



EAST CORNICE ELEVATION
FULL SCALE

| | | | |
|---|--|---|---|
| DESIGNED BY RUSSEL MOBLEY, CHECKED BY DAVID D. GALE, JR. 1980 | TITLE AND DATE OF THIS SHEET GENESAR | SHEET NO. MD-24 | HISTORIC AMERICAN BUILDINGS SURVEY MAY 13 OF 15 SHEETS |
| GENESAR PROJECT 1980 SERIES OF ARCHITECTURAL AND HISTORICAL DRAWINGS FOR THE HISTORIC PRESERVATION OF THIS BUILDING | | BERLIN VICINITY, WORCESTER COUNTY, MARYLAND | |



WO-3

Gibbs Pond

Golf and Yacht Club

BAY

lat. 38° 14' 09"
long. 75° 11' 28"

lat. 38° 14' 09"
long. 75° 11' 28"

lat. 38° 14' 01"
long. 75° 11' 28"

lat. 38° 14' 01"
long. 75° 11' 18"

Knot Point

Knot Point

Green Point

Green Point

TINGLES ISLAND QUADRANGLE
USGS 7.5 minute map
scale: 1: 24 000
1964

Newport Neck

NECK

Spence

STEPHEN SINEPUXEN

LOWER

SINEPUXENT

South Point

Tidal Flat

Light

Tidal Flat

Great Egging Beach

Little Egging Beach

N





GENEZIV

WO-3

2

11/69 Michael BOURNE