

Memo to file

December 30, 2003

From: Peter E. Kurtze
Administrator, Evaluation and Registration

Re: M: 23-144
Mable Bronson Milne Property

The property documented in the following MIHP form has not been formally evaluated for eligibility for listing in the National Register of Historic Places. The comments in the text are those of the preparer of the documentation. The State Historic Preservation Officer has neither concurred nor disagreed with those comments.

CAPSULE SUMMARY SHEET

Survey No.: M:23-144 (PACS 9.37) Construction Date: Circa 1935

Name: Mable Bronson Milne Property

Location: 17119 Old Baltimore Road, Olney vicinity, Montgomery County

Ownership/Present use/Status/Condition/Accessibility

Description:

The Mable Bronson Milne Property is a 2-story, 3-bay Colonial Revival-style house on the south side of Old Baltimore Road in the Olney vicinity, Montgomery County. Constructed circa 1935, the building is rectangular in plan with a small entry porch on the front elevation, a shed roof porch on the east elevation and an addition on the rear elevation. The structure has a side-gable roof with cornice returns and is covered with asphalt shingles. It is of wood-frame construction with a panel-face molded concrete block foundation, wood siding and wood 6/6 double-hung windows. An exterior brick chimney is located on the east elevation. The house has an entry porch centered on the front elevation. It has a gable roof with small cornice returns, supported by slender Doric columns and pilasters.

Significance:

The lot upon which Mable Bronson Milne constructed her house was once part of a larger tract of land which extended along both sides of Georgia Avenue and was used for agricultural purposes. Ward and Cora Savage bought 28.3 hectares (69.89 acres) of land from William E. Dill in 1921. Ward and Cora Savage began subdividing the land into small residential lots along Georgia Avenue and Old Baltimore Road in the late 1920s. Mable Bronson Milne bought a .5 hectare (1.2 acre) parcel from Ward and Cora Savage in 1933. Milne constructed a house on the property circa 1935. The property was sold to Thomas and Phoebe Harrison in 1958. The property was transferred four times until purchased by the current owners, Guy Gran and Theresa Bordon, in 1985. The lot size remains .5 hectares (1.2 acres).

Maryland Historical Trust
Maryland Inventory of Historic Properties Form
Montgomery-Prince George's Short-term Congestion Relief

DOE yes no

1. Name: (indicate preferred name)

historic Mabel Bronson Milne Property (preferred)

and/or common Gran/Borden Property

2. Location:

street & number 17119 Old Baltimore Road N/A not for publication

city, town Olney vicinity of _____ congressional district _____

state Maryland county Montgomery

3. Classification:

Category	Ownership	Status	Present Use	
<input type="checkbox"/> district	<input type="checkbox"/> public	<input checked="" type="checkbox"/> occupied	<input type="checkbox"/> agriculture	<input type="checkbox"/> museum
<input checked="" type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> unoccupied	<input type="checkbox"/> commercial	<input type="checkbox"/> park
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> work in progress	<input type="checkbox"/> education	<input checked="" type="checkbox"/> private residence
<input type="checkbox"/> site	Public Acquisition	Accessible	<input type="checkbox"/> entertainment	<input type="checkbox"/> religious
<input type="checkbox"/> object	<input type="checkbox"/> in process	<input checked="" type="checkbox"/> yes: restricted	<input type="checkbox"/> government	<input type="checkbox"/> scientific
	<input type="checkbox"/> being considered	<input type="checkbox"/> yes: unrestricted	<input type="checkbox"/> industrial	<input type="checkbox"/> other:
	<input checked="" type="checkbox"/> not applicable	<input type="checkbox"/> no	<input type="checkbox"/> military	
			<input type="checkbox"/> transportation	

4. Owner of Property: (give names and mailing addresses of all owners)

name Guy Gran and Theresa A. Borden

street & number 17119 Old Baltimore Road telephone no.:

city, town Olney state and zip code MD 20832

5. Location of Legal Description

Land Records Office of Montgomery County liber 6956

street & number Montgomery County Judicial Center folio 637

city, town Rockville state Maryland

6. Representation in Existing Historical Surveys

title

date federal state county local

depository for survey records

city, town _____ state _____

7. Description

Survey No. M:23-144 (PACS 9.37)

Condition		Check one	Check one	
<input type="checkbox"/> excellent	<input type="checkbox"/> deteriorated	<input type="checkbox"/> unaltered	<input type="checkbox"/> original site	
<input type="checkbox"/> good	<input type="checkbox"/> ruins	<input type="checkbox"/> altered	<input type="checkbox"/> moved	date of move _____
<input type="checkbox"/> fair	<input type="checkbox"/> unexposed			

Resource Count: 3

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

The Mabel Bronson Milne Property is a 2-story, 3-bay Colonial Revival-style house on the south side of Old Baltimore Road in the Olney vicinity, Montgomery County. Constructed circa 1935, the building is rectangular in plan with a small entry porch on the front elevation, a shed roof porch on the east elevation and an addition on the rear elevation.

The structure has a side-gable roof with cornice returns and is covered with asphalt shingles. It is of wood-frame construction with a panel-face molded concrete block foundation, wood siding and wood 6/6 double-hung windows. An exterior brick chimney is located on the east elevation. The house has an entry porch centered on the front elevation. It has a gable roof with small cornice returns, supported by slender Doric columns and pilasters.

Within the entry porch, on the north or front facade, is a 9-panel wood door and 5-light fanlight. The first story has two 6/6 double-hung windows, while the second story had three double-hung windows vertically aligned over the first story openings. All of the windows on the front elevation have wood shutters.

The east elevation has a 1-story porch with an asphalt shingle shed roof porch. The porch is supported by two square wood posts on concrete block piers and has a simple wood railing. Located within the porch is a 9-light wood panel door and a 6/6 double-hung window. The first story also has a pair of 6/6 double-hung windows. The second story contains two 6/6 double-hung windows with wood shutters. Within the open gable end is a wood 6-light casement window. The east elevation of the rear addition has a wood door accessed by an exterior wood staircase.

The rear elevation has a single 6/6 double-hung window on the basement level, four 6/6 double-hung windows on the first story, and two 6/6 double-hung windows on the second story. The 2-story wood-frame rear addition has fenestration on the basement level and first story of the house. It has a 4-light wood panel door and a 6-light metal casement window on the basement level. The first story of the addition has a 2/2 double-hung window, divided horizontally.

The west elevation has a symmetrical fenestration pattern. The basement level has three 3-light awning windows on the basement level, while the first and second stories each have three 6/6 double-hung windows. The attic level has a wood 6-light casement window.

There are two outbuildings associated with this property. The first outbuilding is a garage, with a side-gable roof covered with asphalt shingles. Constructed circa 1935 and rehabilitated in 1997, it is of wood-frame construction with a concrete block foundation, wood siding, 6/6 double-hung windows and a wood overhead door. The structure is located south of the house.

CONTINUATION SHEET

MARYLAND HISTORICAL TRUST

STATE HISTORIC SITES INVENTORY FORM

RESOURCE NAME: Mable Bronson Milne Property

SURVEY NO.: M:23-144 (PACS 9.37)

ADDRESS: 17119 Old Baltimore Road, Olney vicinity, Montgomery County

7. Description (Continued)

The second outbuilding is a shed, with a shed roof covered with metal. Constructed circa 1935, it is of wood-frame construction, on a concrete foundation, with wood siding, 6-light casement windows and a batten door. The structure is located south of the house and garage.

The property is located on the south side of Old Baltimore Road, with a modern residential development to the north, residential property to the east and west and a farmstead to the south.

8. Significance

Survey No. M:23-144 (PACS 9.37)

Period	Areas of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archaeology-prehistoric	<input type="checkbox"/> Community planning	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600-1699	<input type="checkbox"/> architecture	<input type="checkbox"/> education	<input type="checkbox"/> military	<input type="checkbox"/> social/ humanitarian
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	<input type="checkbox"/> theater
<input type="checkbox"/> 1800-1899	<input type="checkbox"/> commerce	<input type="checkbox"/> exploration/settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> transportation
<input checked="" type="checkbox"/> 1900-	<input type="checkbox"/> communication	<input type="checkbox"/> industry	<input type="checkbox"/> politics/government	<input type="checkbox"/> transportation
		<input type="checkbox"/> invention	<input type="checkbox"/> other (specify)	

Specific dates Circa 1935 Builder/Architect Unknown

check: Applicable Criteria: A B C D
and/or
Applicable Exceptions: A B C D E F G
Level of Significance: national state local

Prepare both a summary paragraph of significance and a general statement of history and support.

The lot upon which Mable Bronson Milne constructed her house was once part of a larger tract of land which extended along both sides of Georgia Avenue and was used for agricultural purposes. Ward and Cora Savage bought 28.3 hectares (69.89 acres) of land from William E. Dill in 1921. Ward and Cora Savage began subdividing the land into small residential lots along Georgia Avenue and Old Baltimore Road in the late 1920s. Mable Bronson Milne bought a .5 hectare (1.2 acre) parcel from Ward and Cora Savage in 1933. Milne constructed a house on the property circa 1935. The property was sold to Thomas and Phoebe Harrison in 1958. The property was transferred four times until purchased by the current owners, Guy Gran and Theresa Bordon, in 1985. The lot size remains .5 hectares (1.2 acres).

The Mable Bronson Milne Property is located in the vicinity of Olney. The settlement of Olney began before 1800 as a cross-roads village at the intersection of Brookeville/Washington Pike Road (now Georgia Avenue - MD 97) and Sandy Spring/Mechanicsville Road (now Olney-Sandy Spring Road - MD 108). The initial name for the area was Fair Hill, however it soon became known as Mechanicsville, for the large number of craftsman and artisans who settled at the cross-roads. Olney became the official name of the community in 1851. Olney's importance throughout the nineteenth century derived from its ability to provide goods and services to travelers and the surrounding agricultural region. In 1865, Martenet and Bond's Map of Montgomery County, Maryland shows several businesses, a seminary, schoolhouse and Episcopal Church. Most of the structures were destroyed by fire or demolished for road construction during the twentieth century. Two structures which remain of the historic village of Olney are the St. John's Episcopal Church (1842) and the Olney House (1841) (Maryland Historical Trust Worksheet-Nomination Form: Olney Historic District).

The house on the Mable Bronson Milne Property was constructed in the Colonial Revival style. Popular in the years from 1880 to 1955, the Colonial Revival style resulted from a rebirth of interest in the colonial English and Dutch houses of the eastern seaboard coincident with the Philadelphia Centennial. Stylistic details in Colonial Revival dwellings were drawn predominantly from Georgian and Federal styles; secondary influences included Dutch Colonial and English Postmedieval types. Late nineteenth century examples of Colonial Revival were often asymmetrical and exhibited a combination of Queen Anne features, such as turrets and wide porches, and Colonial features such as Palladian windows and Adamesque swags or urns. Examples built from 1915 to 1935 reflected colonial precedents more closely, while those built after World War II simplified the style, with details which only suggested rather than duplicated the original

CONTINUATION SHEET

MARYLAND HISTORICAL TRUST

STATE HISTORIC SITES INVENTORY FORM

RESOURCE NAME: Mable Bronson Milne Property

SURVEY NO.: M:23-144 (PACS 9.37)

ADDRESS: 17119 Old Baltimore Road, Olney vicinity, Montgomery County

8. Significance (Continued)

examples. Various sub-styles, such as the Dutch Colonial Revival, were popular during the early to mid-twentieth century.

Colonial Revival houses are usually strictly rectangular in plan with few projections and have symmetrical facades. They range from one to three stories with hipped, side-gable, cross-gable, or gambrel roofs. Clapboard is the most popular sheathing material, although brick is not uncommon. After World War II, colonial homes frequently featured a brick-sided first story with an overhanging wood-sided second story. In more elaborate homes, a hipped roof is often topped with a flat deck and balustrade or a cupola. Pedimented doorways and fanlights are common. Some pediments evolved into porticos with slender columns. The typical form of the windows is rectangular with double-hung sash. Palladian windows are common on more sophisticated dwellings. The addition of side porches, terraces and sunrooms are modern features common to Colonial Revival homes (McAlester 1984, 321-6).

National Register Evaluation:

Constructed circa 1935, the Mabel Bronson Milne Property is not eligible for the National Register of Historic Places. The property is not eligible under Criterion A, as research conducted indicates no association with any historic events or trends significant in the development of national, state, or local history. Historic research indicates that the property has no association with persons who have made specific contributions to history, and therefore, it does not meet Criterion B. It is not eligible under Criterion C, as it is a ubiquitous building type which lacks architectural significance. The property is common of mid-twentieth century suburban residences that integrated simplified elements of popular styles into basic building configurations. The house is not a significant example of mid-twentieth century Colonial Revival design, as it lacks such characteristic features as a pedimented door surround and dentil molding, and has an addition on the rear elevation. Finally, preliminary studies conducted for this project indicate the need for further assessment of the archaeological potential of this property. Therefore, no evaluation under Criterion D is being conducted at this time.

MARYLAND HISTORICAL TRUST

Eligibility recommended _____ Eligibility Not Recommended _____

Comments _____

Reviewer, OPS: _____ Date: _____

Reviewer, NR Program: _____ Date: _____

9. Major Bibliographical References

Survey No. M:23-144(PACS 9.37)

See Attached

10. Geographical Data

Acreage of nominated property _____
Quadrangle name Sandy Spring Quadrangle scale 1:24,000

Verbal boundary description and justification

List all states and counties for properties overlapping state or county boundaries

state code county code

state code county code

11. Form Prepared By

name/title Tim Tamburrino

organization P.A.C. Spero & Company

date May 1998

street & number 40 W. Chesapeake Avenue, Suite 412

telephone (410) 296-1635

city or town Baltimore

state Maryland

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust
DHCP/DHCD
100 Community Place
Crownsville, MD 21032-2023
(410) 514-7600

CONTINUATION SHEET

MARYLAND HISTORICAL TRUST

STATE HISTORIC SITES INVENTORY FORM

RESOURCE NAME: Mable Bronson Milne Property

SURVEY NO.: M:23-144 (PACS 9.37)

ADDRESS: 17119 Old Baltimore Road, Olney vicinity, Montgomery County

9. Major Bibliographical References (Continued)

- Boyd, T.H.S. 1968. The History of Montgomery County, Maryland, From its Earliest Settlement in 1650 to 1879. Baltimore: Regional Publishing Company.
- Brugger, Robert A. 1988. Maryland, A Middle Temperament 1634-1980. Baltimore and London: Johns Hopkins University Press.
- Coleman, Margaret Marshall. 1984. Montgomery County: A Pictorial History. Rev. 1990. Norfolk and Virginia Beach: The Donning Company Publishers.
- Farquhar, Roger Brooke. 1962. Old Homes and History of Montgomery County, Maryland. Washington: Judd and Detweiler, Inc.
- Hiebert, Ray Eldon, and Richard K. MacMaster. 1976. A Grateful Remembrance: the Story of Montgomery County, Maryland. Rockville, Maryland: Montgomery County Government and the Montgomery County Historical Society.
- Hopkins, G.M. [1879] 1975. Atlas of 15 Miles Around Washington including the County of Montgomery, Maryland. Reprint. Rockville, Maryland: Montgomery County Historical Society.
- Land Records of Montgomery County, Maryland.
- Martenet, Simon J. [1865] 1975. Martenet and Bond's Map of Montgomery County, Maryland. Reprint. Rockville, Maryland: Montgomery County Historical Society.
- Maryland Historical Trust Worksheet - Nomination Form for the National Register of Historic Places, National Park Service. Olney Historic District, Capsule Summary (M:23-98).
- McAlester, Virginia and Lee. A Field Guide to American Houses. New York: Alfred A. Knopf.
- Tindall, George Brown. 1984. America: A Narrative History. 2 vols. New York: W.W. Norton & Company, Inc.

CONTINUATION SHEET

MARYLAND HISTORICAL TRUST

STATE HISTORIC SITES INVENTORY FORM


RESOURCE NAME: Mable Bronson Milne Property

SURVEY NO.: M:23-144 (PACS 9.37)

ADDRESS: 17119 Old Baltimore Road, Olney vicinity, Montgomery County

10. Geographical Data (Continued)

Resource Sketch Map:



CONTINUATION SHEET

MARYLAND HISTORICAL TRUST

STATE HISTORIC SITES INVENTORY FORM

RESOURCE NAME: Mable Bronson Milne Property

SURVEY NO.: M:23-144 (PACS 9.37)

ADDRESS: 17119 Old Baltimore Road, Olney vicinity, Montgomery County

Maryland Comprehensive Historic Preservation Plan Data Sheet

Historic Context:

MARYLAND COMPREHENSIVE PRESERVATION PLAN DATA

Geographic Organization:

Piedmont

Chronological/Developmental Period Theme (s):

Modern Period A.D. 1930-Present

Prehistoric/Historic Period Theme(s):

Architecture

RESOURCE TYPE:

Category (see Section 3 of survey form):

Building

Historic Environment (urban, suburban, village, or rural):

Suburban


Historic Function(s) and Use(s):

Private Residence

Known Design Source (write none if unknown):

None

Montgomery-Prince George's Short-term
Congestion Relief
Town/County Olney vicinity / Montgomery
Quad Sandy Spring, MD
Survey No. M:23-144 (PACS 9.37)
Property Name Mable Bronson Milne Property





M. 23-144

MABLE BRONSON MILNE PROPERTY

MONTGOMERY CO., MD

TIM TAMBURRINO

4-98

ASBESTOS

MARYLAND SHAD

FRONT ELEVATION

79



M-23-144

MABLE BRONSON MILNE PROPERTY

MONTGOMERY Co., MD

TIM TAMBURRINO

4-98

COLLECTOR'S NAME

MARYLAND SHPO

NORTHWEST CORNER

2/9



M-23-144

MABLE BRANSON MILNE PROPERTY
MONTGOMERY CO., MD

TIM TIMBERLINE

4-98

0040071 000000

MARYLAND SHPO

WEST ELEVATION

319



M-23-144

MABLE BRANSON MILNE PROPERTY

MONTGOMERY Co., MD

TIM TAMBURRINO

4-98

353271 48840

MARYLAND SHPO

SOUTHWEST CORNER

4/9



M-23-144

MABLE BRONSON MILNE PROPERTY

MONTGOMERY Co., MD

TIM TIMBURRING

4-98

0040271 N N N 24

MARYLAND SHPO

REAR ELEVATION

519



M-23-14U

MABLE BRANSON MILNE PROPERTY

MONTGOMERY CO., MD

TIM TAMBUKINO

H-98

MARYLAND SHPO

DETAIL OF FRONT ENTRANCE

6/9



M-23-144

MABLE BRONSON MILNE PROPERTY
MONTGOMERY CO., MD

TIM TAMBURRINO

4-98 10001 HUNTERS

MARYLAND SHPO

GARAGE AND SHED

7/9



M-23-144

MABLE BRANSON MILNE PROPERTY

MONTGOMERY Co., MD

TIM TAMBURRINO

4-98

2009 2002 11/14/03

MARYLAND STATE

GARAGE, VIEW FROM WEST

8/9



M-23-144

MABLE BRONSON MILNE PROPERTY

MONTGOMERY Co., MD

TIM TAMBURRINO

4-98

05/20/22 9:44 AM

MARYLAND SHPB

SHED, VIEW FROM WEST

9/9