

MARYLAND HISTORIC PRESERVATION PLAN INFORMATION

RESOURCE NAME: "Moorfield" Yellow Brick House

MHT INVENTORY NUMBER: WI-9

MARYLAND COMPREHENSIVE PLAN DATA

1. Historic Period Theme(s): Architecture
2. Geographic Orientation: Eastern Shore
3. Chronological/Development Period(s): Agricultural-Industrial Transition
1815-1870
4. Resource Type(s): Single-family dwelling

**Maryland Historical Trust
State Historic Sites Inventory Form**

1. Name (indicate preferred name)

historic Moorfield

and/or common Yellow Brick House

2. Location

street & number 22342 Capitola Road not for publication

city, town Cox's Corner vicinity of congressional district First

state Maryland county Wicomico

3. Classification

| | | | | |
|---|--|---|--|---|
| Category | Ownership | Status | Present Use | |
| <input type="checkbox"/> district | <input type="checkbox"/> public | <input checked="" type="checkbox"/> occupied | <input type="checkbox"/> agriculture | <input type="checkbox"/> museum |
| <input checked="" type="checkbox"/> building(s) | <input checked="" type="checkbox"/> private | <input type="checkbox"/> unoccupied | <input type="checkbox"/> commercial | <input type="checkbox"/> park |
| <input type="checkbox"/> structure | <input type="checkbox"/> both | <input type="checkbox"/> work in progress | <input type="checkbox"/> educational | <input checked="" type="checkbox"/> private residence |
| <input type="checkbox"/> site | Public Acquisition | Accessible | <input type="checkbox"/> entertainment | <input type="checkbox"/> religious |
| <input type="checkbox"/> object | <input type="checkbox"/> in process | <input checked="" type="checkbox"/> yes: restricted | <input type="checkbox"/> government | <input type="checkbox"/> scientific |
| | <input type="checkbox"/> being considered | <input type="checkbox"/> yes: unrestricted | <input type="checkbox"/> industrial | <input type="checkbox"/> transportation |
| | <input checked="" type="checkbox"/> not applicable | <input type="checkbox"/> no | <input type="checkbox"/> military | <input type="checkbox"/> other: |

4. Owner of Property (give names and mailing addresses of all owners)

name Mr. Edward W. Warns

street & number 22342 Capitola Road telephone no.:

city, town Tyaskin state and zip code Maryland 21865

5. Location of Legal Description

courthouse, registry of deeds, etc. Wicomico County Clerk of Court Map 54, Parcel 21
liber 902

street & number Wicomico County Courthouse folio 163

city, town Salisbury state MD 21801

6. Representation in Existing Historical Surveys

title Maryland Inventory of Historical Properties

date 1976 federal state county local

depository for survey records Maryland Historical Trust

city, town Crownsville state MD 21032

7. Description

Survey No. WI-9

| | | | |
|--|---------------------------------------|---|---|
| Condition | | Check one | Check one |
| <input type="checkbox"/> excellent | <input type="checkbox"/> deteriorated | <input type="checkbox"/> unaltered | <input checked="" type="checkbox"/> original site |
| <input checked="" type="checkbox"/> good | <input type="checkbox"/> ruins | <input checked="" type="checkbox"/> altered | <input type="checkbox"/> moved |
| <input type="checkbox"/> fair | <input type="checkbox"/> unexposed | | date of move _____ |

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

The two-story, five-bay brick dwelling commonly known as the "Yellow Brick House" stands on property known as "Moorfield." The 41.13-property, bounded by Capitola Road along the southwest side, is located southeast of Cox's Corner, Wicomico County, Maryland. The house faces southwest with the gable roof oriented on a northwest/south east axis.

Estimated to date around 1815-20, the two-story common bond brick house is supported by raised common bond brick foundation, and the house is covered by a medium pitched gable roof sheathed with asphalt shingles. Attached to the southeast side is a two-story, three-bay frame addition.

The southwest (main) facade is a symmetrical five-bay elevation laid in three-course common bond. A center boarded up entrance is flanked by pairs of nine-over-six sash windows. Each window opening features a wooden jack arch that boasts a center keyblock. The nine-over-six sash windows are framed by a narrow beaded edge surround fitted with mid nineteenth century shutter hinges. The second floor is defined by five evenly spaced nine-over-six sash windows finished in the same fashion with wooden jack arches and molded keyblock. The window surrounds have shutter hinges, and a few twisted iron shutter hooks remain imbedded in the brick wall. Finishing the base of the roof is an elaborate boxed cornice featuring paired modillion blocks that taper inward in a graceful curve.

The northwest gable end is a five-course common bond wall defined by a slightly asymmetrical fenestration. Three nine-over-six sash windows light the first and second floors, and each window has a wooden jack arch and stepped keyblock. Shutter hardware remains consistent with the front wall. The center bay windows are located off axis in order to light the northeast room. The third floor or attic is defined by a pair of six-over-six sash windows that flank the interior end brick chimney. The edge of the roof is trimmed with a plain bargeboard.

The northeast (rear) wall follows in the same symmetrical fenestration as the front wall with a center door and flanking nine-over-six sash windows. The flush six-panel door features a narrow beaded edge that frames each door panel. The door reveals are paneled in the same manner. Fixed between the doorway and the overhead transom is a narrow lintel embellished with an intricate row of gougework. The second floor is lighted by five evenly spaced nine-over-six sash windows. The base of the roof is finished with the same paired block cornice found on the front of the house.

The southeast gable end is partially covered by the two-story frame wing sheathed with vinyl siding and covered by a medium pitched asphalt shingle roof. Two six-over-six sash windows are located above the addition roof and light the attic of the main block on each side of an interior end brick chimney.

The interior of the main block follows a four-room plan with a corner stair rising in the southwest entrance hall. The staircase boasts an early nineteenth century turned newel post and slender rectangular balusters that support a circular profile handrail.

8. Significance

| Period | Areas of Significance—Check and justify below | | | |
|---|--|---|---|--|
| <input type="checkbox"/> prehistoric | <input type="checkbox"/> archeology-prehistoric | <input type="checkbox"/> community planning | <input type="checkbox"/> landscape architecture | <input type="checkbox"/> religion |
| <input type="checkbox"/> 1400–1499 | <input type="checkbox"/> archeology-historic | <input type="checkbox"/> conservation | <input type="checkbox"/> law | <input type="checkbox"/> science |
| <input type="checkbox"/> 1500–1599 | <input type="checkbox"/> agriculture | <input type="checkbox"/> economics | <input type="checkbox"/> literature | <input type="checkbox"/> sculpture |
| <input type="checkbox"/> 1600–1699 | <input checked="" type="checkbox"/> architecture | <input type="checkbox"/> education | <input type="checkbox"/> military | <input type="checkbox"/> social/ humanitarian |
| <input type="checkbox"/> 1700–1799 | <input type="checkbox"/> art | <input type="checkbox"/> engineering | <input type="checkbox"/> music | <input type="checkbox"/> theater |
| <input checked="" type="checkbox"/> 1800–1899 | <input type="checkbox"/> commerce | <input type="checkbox"/> exploration/settlement | <input type="checkbox"/> philosophy | <input type="checkbox"/> transportation |
| <input type="checkbox"/> 1900– | <input type="checkbox"/> communications | <input type="checkbox"/> industry | <input type="checkbox"/> politics/government | <input type="checkbox"/> other (specify) |
| | | <input type="checkbox"/> invention | | |

Specific dates **Builder/Architect**

check: Applicable Criteria: A B C D
and/or
Applicable Exception: A B C D E F G

Level of Significance: national state local

Prepare both a summary paragraph of significance and a general statement of history and support.

Although an exact date has not surfaced for the construction of the impressive Moorfield house, the common bond walls, the tall and narrow proportions of the two-story, four-room plan dwelling coupled with the distinct Federal character of the exterior and interior finishes, suggest the building program took place around 1815-20. Particularly fine architectural finishes include the paired block cornices that define the base of the roof as well as the keyblock jack arches that span the nine-over-six sash windows. Interior brick bearing walls divide the first floor into four rooms with the stairhall occupying the southwest corner.

The 1815-20 construction date suggests that Charles Jones financed construction of the house after his purchase of the property from George Jones in April 1814, paying \$4,000 for the plantation. (1) Although a specific acreage is not listed in the 1814 deed, the year before George Jones purchased the 400-plantation from Littleton Ayres for \$5,000.(2) The decrease in the value of the property in one year is not explained other than as a result of a reduction in the amount of land that was transferred. The Somerset County Court of Chancery forced sale of the property following Charles Jones' death. Trustee James Wilson sold the Moorfield plantation to Levin Walter in June 1833.(3) At Levin Walter's direction, "my dwelling plantation with the exception of fifty acres" was intended to pass to James H. Walter according to his 1846 will, proved two years later.(4) James H. Walter held title to the Moorfield house and plantation lands, then comprising around 359 acres, until his death in the mid 1850s. During the second half of the nineteenth century the property was purchased by Noah J. Tilghman, who was the proprietor of "Tyaskin Mills," which processed local timber as well as cereal grains. A store, operated by W. G. and J. Q. Tilghman, was located along the Whitehaven-Tyaskin road in front of the house.(5) Noah J. And Carrie P. Tilghman retained ownership of the brick house and approximately 370 acres until 1885 when the property was sold.(6) During the first quarter of the twentieth century the farm remained intact under the ownership of William W. Culver, Jr. and later Franklin B. Culver, who maintained ownership with other family members until 1927.(7)

The house deserves listing in *Category A*, which identifies buildings of high architectural and historic merit. Moorfield is eligible for listing on the National Register of Historic Places.

9. Major Bibliographical References

Survey No. WI-9

10. Geographical Data

Acreeage of nominated property _____

Quadrangle name _____

Quadrangle scale _____

UTM References do NOT complete UTM references

A
 Zone Easting Northing

B
 Zone Easting Northing

C

D

E

F

G

H

Verbal boundary description and justification

List all states and counties for properties overlapping state or county boundaries

| state | code | county | code |
|-------|------|--------|------|
| | | | |

| state | code | county | code |
|-------|------|--------|------|
| | | | |

11. Form Prepared By

name/title Paul B. Touart, Architectural Historian

organization Private Consultant date 7/1/96

street & number P. O. Box 5 telephone 410-651-1094

city or town Westover state Maryland 21871

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust
 Shaw House
 21 State Circle
 Annapolis, Maryland 21401
 (301) 269-2438

MARYLAND HISTORICAL TRUST
 21 STATE CIRCLE
 ANNAPOLIS, MARYLAND 21401
 (301) 269-2438
 FAX (301) 269-2438

8.1 SIGNIFICANCE

Moorfield (Yellow Brick House) WI-9
Cox's Corner vicinity

FOOTNOTES

1 Somerset County Land Record, JP 2/83, 4/2/1814, Somerset County Courthouse.

2 Somerset County Land Record, JP 1/75, 3/6/1813, Somerset County Courthouse.

3 Somerset County Land Record, GH 7/26, Somerset County Courthouse.

4 Somerset County Register of Wills, JP 5/144, 5/30/1846, Somerset County Courthouse.

5 John L. Graham, ed. *The 1877 Atlases and other Early Maps of the Eastern Shore of Maryland*. Salisbury, Maryland: Peninsula Press, 1976.

6 Wicomico County Land Record, TF, Jr. 2/113, 4/18/1870, Wicomico County Courthouse.

7 Wicomico County Land Record, IDT 146/504, 1/18/1927, Wicomico County Courthouse.

WI-9
Moorfield
(Yellow Brick House)
Cox's Corner vicinity
Private

Map 54, Parcel 21

JWTS 719/195

Jack Brookes
Eleanor Brookes

to

9/15/1970

Reuben Friedman
Sylvia Friedman

40.5 acres, Plat drawn by Roy E. Moore, S.W.C.
1/15/1935, IDT 191/73

JWTS 698/24

David T. Eisen, Gloria B. Eisen
William F. Magers, Margaret Magers, Montgomery
County, Maryland

to

8/8/1969

Loren Goodman
Jack Brookes

JWTS 624/200

Permanent Builders Company

to

10/15/1965

David T. Eisen, Gloria B. Eisen
William F. Magers, Margaret Magers
40.9 acres

WI-9
Moorfield
(Yellow Brick House)
Cox's Corner vicinity
Chain of title continued

Page 2

JWTS 602/253

Theodore R. Willis
Marie R. Willis

to

12/31/1964

Permanent Builders Co.

IDT 191/71

Allan W. Mezick, et ux.

to

1/19/1935

Theodore R. Willis
Marie P. Willis

40.9 acres

IDT 146/504

Franklin B. Culver, et al; E. Capitola White
Culver, Irving C. Jones, Ella Jones

to

1/18/1927

Allan W. Mezick

"Brick House Farm" same land conveyed to
George Jones by Littleton Aires, 3/6/1813

303 21/100 acres

WI-9
Moorfield
(Yellow Brick House)
Cox's Corner vicinity
Chain of title continued

Page 3

EAT 49/4

William W. Culver, Jr.
Sarah A. Culver

to

3/5/1906

Benjamin R. Dashiell
Irving C. Jones
Franklin B. Culver

\$5,000 Moorfield 303 21/100 acres

JTT 29/286

Isaac J. Street

to

5/20/1901

William W. Culver, Jr.

\$3,000 300 acres "Moore field"

SPT 7/366

Noah J. Tilghman
Carrie P. Tilghman

to

7/15/1885

Isaac J. Street

\$2,500

WI-9
Moorfield
(Yellow Brick House)
Cox's Corner vicinity
Chain of title continued

Page 4

TF, Jr. 2/113

Purnell Toadvine

to

4/18/1870

Noah J. Tilghman

\$2,100 "Moorsfield" by purchase of the real estate of John Q. Robertson at a sale made by William Howard, late sheriff

370 acres

Somerset County
Land Record

LW 6/241

John W. Crisfield, Trustee

to

8/30/1859

Samuel White
John Q. Robertson

Decree of Circuit Court in Somerset County, 4/10/1857, William J. Willing vs. George B. Cooper and Ann W. Cooper, "Moorsfield" and being the same farm on which James H. Walter resided at the time of his death containing by estimation 359 acres

WI-9
Moorfield
(Yellow Brick House)
Cox's Corner vicinity
Chain of title continued

Page 5

Somerset County
Register of Wills

Last Will and Testament of Levin Walter

JP 5/144

First, I give and devise unto my son James
H. Walter my dwelling plantation with the
exception of fifty acres

Written
5/30/1846
Proved
6/27/1848

GH 7/26

James Wilson, Trustee

to

6/18/1833

Levin Walter

Court of Chancery, 12/2/1831, make sale of
real estate of Charles Jones, deceased

JP 2/83

George Jones

to

4/2/1814

Charles Jones

\$4,000.00 "Moorfields"

WI-9
Moorfield
(Yellow Brick House)
Cox's Corner vicinity
Chain of title continued

Page 6

JP 1/75

Littleton Ayres

to

3/6/1813

George Jones

\$5,000 400 acres

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

| | |
|------------------|--|
| FOR NPS USE ONLY | |
| RECEIVED | |
| DATE ENTERED | |

NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

SEE INSTRUCTIONS IN HOW TO COMPLETE NATIONAL REGISTER FORMS
TYPE ALL ENTRIES -- COMPLETE APPLICABLE SECTIONS

1 NAME

HISTORIC

AND/OR COMMON

Yellow Brick House

2 LOCATION

Northeast side of Maryland Route 352, .4 mile east
of its junction with Maryland Route 349

CITY, TOWN

Bivalve

NOT FOR PUBLICATION

CONGRESSIONAL DISTRICT

First

STATE

Maryland

VICINITY OF

CODE
24

COUNTY
Wicomico

CODE
045

3 CLASSIFICATION

CATEGORY

- DISTRICT
- BUILDING(S)
- STRUCTURE
- SITE
- OBJECT

OWNERSHIP

- PUBLIC
- PRIVATE
- BOTH
- PUBLIC ACQUISITION**
- IN PROCESS
- BEING CONSIDERED

STATUS

- OCCUPIED
- UNOCCUPIED
- WORK IN PROGRESS
- ACCESSIBLE**
- YES: RESTRICTED
- YES: UNRESTRICTED
- NO

PRESENT USE

- AGRICULTURE
- MUSEUM
- COMMERCIAL
- PARK
- EDUCATIONAL
- PRIVATE RESIDENCE
- ENTERTAINMENT
- RELIGIOUS
- GOVERNMENT
- SCIENTIFIC
- INDUSTRIAL
- TRANSPORTATION
- OTHER: Vacant

4 OWNER OF PROPERTY

NAME Loren Goodman and Ruben and Sylvia Friedman

STREET & NUMBER

8805 Flower Street

CITY, TOWN

Silver Spring

VICINITY OF

STATE

Maryland 21209

5 LOCATION OF LEGAL DESCRIPTION

COURTHOUSE,
REGISTRY OF DEEDS, ETC.

Wicomico County Courthouse

STREET & NUMBER

North Division Street

CITY, TOWN

Salisbury

STATE

Maryland 21801

6 REPRESENTATION IN EXISTING SURVEYS

TITLE

DATE

FEDERAL STATE COUNTY LOCAL

DEPOSITORY FOR
SURVEY RECORDS

CITY, TOWN

STATE

7 DESCRIPTION

WI-9

| CONDITION | | CHECK ONE | CHECK ONE |
|------------------------------------|--|---|---|
| <input type="checkbox"/> EXCELLENT | <input checked="" type="checkbox"/> DETERIORATED | <input checked="" type="checkbox"/> UNALTERED | <input checked="" type="checkbox"/> ORIGINAL SITE |
| <input type="checkbox"/> GOOD | <input type="checkbox"/> RUINS | <input type="checkbox"/> ALTERED | <input type="checkbox"/> MOVED DATE _____ |
| <input type="checkbox"/> FAIR | <input type="checkbox"/> UNEXPOSED | | |

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

The Yellow Brick House is located on the northeast side of Maryland Route 352, .4 mile east of its junction with Maryland Route 349, near Bivalve in Wicomico County, Maryland.

It is a Federal-style brick dwelling of two stories, five bays wide and three deep. The facade faces south and is very simple; the only decoration is the rusticated wood lintels with keystones and the cornice. The latter consists of pairs of brackets on a facing of flutes. The house is laid in an early common bond with five courses of stretchers between each row of headers.

The east gable end is punctuated by asymmetrical openings, with a door with paneled, recessed jambs on the southeast and two windows, one above the other, on the northeast. These are topped by two symmetrical but fairly large gable windows which, like the corresponding windows in the west gable end, do not have wooden lintels. The west gable end has two rows of three windows each placed symmetrically beneath the gable windows. Remaining shutter dogs are evident on some windows. The outline of an early wing is evident on the east gable, particularly above the door.

On the first floor are three rooms and a stairhall. The main entrance opens into the stair passage with a short set of stairs ascending the south wall to a small, square landing before rising to the second floor along the east gable wall. A small room with a projecting fireplace and associated cupboard opens from the west; directly north from the passage is the door to the great room. The fireplace here, which projects into the room, has a mantel highly carved with diamond and other motifs. Like all the other rooms upstairs and down, the great room has chairrail and baseboard, but the chairrail is incised with geometric/floral designs and, unlike the other rooms, it has a cornice (which appears to be of plaster). Also opening to the north from the passage is the remaining downstairs room which is lightly larger than the southwest room. There is a projecting fireplace with carved mantel in poor condition and the remains of a cupboard, the top of which was once glazed. The east gable door opens from the passage and there is a small closet door leading to storage space beneath the staircase.

On the second floor three chambers open from the U-shaped passageway which leads to a staircase to the attic. The north rooms have fireplaces with carved mantels, whereas the small southwest room is without a fireplace and very simply decorated.

See continuation sheet #1

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

FOR NPS USE ONLY

RECEIVED

DATE ENTERED

Yellow Brick House
Bivalve,
Maryland

CONTINUATION SHEET

ITEM NUMBER 7

PAGE 1

DESCRIPTION (continued)

The window jambs upstairs and down are paneled. The ceilings are plastered. The doors are hung with early butt hinges. The window sash have small muntins with some remaining old glass.

The interior of the house is in a very deteriorated state; however, a buyer who wants to restore the building is in the wings.

| PERIOD | AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW | | | | |
|---|--|---|---|--|--|
| REHISTORIC | <input type="checkbox"/> ARCHEOLOGY-PREHISTORIC | <input type="checkbox"/> COMMUNITY PLANNING | <input type="checkbox"/> LANDSCAPE ARCHITECTURE | <input type="checkbox"/> RELIGION | |
| <input type="checkbox"/> 1400-1499 | <input type="checkbox"/> ARCHEOLOGY-HISTORIC | <input type="checkbox"/> CONSERVATION | <input type="checkbox"/> LAW | <input type="checkbox"/> SCIENCE | |
| <input type="checkbox"/> 1500-1599 | <input type="checkbox"/> AGRICULTURE | <input type="checkbox"/> ECONOMICS | <input type="checkbox"/> LITERATURE | <input type="checkbox"/> SCULPTURE | |
| <input type="checkbox"/> 1600-1699 | <input checked="" type="checkbox"/> ARCHITECTURE | <input type="checkbox"/> EDUCATION | <input type="checkbox"/> MILITARY | <input type="checkbox"/> SOCIAL/HUMANITARIAN | |
| <input type="checkbox"/> 1700-1799 | <input type="checkbox"/> ART | <input type="checkbox"/> ENGINEERING | <input type="checkbox"/> MUSIC | <input type="checkbox"/> THEATER | |
| <input checked="" type="checkbox"/> 1800-1899 | <input type="checkbox"/> COMMERCE | <input type="checkbox"/> EXPLORATION/SETTLEMENT | <input type="checkbox"/> PHILOSOPHY | <input type="checkbox"/> TRANSPORTATION | |
| <input type="checkbox"/> 1900- | <input type="checkbox"/> COMMUNICATIONS | <input type="checkbox"/> INDUSTRY | <input type="checkbox"/> POLITICS/GOVERNMENT | <input type="checkbox"/> OTHER (SPECIFY) | |
| | | <input type="checkbox"/> INVENTION | | | |

SPECIFIC DATES *circa 1810*

BUILDER/ARCHITECT

STATEMENT OF SIGNIFICANCE

This house is situated on a tract of land which first appears in the records on December 2, 1760, when Jacob Aires' 323-acre property, "Aires Purchase," was resurveyed to include 370 acres of vacant land. The new 693-acre tract was called "Moorefields." In 1765 part of this tract was sold to Daniel and Elizabeth McIntyre (Deed C/264); circa 1780 it came into the hands of their son, John (Will EB 1/141). The 1783 tax assessment, however, lists the parts of "Moorefield" in possession of Willin McIntyre (42 3/4 acres) and Betty McIntyre (42 1/4 acres) leading one to believe that John had leased this land to his brother and his mother. Littleton Aires also owned part of "Moorfields" on this assessment.

George and Amelia Aires obtained part of Moorefield from the McIntyres in 1785 (Deed H/64). He is listed on the 1798 federal tax assessment as the owner of a one-story, wooden dwelling in good repair, with several outbuildings, valued at \$450.00. Littleton and Sarah E. Aires acquired part of Moorefield from George Aires in 1806 (Will EB 23/106 and Deed P/106). They retained the property until 1813 when it was sold to George and Leah Jones.

The present "yellow brick house" was built in the first decade of the 19th century, thus either by George or Littleton Aires.

The Yellow Brick House is one of the largest Federal-style dwellings extant in Wicomico County. This simple house has little architectural decoration and a refined, conservative appearance characteristic of Federal architecture. The detail present is of interest: double keystones with splayed lintels and an unusual cornice which is perhaps a rural adaptation of a classical triglyph-metope frieze.

9 MAJOR BIBLIOGRAPHICAL REFERENCES

WI-9

Clay, Anne. "Moorfield and the Yellow Brick House: A History." Unpublished research paper, copy in files of Maryland Historical Trust, Annapolis, Maryland.

10 GEOGRAPHICAL DATA

ACREAGE OF NOMINATED PROPERTY 4

UTM REFERENCES

| | | | |
|---|------|---------|----------|
| A | ZONE | EASTING | NORTHING |
| C | ZONE | EASTING | NORTHING |

| | | | |
|---|------|---------|----------|
| B | ZONE | EASTING | NORTHING |
| D | ZONE | EASTING | NORTHING |

VERBAL BOUNDARY DESCRIPTION

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

| STATE | CODE | COUNTY | CODE |
|-------|------|--------|------|
| STATE | CODE | COUNTY | CODE |

11 FORM PREPARED BY

| | | |
|-----------------|--|------------------------|
| NAME / TITLE | Robert L. McFarlin, M.D.; Pamela James | bjn 9/76 |
| ORGANIZATION | Maryland Historical Trust | DATE |
| STREET & NUMBER | 21 State Circle | TELEPHONE 301-267-1438 |
| CITY OR TOWN | Annapolis | STATE Maryland 21401 |

12 STATE HISTORIC PRESERVATION OFFICER CERTIFICATION

THE EVALUATED SIGNIFICANCE OF THIS PROPERTY WITHIN THE STATE IS:

NATIONAL _____ STATE _____ LOCAL _____

As the designated State Historic Preservation Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the National Park Service.

STATE HISTORIC PRESERVATION OFFICER SIGNATURE

TITLE DATE

| | |
|--|------|
| FOR NPS USE ONLY | |
| I HEREBY CERTIFY THAT THIS PROPERTY IS INCLUDED IN THE NATIONAL REGISTER | |
| DIRECTOR, OFFICE OF ARCHEOLOGY AND HISTORIC PRESERVATION | DATE |
| ATTEST: | DATE |
| KEEPER OF THE NATIONAL REGISTER | |

9 MAJOR BIBLIOGRAPHICAL REFERENCES

WI-9

Clay, Anne. "Moorfield and the Yellow Brick House: A History." Unpublished research paper, copy in files of Maryland Historical Trust, Annapolis, Maryland.

10 GEOGRAPHICAL DATA

ACREAGE OF NOMINATED PROPERTY 4

UTM REFERENCES

| | | | |
|---|------|-------------|---------------|
| A | 1 8 | 4 2 6 5 2 0 | 4 2 3 9 4 4 0 |
| | ZONE | EASTING | NORTHING |
| C | | | |

| | | | |
|---|------|---------|----------|
| B | | | |
| | ZONE | EASTING | NORTHING |
| D | | | |

VERBAL BOUNDARY DESCRIPTION

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

| STATE | CODE | COUNTY | CODE |
|-------|------|--------|------|
| STATE | CODE | COUNTY | CODE |

11 FORM PREPARED BY

NAME / TITLE

Robert L. McFarlin, M.D.; Pamela James

bjn
9/76

ORGANIZATION

Maryland Historical Trust

DATE

STREET & NUMBER

21 State Circle

TELEPHONE

301-267-1438

CITY OR TOWN

Annapolis

STATE

Maryland 21401

12 STATE HISTORIC PRESERVATION OFFICER CERTIFICATION

THE EVALUATED SIGNIFICANCE OF THIS PROPERTY WITHIN THE STATE IS:

NATIONAL

STATE

LOCAL

As the designated State Historic Preservation Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the National Park Service.

STATE HISTORIC PRESERVATION OFFICER SIGNATURE

John N. Pearce 6/18/77

TITLE

DATE

FOR NPS USE ONLY

I HEREBY CERTIFY THAT THIS PROPERTY IS INCLUDED IN THE NATIONAL REGISTER

DATE

DIRECTOR, OFFICE OF ARCHEOLOGY AND HISTORIC PRESERVATION

TEST:

DATE

KEEPER OF THE NATIONAL REGISTER

12

WI-9

WETIPQUIN NECK

20'

Wetipquin

WETIPQUIN

Wetipquin Ferry

Traskin

Home Gulch

7

Deep

NANTICOKE 3.5 MI. (NANTICOKE)

349

St Marys Sch

Creek

New Town

Yellow Brick House

385

Wetipquin Quad


17'30"

Nigger I


Nigger I Gulch

Creek

Tr



1



Wetipquin Quad

Yellow Brick House

TYASKIN

Dist. No. 3
WICOMICO CO.



WARE WINRIGHT. Dealer in Dry Goods, Groceries, Hats, Caps, Boots, Shoes, Hardware, Queensware, Glassware, Notions, &c., and all goods usually kept in a country store. Whitehaven P. O.

W. G. & J. Q. TILGEMAN. Dealers in Dry Goods, Groceries, Hats, Caps, Boots, Shoes, Hardware, Queensware, Glassware, Cattery, Tobacco, Cigars, Notions, &c. Tyaskin, Md.

JOHN WILLING AND CO. Dealer in Dry Goods, Groceries, Hats, Caps, Shoes, Hardware, Queensware, Glassware, Notions and all articles usually kept in a country store. Nanticoke P. O.

S. A. LANGRALL. Dealer in Dry Goods, Groceries, Hats, Caps, Boots, Shoes, Hardware, Queensware, Glassware, and all articles usually kept in a first class country store. Store near M. E. Church, Nanticoke Point.

JNO. TURNER AND SON, Dealers in Dry Goods, Groceries, Hardware, Queensware, Boots, Shoes, &c. Nanticoke, Md.

J. A. CONRAWAY. Physician and Surgeon. Office and Res. near M. E. Church, Nanticoke Point.

J. H. ELLIOTT. Dealer in Dry Goods, Groceries, Hats, Caps, Boots, Shoes, Hardware, Queensware, Glassware, Ready-made clothing, Eastons, Patent Medicines, Notions, and all goods usually kept in a first class country store. Store at Green Hill.

TYASKIN DISTRICT BUSINESS REFERENCES.


W. J. CATLIN, M. D., Physician and Surgeon. All calls promptly attended to. Res. and Office at Belgrade Farm, P. O., Tyaskin, Md.

W. D. HEATH, Dealer in Groceries, Hardware, Tobacco, Liquors, &c. Tyaskin, Md.

NOAH J. TILGEMAN, Proprietor of "Tyaskin Mills," Manufacturer of Corn-meal, Hominy, and all kinds of Lumber. Custom work done in sawing and grinding.

J. E. B. HORNER, Owner of the fine Sloop "James Wesley." All kinds of freighting done to and from any point on the "Chesapeake Bay," or its tributaries. Especial Attention to the purchase and freighting of Oysters, Res. and P. O., Tyaskin, Md.

J. W. WINGATE, Dealer in Dry Goods, Groceries, Hats, Caps, Hardware, Queensware, Glassware, Ready-made clothing, Confectionery, Wines, Whiskies, Brandies and Kums, and all articles usually kept in a first class country store, at Whitehaven.



40

39

17'30"

38

37

36

160 000
FEET

35

WI-9
Moorfield (Yellow Brick House)
Cox's Corner vicinity

Wetipquin, Maryland Quadrangle
1983

Light
WICOMICO CO
OMERSET CO
Child



VI-9

MOORFIELD

COX'S CORNER VICINITY, NICOBARAS ISLANDS
WEST ELEVATION

6/96, PAUL TOUHAUT, PHOTOGRAPHER

NEG. / MD HISTORICAL TRUST



W1-9

MOORFIELD

COX'S CORNER VIC., WICOMICO CO., MD.

NORTHWEST ELEVATED

6/96, PAUL TOUANT, PHOTOGRAPHER

NEG, / MD HISTORICAL TRUST



W1-9

MOORFIELD

COY'S CORNER VICINITY, WINDSOR Co. Vt.

EAST ELEVATION

6/96, PAUL TOURIST, PHOTOGRAPHER

NEG. / M.D. HISTORICAL TRUST



W1-9

MORNING

Coy's CORNER vic. Wicomico
County, MD.

NW CORNER

6/96, Paul Toward, MD

MEG. / MD. HISTORICAL TRUST



W-9 YELLOW BRICK HOUSE

12