CAPSULE SUMMARY SHEET

Survey No.: M:32-11 **Construction Date:** 1931-circa 1955

Name: North Hills of Sligo Park

Location: Bounded by Granvill Drive, Colesville Road, and Brunett Avenue, Four Corners vicinity, Montgomery County

Private Ownership / Present Use: Private Residence / Occupied / Condition: Good / Restricted Access

Description:

The residential subdivision of North Hills of Sligo Park is located in the Four Corners vicinity of Montgomery County. North Hills of Sligo Park was developed by E. Brooke Lee, president of the North Washington Realty Company, in 1931. The development continued the grid pattern of streets established by the 1926 plat of Argyle Park, located to the north and west of the North Hills of Sligo Park. The street pattern becomes increasingly curvilinear as the community extends south. Along these streets were platted over 200 building lots in three sections between 1931 and the early 1940s. The community was developed on land purchased from Victor Brunett in 1930. The land first passed into the Brunett family in the early 1860s and a large Gothic Revival house was constructed by Louis Brunett between 1860 and 1863. E. Brooke Lee used the house as the centerpiece of his new development and used its image in advertising campaign. The house also served as offices for the real estate company. The subdivision was platted with lot sizes of between 5000 and 9800 square feet. The streets were paved, though no curbing or streetlights were provided. Curbs were later added to some streets. North Hills of Sligo Park also lacked parkland or other public amenities. The large lots and expensive houses constructed by the North Washington Realty Company were difficult to sell during the Depression years with many lots remaining unsold. Eventually the bank had to foreclose on the North Hills of Sligo Creek properties. By 1941, only 90 houses had been constructed, and only three-quarters of the development had been completed by 1948.

Significance:

The community was developed by E. Brooke Lee, through the North Washington Realty Company. E. Brooke Lee was a Silver Spring native whose family owned a substantial amount of land in southern Montgomery County. Lee introduced the legislation establishing the Maryland-National Capital Park & Planning Commission, helped draft the Capper-Cramton legislation, and worked with the State Roads Commissions to develop new thoroughfares in the county. The North Washington Realty Company was Lee's real estate and building firm, however, he formed and built under a number of corporations to protect each subdivision from the failure of another. These included: the North City Land Company, Sligo Park Development Company, the Silver Spring Investment Company, and the Fairway Land Company. Lee was involved in the subdivision of land and home construction in more than half of the subdivisions platted in Silver Spring throughout the 1920s and early 1930s. He did not build all of the houses in the subdivisions he platted, though the North Washington Realty Company had established fifteen house designs that could be built in a number of subdivisions (Secrist 57-61).

Although the North Washington Realty Company is responsible for the design and construction of some houses within the North Hills of Sligo Park, the architects for most of the houses are not known. The models are variations on basic house designs constructed around many cities in the early to mid-twentieth century. The houses closely resemble the residences in the nearby developments of Argyle Park, Argyle Club Forest, Fairway, Sligo Park Knolls, Woodside Park, and Greenacres, among many others located elsewhere in the Washington, D.C. suburbs. The houses represent Colonial Revival designs modified for modest house designs. The residences possess the building form and some features of the Colonial Revival style, but on a smaller scale and with inexpensive modern materials, such as molded door surrounds and metal casement windows. The community is identical to hundreds of other developments constructed on the periphery of cities during the early to mid-twentieth century. The construction of this specific development does not represent a historic trend that made a significant contribution to the development of the nation, state, or community. The development does not possess distinctive design features or innovative concepts that would distinguish this development from others. The community does not include significant elements of architecture, landscape architecture, engineering, or artwork. It is a simple and prevalent community of modest structures with Colonial Revival and modern influences. The modest structures have a reserved use of architectural detail, therefore integrity of the individual resources is critical. Many of the houses in the community have replacement windows and additions. The community lacks comprehensive design features such as public space, ceremonial entrances, pathways, or original streetlights.

Preparer:
KCI Technologies, Inc.
January 2000

Survey No. M:32-11

Maryland Historical Trust
Maryland Inventory of Historic Properties

DOE ☐ yes ☐ no

1. Name (indicate preferred name)

historic North Hills of Sligo Park (Preferred)

and/or common

2. Location

street & number: Bounded by Granvill Drive, Colesville Road, and Brunett Avenue ☐ not for publication

city, town Silver Spring, vicinity of Silver Spring congressional district

state Maryland county Montgomery

3. Classification

Category	Ownership	Status	Present Use	
☒ district	☐ public	☒ occupied	☐ agriculture	☐ museum
☐ building(s)	☒ private	☐ unoccupied	☐ commercial	☐ park
☐ structure	☐ both	☐ work in progress	☐ educational	☒ private residence
☐ site	**Public Acquisition**	**Accessible**	☐ entertainment	☐ religious
☐ object	☐ in process	☒ yes: restricted	☐ government	☐ scientific
	☐ being considered	☐ yes: unrestricted	☐ industrial	☐ transportation
	☒ not applicable	☐ no	☐ military	☐ other:

4. Owner of Property (give names and mailing addresses of all owners)

name Multiple Owners

street & number: telephone no.:

city, town state and zip code:

5. Location of Legal Description

courthouse, registry of deeds, etc. Montgomery County Judicial Center liber:

street & number 50 Maryland Avenue folio:

city, town Rockville state Maryland

6. Representation in Existing Historical Surveys

title

date ☐ federal ☐ state ☐ county ☐ local

depository for survey records

city, town state

7. Description

Survey No. M:32-11

Condition		Check one	Check one	
☐ excellent	☐ deteriorated	☐ unaltered	☒ original site	
☒ good	☐ ruins	☒ altered	☐ moved	date of move

Resource Count: approx. 200

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

The residential subdivision of North Hills of Sligo Park is located in the Four Corners vicinity of Montgomery County. North Hills of Sligo Park is one of several residential subdivisions platted along Forest Glen Road in the Four Corners vicinity between the late 1920s and the early 1950s. Developers and home buyers were attracted to this area because of the easy access into the District of Columbia and the numerous recreation amenities, including the Silver Spring Branch of the Boy's and Girl's Club, Sligo Creek Parkway, the Argyle Country Club, and the Indian Springs Country Club.

A number of subdivisions were constructed by various developers on the north side of Forest Glen Road in the late 1940s and early 1950s. It was not unusual for streets within a subdivision to end abruptly, since developers anticipated the streets being continued by the next subdivision or during the next phase of house construction. As such, it is common for roads to extend through several subdivisions even though there is no relationship between the developers. North Hills of Sligo Park was developed by E. Brooke Lee, president of the North Washington Realty Company, in 1931. The development continued the grid pattern of streets established by the 1926 plat of Argyle Park, located to the north and west of the North Hills of Sligo Park. The street pattern becomes increasingly curvilinear as the community extends south. Along these streets were platted over 200 building lots in three sections between 1931 and the early 1940s. The community was developed on land purchased from Victor Brunett in 1930. The land first passed into the Brunett family in the early 1860s and a large Gothic Revival house was constructed by Louis Brunett between 1860 and 1863. E. Brooke Lee used the house as the centerpiece of his new development and used its image in advertising campaign. The house also served as offices for the real estate company.

The subdivision was platted with lot sizes of between 5000 and 9800 square feet. The streets were paved, though no curbing or streetlights were provided. Curbs were later added to some streets. North Hills of Sligo Park also lacked parkland or other public amenities. The large lots and expensive houses constructed by the North Washington Realty Company were difficult to sell during the Depression years with many lots remaining unsold. Eventually the bank had to foreclose on the North Hills of Sligo Creek properties. By 1941, only 90 houses had been constructed, and only three-quarters of the development had been completed by 1948.

Dwelling Types: North Hills of Sligo Creek contains a variety of suburban building styles. The most common styles are Colonial Revival with both 2-story and 1-story versions.

Colonial Revival, 2-story: Most of the residences were constructed in the Colonial Revival style. A typical example of the prevalent 2-story Colonial Revival-style model has 3-bays with a central entrance and a brick exterior. One of the gable ends has a semi-exterior brick chimney. The entrance has a Colonial Revival door surround consisting of fluted pilasters often topped by a triangular or broken pediment with dentil molding. The original windows are wood 6/6 double-hung, though many have been replaced by vinyl units. A feature common to all of these residences is a small casment or double-hung window centered on the second story above the entrance. Though side porches were not standard on this model, many have been added. Some sub-types of this model include examples with small entry porches, full-height porticos, and Tudor Revival detailing. Examples: 9619 Brunett Avenue, owner: Todd and Dawn Harris (See Photo 24 of 27), and 9602 Sutherland Road, owner Douglas and S.W. Taylor (See Photo 25 of 27).

Colonial Revival, 1-story: The 1-story model constructed within North Hills of Sligo Park is a mid-twentieth century suburban building form with Revival-style details. The buildings form is created by the intersection of a principal low-pitched side-gable roof with a projecting front-gable section. The houses are typically constructed of brick and may have a front porch. The windows are double-hung with picture and bay windows common. Examples: 9518 Bruce Drive, owner: H.F. and E.G. Stegman (See Photo 26 of 27), and 9404 Thornhill Road, owner: Bruce Drake (See Photo 27 of 27).

8. Significance

Survey No. M:32-11

Period	Areas of Significance – Check and justify below				
☐ prehistoric	☐ archaeology-prehistoric	☐ community planning	☐ landscape architecture	☐ religion
☐ 1400-1499	☐ archeology-historic	☐ conservation	☐ law	☐ science
☐ 1500-1599	☐ agriculture	☐ economics	☐ literature	☐ sculpture
☐ 1600-1699	☐ architecture	☐ education	☐ military	☐ social/ humanitarian
☐ 1700-1799	☐ art	☐ engineering	☐ music	☐ theater
☐ 1800-1899	☐ commerce	☐ exploration/settlement	☐ philosophy	☐ transportation
☒ 1900-	☐ communications	☐ industry	☐ politics/government	☐ other (specify)
	☐ invention			

Specific Dates 1931-circa 1955 **Builder Architect** North Washington Realty Company

check: Applicable Criteria: ☐ A ☐ B ☐ C ☐ D
and/or
Applicable Exception: ☐ A ☐ B ☐ C ☐ D ☐ E ☐ F ☐ G

Level of Significance: ☐ national ☐ state ☐ local

Prepare both a summary paragraph of significance and a general statement of history and support

The community of North Hills of Sligo Park is located in the vicinity of Four Corners, Montgomery County. Four Corners began as a 19th-century agricultural community located at the crossroads of Bladensburg and Colesville Roads. The community remained rural until the post-World War I building boom in suburban Montgomery County. Beginning in the late 1930s, Four Corners saw the development of Northwood Park, Woodmoor, Indian Spring Village, Indian Spring Terrace, North Hills of Sligo Park, and Fairway, among others. These subdivisions expanded between 1945 and 1955 even as new ones, such as Northwood and Franklin Knolls, were constructed. The single-family house subdivisions that soon surrounded Four Corners had winding streets that formed an irregular grid in between major roads. Commercial establishments lined Bladensburg Road (now University Boulevard) and Colesville Road. The Woodmoor Shopping Center, established in 1946, is one landmark of the community. Four Corners was largely developed by the late 1950s.

North Hills of Sligo Park was developed by the North Washington Development Company in three sections beginning in 1931. The sale of large lots and expensive homes for affluent buyers proved to be too great a challenge for the realty company during the depression years. Most lots were unsold by 1935 and the bank was forced to foreclose on the undeveloped lots within the community. Despite this, the community continued to slowly develop throughout the 1930s and 1940s. By 1948, three-quarters of the lots had been improved by houses.

The community was developed by E. Brooke Lee, through the North Washington Realty Company. E. Brooke Lee was a Silver Spring native whose family owned a substantial amount of land in southern Montgomery County. Like his father, he entered politics and influenced the development of the county through policy and administration. Lee introduced the legislation establishing the Maryland-National Capital Park & Planning Commission, helped draft the Capper-Cramton legislation, and worked with the State Roads Commissions to develop new thoroughfares in the county (Secrist, 57-58).

The North Washington Realty Company was Lee's own real estate and building firm, however, he formed and built under a number of corporations to protect each subdivision from the failure of another. These included: the North City Land Company, Sligo Park Development Company, the Silver Spring Investment Company, and the Fairway Land Company. Lee was involved in the subdivision of land and home construction in more than half of the subdivisions platted in Silver Spring throughout the 1920s and early 1930s. He did not build all of the houses in the subdivisions he platted, though the North Washington Realty Company had established fifteen house designs that could be built in a number of subdivisions (Secrist 60-61).

Although the North Washington Realty Company is responsible for the design and construction of some houses within the North Hills of Sligo Park, the architects for most of the houses are not known. The models are variations on basic house

8. Significance (Continued)

designs constructed around many cities in the early to mid-twentieth century. The houses closely resemble the residences in the nearby developments of Argyle Park, Argyle Club Forest, Fairway, Sligo Park Knolls, Woodside Park, and Greenacres, among many others located elsewhere in the Washington, D.C. suburbs. The houses represent Colonial Revival designs modified for modest house designs. The residences possess the building form and some features of the Colonial Revival style, but on a smaller scale and with inexpensive modern materials, such as molded door surrounds and metal casement windows.

National Register Evaluation:

Character-defining elements for Planned Suburban Developments, as defined in the I-495/I-95 Capital Beltway Corridor Transportation Improvement Study, include 1) concentration of historically or aesthetically-cohesive buildings; 2) community design with planned landscape and public amenities; 3) single period of construction; 4) architecturally-significant suburban building types. To be considered eligible for the National Register of Historic Places, Planned Suburban Developments must possess excellent integrity of all character-defining elements. North Hills of Sligo Park does not contain public amenities or a planned landscape design and does not possess architecturally-significant suburban building types.

Constructed between 1931 and the early 1950s, North Hills of Sligo Park is not eligible for the National Register of Historic Places. The property is not eligible for the National Register do to the ubiquitous nature of the resource. The community is identical to hundreds of other developments constructed on the periphery of cities during the early to mid-twentieth century. The construction of this specific development does not represent a historic trend that made a significant contribution to the development of the nation, state, or community. The development does not possess distinctive design features or innovative concepts that would distinguish this development from others, and therefore is not eligible under Criterion A. Historic research indicates that the community has no association with persons who have made specific contributions to history, and therefore, it does not meet Criterion B. It is not eligible under Criterion C, as the community does not include significant elements of architecture, landscape architecture, engineering, or artwork. It is a simple and prevalent community of modest structures with Colonial Revival and modern influences. The modest structures have a reserved use of architectural detail, therefore integrity of the individual resources is critical. Many of the houses in the community have replacement windows and additions. The community lacks comprehensive design features such as public space, ceremonial entrances, pathways, or original streetlights. Finally, investigations have not been conducted to determine whether the property has the potential to yield information important in history or pre-history, therefore, National Register Criterion D can not be assessed at this time.

MARYLAND HISTORICAL TRUST

Eligibility recommended — Eligibility Not Recommended: XX

Comments:

Reviewer, OPS: [signature] Date: 9/11/00

Reviewer, NR Program: [signature] Date: 10/12/00

9. Major Bibliographical References

Survey No. M:32-11

See Continuation Sheet

10. Geographical Data

Acreage of nominated property

Quadrangle name Kensington, MD

Quadrangle scale 1:24,000

Verbal boundary description and justification
N/A

List all states and counties for properties overlapping state or county boundaries

state	code	county	code
state	code	county	code

11. Form Prepared By

name/title Tim Tamburrino	
organization KCI Technologies, Inc.	date January 2000
street & number 10 North Park Drive	telephone 410-316-7800
city or town Hunt Valley	state/zip Maryland, 21030

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

Return to:

Maryland Historical Trust
DHCP/DHCD
100 Community Place
Crownsville, MD 21032-2023
410-514-7600

9. Major Bibliographical References (Continued)

Baist, G. Wm. *Washington, D.C. and Suburbs*. Philadelphia, 1918.

Deets, Edward H., and Charles J. Maddox. *Real Estate Atlas of the Part of Montgomery County, MD, Adjacent to the District of Columbia*. Rockville, MD, 1917.

Hopkins, G. M. [1879] 1975. *Atlas of Montgomery County, Maryland, 1879*. Philadelphia: G.M. Hopkins. Rockville, MD: Montgomery County Historical Society.

Maryland – National Capital Park and Planning Commission (M-NCPPC). 1996. *Four Corners Master Plan*. Silver Spring, MD: M-NCPPC.

Maryland – National Capital Park and Planning Commission (M-NCPPC). 1996. Four Corners Master Plan. Silver Spring, MD: M-CPPC

Real Estate Data, Inc. *Real Estate Atlas of Montgomery County, Maryland, Recorded Subdivision Maps, Sunset Terrace Subdivision Plats, 1947 and 1948*. Miami, FL: Real Estate Data, Inc.

Sechrist, Stephanie Ann. "Silver Spring, Maryland: Residential Development of a Washington Suburb, 1920-1955." M.A. thesis, George Washington University, 1994.

United States Geological Survey (USGS). 1917. *Washington and Vicinity Topographic Map*. Washington, D.C.: USGS.

------. 1944. *Washington and Vicinity Topographic Map*. Washington, D.C.: USGS.

------. 1956. *Kensington, MD Quadrangle Map*. Washington, D.C.: USGS.

------. 1965. *Kensington, MD Quadrangle Map*. Washington, D.C.: USGS.

CONTINUATION SHEET

MARYLAND HISTORICAL TRUST
STATE HISTORIC SITES INVENTORY FORM
RESOURCE NAME: North Hills of Sligo Park
SURVEY NO.: M:32-11
ADDRESS: Bounded by Granvill Drive, Colesville Road, and Brunett Avenue, Four Corners vicinity, Montgomery County

10. Geographical Data (Continued)

Montgomery County Tax Map JP342, JP343, Subdivision 78



CONTINUATION SHEET

MARYLAND HISTORICAL TRUST
STATE HISTORIC SITES INVENTORY FORM
RESOURCE NAME: North Hills of Sligo Park
SURVEY NO.: M:32-11
ADDRESS: Bounded by Granvill Drive, Colesville Road, and Brunett Avenue, Four Corners vicinity, Montgomery County

Maryland Comprehensive Historic Preservation Plan Data Sheet

Historic Context:

MARYLAND COMPREHENSIVE PRESERVATION DATA

Geographic Organization:

Piedmont

Chronological/Development Period Theme(s):

Modern Period A.D. 1930-Present

Prehistoric/Historic Period Theme(s):

Architecture, Landscape Architecture, and Community Planning

RESOURCE TYPE:

Category (see Section 3 of survey form):

District

Historic Environment (urban, suburban, village, or rural):

Suburban

Historic Function(s) and Use(s):

Private Residence

Known Design Source (write none if unknown):

None

Preparer:
KCI Technologies, Inc.
January 2000

M:32-11

Argyle Park Neighborhood M: 32-7
Kensington Quad

North Hills of Sligo Park M: 32-11



I-495/I-95 Capital Beltway Corridor Transportation Improvement Study

Property Name: North Hills of Sligo Park

MHT#: M: 32-11

Quad Name: Kensington, MD

1. M:32-1
2. North Hills of Sligo Park
3. Montgomery County, MD
4. Tim Tamburrino
5. December 1979
6. MD SHPO
7. View south on Brunette Avenue, View South
8. 1 of 27

1. M:32-11
2. North Hills of Sligo Park Neighborhood
3. Montgomery County MD
4. Tim Tamburino
5. December 1995
6. MD SHPO
7. 9600 block of Brunette Avenue (East side).
   View Northeast
8. 2 of 27

1 M:32-11

2 North Hills of Sligo Park

3 Montgomery County, MD

4. Tim Tamburrino

5 December 1995

6 MD SHPO

7 4400 Block of Brunette Avenue, West Side, looking Northwest

8 3 of 27

1. M:32-11
2. North Hills of Silver Park
3. Montgomery County MD
4. Tim Tamburrino
5. December 1994
6. MD SHPO
7. South side of Brunette Court, View Southwest
8. 4 of 27

1. M:32-11
2. North Hills of Silver Park
3. Montgomery County MD
4. Tim Tamburrino
5. December 1995
6. MD SHPO
7. North Side of Brunette Court, View Northwest
8. 5 of 27

1 M:32-11

2 North Hills of Sligo Park

3. Montgomery County MD

4 Tim Tamburrino

5. December 1999

6. MD SHPO

7. St Andrews Way of Sutherland Road

View North

8. 6 of 27

1. M-32-11
2. North Hills of Silver Park
3. Montgomery County MD
4. Tim Tamborino
5. December 1997
6. MD SHPO
7. 9600 Block of Sutherland Avenue, View Northwest
8. 7 of 27

1 M:32-11

2. North Hills of Sligo Park

3. Montgomery County MD

4 Tim Tamburrino

5 December 1999

6 MD SHPO

7. 9600 Block of Sutherland Avenue, View Southwest

8. 8 of 27

1. M:32-11
2. North Hills of Sligo Park
3. Montgomery County, MD
4. Tim Tamburrino
5. December 1990
6. MD SHPO
7. 9600 Block of Thornhill Road (East side), View East
8. 9 of 27

1. M:32-11
2. North Hills of Sligo Park
3. Montgomery County MD
4. Tim Tamburrino
5. December 1999
6. MD SHPO
7. 9500 block of Bruce Drive (west side), View Northwest
8. 10 of 27

1. M:32-11
2. NORTH HILLS OF SLIGO PARK
3. MONTGOMERY COUNTY, MD
4. TIM TAMBURRINO
5. DECEMBER 1999
6. MD SHPO
7. 9500 BLOCK OF BRUCE DRIVE (EAST SIDE), VIEW NORTH EAST
8. 11 OF 27

1 M:32-11

2 North 4's of Sligo Park

3 Montgomery County MD

4 Tim Tamburrino

5 Dec 1997

6 MUSHPO

7 9400 Block of Thornhill Road (East Side),

View Northeast

8 12 of 27

M:32-11

2. North Hills of Sligo Park

3. Montgomery County, MD

4. Tim Tamburrino

5. December 1999

6. MD SHPO

7. 9500 Block of Thornhill Road (East side), View Northeast

8. 13 of 27

1. M: 32-11
2. NORTH HILLS OF SLIGO PARK
3. MONTGOMERY COUNTY, MD
4. TIM TAMBURRINO
5. DECEMBER 1999
6. MD SHPO
7. VIEW SOUTH ON THORNHILL ROAD. VIEW SOUTH
8. 14 OF 27

1. M:32-11
2. North Hills of Sligo Park
3. Montgomery County MD
4. Tim Tamburrino
5. December 1999
6. MD SHPO
7. 9500 Block of Bruce Drive, Potomac, MD 20854
8. 15 of 27

1 M: 32-11

2 North Hills of Sligo Park

3. Montgomery County, MD

4 Tim Tamburrino

5 December 1997

6 MD SHPO

7 9400 Block of Thornhill Road (West Side) View North West

8 16 of 27

M:32-11

2 North Hills of Sligo Park

3 Montgomery County MD

4 Tim Tamburrino

5 December 1989

6 NO SAPO

7 9400 Block of Colesville Road West Side

Nacho Southwest

8 17 of 27

1 M:32-11

2 [illegible] Hills of Sligo Park

3 Montgomery County MD

4 Tim Tamburrino

5 [illegible]

6 MD SHPO

7 9300 Block of Colesville [illegible]

8 18 of 27

1. M 32-11

2. NORTH H[illegible] [illegible] [illegible] [illegible]

3. M[illegible]

[illegible]

5. DECEMBER [illegible]

6. MD [illegible]

7. 9600 BLOCK [illegible] [illegible] AVENUE (WEST SIDE), VIEW NORTHWEST

8. 19 OF 27

1. M:32-11
2. North Hills of Sligo Park
3. Montgomery County, (MD)
4. Tim Tamburrino
5. December 1999
6. MD SHPO
7. 9500 block of St. Andrews Way (south side), view southwest
8. 20 of 27

1 of 22-11

2 North Hills of Seibo Park

3 Montgomery County, MD

4. Tim Tamburrino

5 December 1999

6 MD SHPO

7 605 St Andrews Lane, Louis L. Brunette House.
Front Elevation, View Southwest

8. 21 of 27

1. M:32-11
2. North Hills of Sligo Park
3. Montgomery County, MD
4. Tim Tamburrino
5. December 1999
6. MD SHPO
7. 605 St. Andrews Lane, Louis L Brunette House, Front Elevation, View Southeast
8. 22 of 27

1. MP 32-11
2. NORTH HILLS OF SEIBO PARK
3. MONTGOMERY COUNTY, MD
4. TIM TAMBURRINO
5. DECEMBER 1999
6. MD SHPO
7. 605 ST ANDREWS LANE, LOUIS L. BRUNETTE HOUSE, REAR ELEVATION, VIEW NORTHEAST
8. 23 OF 27

1. M:32-11
2. North Hills of Sligo Park
3. Montgomery County, MD
4. Tim Tamburrino
5. December 1999
6. MD SHPO
7. 9019 Brunette Avenue, View East
8. 24 of 27

1. M: 32-11
2. North Hills of Sligo Park
3. Montgomery County, MD
4. Tim Tamburello
5. December 1994
6. MD SHPO
7. 9602 Sutherland Way, View Northwest
8. 25 of 27

1. M:32-11
2. North Hills of Sligo Park
3. Montgomery County, MD
4. TM Tallbunking
5. December 1994
6. MD SHPO
7. 9518 Bruce Drive, Vicinity
8. 26 of 27

1 M:32-11

2 North Vicinity of Sligo Park

3 Montgomery County, MD

4 Tim Tamburrino

5 December 1990

6 MD SHPO

7 9404 Thornhill Road View East

8 27 of 27