

**SECTION 2.—Length 5400 feet.**

Cubic yards.		Haul.		Price Cts	Cost.	Total cost.
40697		5	Earth and loose rock,	21	8,516 37	
49269		6	do do	22	10,839 18	
						19,385 55
			Puddle trenches of puddling of bottom 2700 ft.	200		5,400 00
			Paving of inside slope—both sides, 5400 ft.	96		5,184 00
			Metalling of horse path, 5400 ft.	50		2,700 00
<b>Masonry.</b>						
<b>Depth of Emb.</b>	<b>Open'g</b>					
5	4				892 50	
17	40				18,600 00	
11	6				2,219 25	
4	4				870 00	
10	6				1,567 50	
						24,149 25
			Road bridge at Clopper's Mill, and altering road,			7,000 00
			River walling and altering course of river,			500 00
			5 Locks at \$12,500 each,			62,500 00
			<b>Total for Section 2.</b>			<b>\$126,818 80</b>