

SECTION 3.—Length 6100 feet.

Cubic yards.	Haul.		Price. Cts.	Cost.	Total cost.
27602	5	Earth and rock,	21	\$5,792 42	
18535	7	do do	23	4,363 05	
108726	8	do do	24	26,094 21	
4153	7	Rock,	100	4,153 00	
					40,306 71
		Puddle trenches and puddling of bottom, 3050 ft.	200		6,110 00
		Paving of inside slopes—both sides, 6100 ft.	96		5,876 00
		Metalling of horse path, 6100 ft.	50		3,050 00
<b>Masonry.</b>					
<b>Depth of Emb</b>	<b>Open'g</b>				
4	4			870 00	
16	6			2,462 25	
6	4			905 00	
13	10			4,429 50	
13	6			2,316 00	
					10,932 75
		2 Locks at 12500.			25,000 00
<b>Total for Section 3.</b>					<b>\$91,325 46</b>