

SECTION 5 — 5200 feet (first section of Summit pass)

Cubic yards.		Haul.		Price, (^{ts}).	Cost's.	Total costs.
26285		5	Earth and loose rock,	21	5,519 85	
102306		8	Earth,	22	22,573 32	
			Puddle trenches and puddling of bottom,	2600 ft.	200	23,093 17
			Paving of inside slopes, both sides,	5200 ft.	90	5,200 00
			Metalling of horse path	5200 ft.	50	4,681 00
Masonry.						2,600 00
Depth	Open'g					
of Emb.						
9	4				932 50	
7	6				1,497 75	
15	10				4,575 00	
11	6				2,219 25	
			7 Locks, at \$12,500,			9,274 50
			Shew. Bridge for Fred'k. turnpike, & alteration of road.			87,500 00
						6,500 00
Total for section 5						143,847 17