

SECTION 6.--3100 feet.

Cubic yards.		Haul.		Price, Cts.	Costs.	Total costs.
18583		5	Earth and loose Rock,	21	\$3,903 43	
60803		10	Earth,	23	12,984 69	
20523		6	do	21	4,309 83	
			Puddle trenches and puddling of bottom, 1550 ft.	200		22,198 95
			Paving of inside slopes, both sides, 3100 ft	96		3,100 00
			Metalling of horse path, 3100 ft.	50		2,976 00
						1,550 00
Masonry.						
Depth of Emb.	Open's					
28	15				10,380 00	
6	4				915 00	
12	6				2,268 00	
			3 Locks, of \$12,500,			13,563 00
						37,500 00
						80,885 95
			Total for section 6,			