

SECTION 7.—22500 feet.

Cubic yards.	Haul.		Price, Cts.	Costs.	Total costs.
145823	40	Earth and loose Rock,	44	\$61,162 12	
207285	40	Rock,	158	327,510 30	
195 93	45	Earth and loose Rock,	47	91,693 71	
293843	40	Rock,	160	473,348 80	
					\$956,714 93
		Tunnel 8400 feet, at 337.40 per. cu. feet,			2,834,160 00
		Puddle trenches and puddling of bottom, 3000 ft.	200		6,000 00
		Water channels on either side of the tunnel, deep cuts, in lieu of the present natural channel, which would be destroyed by the canal, 10600 ft. at	300		31,800 00
		Pav'g. inside slopes of can. except in rock cut'g. 6600 ft.	95		6,336 00
		Met'ng of horse path, 14100 ft	50		7,050 00
				4,336 50	
				1,447 50	
				2,226 00	
					8,010 00
		Road Bridge, and Emb. of Road,			5,800 00
					3,855,870 93
					<u>3,855,870 93</u>

Masonry.

Depth of Emb	Open'g
12	10
6	8
10	8

Total for section 7,