

SECTION 8.—Length 6000 feet.

Cubic yards.		Haul.		Price. Cts.	Cost	Total cost.
61887		5	Earth and loose rock,	21	\$12,996 27	
136452		10	do do	20	27,290 40	
17614		8	Rock,	100	17,614 00	
						57,800 67
			Puddle trenches and puddling of bottom, 2200 ft.	200		4 400 00
			Paving of inside slopes—both sides, 5200 fr.	96		4,992 00
			Metalling of horse path, 5200 ft.	50		2,600 00
Masonry.						
Depth of Emb	Open'g					
35	15				15,048 09	
13	10				4,429 50	
13	4				1,458 00	
12	4				1,428 00	
12	6				2,268 00	
						24,631 50
			Aqueduct across valley of Rock Creek,			226,184 00
			Total for Section 8.			\$320,709 17

16