

SECTION 12.—Length 5700 feet.

Cubic yards		Haul		P. cr, Crs.	Costs	Total costs.
9996	5	Earth and loose Rock,		21	\$2,099 16	
22105	6	Earth,		21	4,705 05	
149534	8	do		22	26,297 48	
977	7	Rock,		190	977 00	
						\$31,076 69
Puddle trenches and puddling of bottom,			2850 ft.	200		5,700 00
Paving of inside slopes, both sides,			5700 ft.	96		5,472 00
Metalling of horse path,			5700 ft.	50		2,850 00
Masonry.						
Depth of Eml	Open g					
27	6				2,937 00	
25	6				2,799 50	
28	10				7,803 50	
10	6				1,568 50	
15	6				2,414 50	
						17,183 00
Road bridge—Green's bridg road,						5,800 00
8 Locks, at \$12500,						100 000 00
Total for section 12,						<u>171,081 69</u>

036