

## FEEDERS OF SUMMIT LEVEL.

No. 1. SENECA RIVER FEEDER.—SECTION 1.—Length 7700 feet.

| Cub. yards.                 | Haul.  |  | Price.<br>Cts. | Cost.     | Total cost.         |
|-----------------------------|--------|--|----------------|-----------|---------------------|
| 1793                        | 5      | Earth and loose rock,                            | 16             | \$256 85  |                     |
| 20609                       | 7      | do do  | 20             | 4,121 80  |                     |
| 33595                       | 8      | do do  | 23             | 7,726 85  |                     |
| 2059                        | 7      | Rock,  | 100            | 2,059 00  |                     |
| 24500                       | 24     | Earth and some loose rock,                       | 35             | 12,075 00 |                     |
| 34000                       | 28     | Rock,  | 130            | 41,020 00 |                     |
| 11088                       | 18     | Rock,  | 120            | 13,305 60 |                     |
|                             |        | Puddle trenches and puddling of bottom, 3670 ft. | 80             |           | \$3,775 13          |
|                             |        | Paving of inside slopes—both sides, 7700 ft.     | 50             |           | 2,920 00            |
|                             |        |  |                |           | 3,850 00            |
| Masonry.                    |        |  |                |           |                     |
| Depth<br>of Emb.            | Open'g |  |                |           |                     |
| 28                          | 20     |  |                | 10,527 00 |                     |
| 20                          | 6      |  |                | 1,460 00  |                     |
| 20                          | 6      |  |                | 1,430 00  |                     |
| 15                          | 6      |  |                | 1,220 00  |                     |
| 5                           | 4      |  |                | 450 00    |                     |
| 40                          | 15     |  |                | 8,230 00  |                     |
|                             |        |  |                |           | 23,397 50           |
| <b>Total for Section 1,</b> |        |  |                |           | <b>\$112,942 13</b> |