

SECTION 3.—Length 6000 feet.

Cubic yards.		Haul.		Price. Cts.	Cost.	Total cost.
6308		5	Earth and some loose rock,	16	\$1,009 28	
20128		7	do do	20	4,025 60	
30203		8	do do	22	6,644 66	
4301		7	Rock,	100	4,301 00	
						15,980 54
			Puddle trenches and puddling of bottom, 3000 ft.	80		2,400 00
			Paving of inside slopes—both sides, 6000 ft.	50		3,000 00
<b>Masonry.</b>						
Depth of Emb	Open'g					
17	6				1,210 00	
38	15				8,800 00	
8	6				706 00	
7	4				430 00	
22	6				1,450 00	
10	6				970 00	
						13,566 00
			Road from Dorsey's saw-mill,			600 00
			<b>Total for Section 3.</b>			<b>\$35,546 54</b>