

GOSHEN BRANCH FEEDER, No. 2.—SECTION 6.—Length 3900 feet.

Cubic yards.		Haul.		Price, C s.	Costs.	Total cost's.
9256		5	Earth and some loose Rock,	16	\$1,480 96	
14701		8	do	18	2,645 72	
967		7	Rock,	100	967 00	
						\$5,094 68
			Puddle trenches and puddling of bottom, 1950 ft.	80		1,560 00
			Paving of inside slopes, both sides, 3900 ft.	50		1,950 00
Masonry.						
Dept of Emb	Open'g					
18	6				1,408 00	
8	6				606 00	
6	4				410 00	
8	4				420 00	
						2,844 00
Total for section 6,						11,415 68

69