

No. 3, HAWLING'S RIVER FEEDER.—SECTION 7.—Length 5800 feet.

Cubic yards.		Haul.		Price, Cts.	Costs.	Total costs.
497		5	Earth and some loose Rock,	16	\$79 52	
86480		7	do do	20	7,296 00	
26239		12	do do	24	8,697 36	
6226		5	Rock,	100	6,226 00	
						\$22,293 83
			Puddle trenches and puddling of bottom, 2900 ft.	80		2,320 00
			Paving of inside slopes, both sides, 5800 ft.	50		2,900 00
Masonry.						
Depth of Emt	Open'g					
26	10					4,030 00
12	6					1,067 00
28	6					1,750 00
20	6					1,355 00
						8 202 00
						101,364 00
						600 00
Total for section 7.						140,684 88