

SECTION 8.—Length 5900 feet.

Cubic yards.		Haul.		Price, Cts.	Costs	Total costs.
429		5	Earth and some loose Rock,	16	\$68 64	
89919		7	do	20	17,983 80	
454		5	Rock,	100	454 00	
			Puddle trenches and puddling of bottom, 2950 ft.	80		\$18,506 44
			Paving of inside slopes, both sides, 5900 ft.	50		2,360 00
						2,950 00
Masonry.						
Depth of Emb	Open'g					
28	10				3,862 00	
24	6				1,550 00	
20	6				1,455 00	
26	10				4,030 00	
15	6				1,220 00	
22	6				1,450 00	
8	4				450 00	
						14,017 00
Total for section 8,						<u>4 37,833 44</u>