

No. 4.—PATUXENT RIVER FEEDER.—SECTION 10.—Length 7800 feet.

Cubic yards.		Haul.		Price Cts.	Cost.	Total cost.
10915	17	Earth and some loose rock,		23	\$3 064 60	
2046	15	do do		26	531 06	
10971	20	Rock,		120	13,165 26	
20456	24	Earth and loose rock,		35	7,159 60	
26705	10	Rock,		120	29,376 60	
						52 227 95
Tunnelling 2200 feet, (not arched) \$28,				80		6 500 00
Puddle trenches and puddling of bottom, 1800 ft				80		1,440 00
Paving of inside slopes except in rock cut, 3500 ft.				50		1,750 00
Water channel along top of slopes in the deep cut 3200 ft.				250		8,000 00
Masonry.						
Depth of Ent	Clear open'g					
8	6					706 00
12	6					1,067 00
10	6					870 00
						2,643 00
Total for Section 10,						\$125,730 96

33