

SECTION 11.—Length 4600 feet.

Cubic yards.		Haul.		Price. Cts.	Cost.	Total cost.
1364	5	Earth and loose rock,		16	218 24	
13384	7	do do		20	2,676 40	
20438	10	do do		23	4,700 74	
2153	6	Rock,		100	2,153 00	
						9,748 38
		Puddle trenches and puddling of bottom,	2300 ft.	80		1,840 00
		Paving of inside slope	4600 ft.	50		2,300 00
<b>Masonry.</b>						
Depth of Emb	Open'g					
25	10				3,612 00	
10	4				445 00	
25	6				1,600 00	
35	15				7,030 00	
						12,687 00
<b>Total for Section 11,</b>						<b>\$26,575 38</b>