

**SECTION 12.—Length 4700 feet.**

Cubic yards.	Haul.		Price. Cts.	Cost.	Total cost.
1200	5	Earth and some loose rock,	16	192 00	
20690	7	do do	20	4,138 00	
1907	6	Rock,	100	1,907 00	6,237 00
		Puddle trenches and puddling of bottom, 2350 ft.	80		11,880 00
		Paving of inside slopes, 4700 ft.	50		2,350 00
<b>Masonry.</b>					
<b>Depth</b> of Emb	<b>Open'g</b>				
8	4			420 00	
6	4			400 00	
24	6			1,650 00	
20	6			1,455 00	
14	6			1,205 00	
8	4			420 00	
4	4			320 00	
					5,870 00
<b>Total for Section 12.</b>					<b>\$16,337 00</b>