

No. 6, BIG BRANCH FEEDER.—SECTION 15.—Length 6100 feet

Cubic yards.		Haul.		Price, C. s.	Costs.	Total costs.
10615	5	Earth and some loose Rock,		16	\$ 1,698 40	
2658	6	do		19	505 02	
26804	8	do		20	5,360 80	
26649	12	do		22	5,862 78	
5190	5	Rock,		100	5,190 00	
		Puddle trenches and puddling of bottom,	3050 ft.	80		\$18,617 00
		Paving of inside slopes,	6100 ft.	50		2,440 00
						3,050 00
Masonry.						
Depth of Emb	Open'g					
45	30				16,480 00	
30	6				1,840 00	
18	6				1,408 00	
18	6				1,404 00	
14	4				520 00	
17	6				1,310 00	
10	4				420 00	
						23,382 00
Total for section 15,						47,489 00