

No. 5. DAM OF HAWLINGS RIVER RESERVOIR.

Cubic yards.		Price, Cts.	Costs.	Total costs.
32750	Gravel removed from foundation,	18	\$5,895 00	
228229	Embankment,	24	54,794 00	
64724	Puddling of puddle dyke,	40	25,889 00	
2690	Soiling of lower slope,	25	134 50	
Perches.				\$86,713 46
7074	Paving on upper slope,	200		14,148 00
11137	Masonry of culvert of feeder,	800		88,096 00
	Waste wier and waste lead,			6,000 00
	Guage of culvert—guage rods—sheath for do. and house on top of embankment,			5,000 00
	Pumping apparatus,			4,000 00
				<u>203,967 46</u>

45