

EMBANKMENT OR DAMS OF RESERVOIRS FOR COLLECTION OF SECONDARY WATER.

DAM OF SECONDARY RESERVOIRS ON SENECA.

Cubic yards.		Price. Cts.	Cost.	Total cost.
78726	Gravel removed from foundation,	18	14 170 68	
181459	Embankment,	24	43,550 06	
79292	Puddling of puddle dyke,	40	31,716 80	
2720	Soiling of lower slope,	25	680 00	
Perches.				90,117 54
6802	Paving on upper slope,	200		13,604 00
7837	Masonry of culvert of feeder,	800		62,695 00
	Waste weir and waste lead,			6,000 00
	Guage of culvert—guage rods—sheath per do. and house on top of embankment,			5,000 00
	Pumping apparatus,			4,000 00
				<u>\$181,417 54</u>