

1987

S-233

FANNIE L. DAUGHERTY (skipjack)
Wenona, Maryland

FANNIE L. DAUGHERTY is a 41.3' long two-sail bateau, or V-bottomed deadrise type of centerboard sloop, commonly referred to as a skipjack. She has a beam of 8', a depth of 3.6', and a gross registered tonnage of 8. She carries a typical skipjack rig of jib-headed mainsail and a single large jib with a club on its foot. Built in 1904 in Crisfield, Maryland following traditional Bay design and construction methods, FANNIE L. DAUGHERTY is significant as being one of the 35 surviving traditional Chesapeake Bay skipjacks and a member of the last commercial sailing fleet in the United States. FANNIE L. DAUGHERTY is of special interest as being one of the older skipjacks in the fleet and one of the 19 surviving working skipjacks built previous to 1912.

Survey No. S-233

Magi No.

DOE yes no

Maryland Historical Trust State Historic Sites Inventory Form

CHESAPEAKE BAY SKIPJACK FLEET THEMATIC GROUP

1. Name (indicate preferred name)

historic FANNIE L. DAUGHERTY

and/or common skipjack

2. Location

street & number lower thorofare n/a not for publication

city, town Wenona n/a vicinity of congressional district First

state Maryland 024 county Somerset 039

3. Classification

Category	Ownership	Status	Present Use	
<input type="checkbox"/> district	<input type="checkbox"/> public	<input checked="" type="checkbox"/> occupied	<input type="checkbox"/> agriculture	<input type="checkbox"/> museum
<input type="checkbox"/> bulding(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> unoccupied	<input checked="" type="checkbox"/> commercial	<input type="checkbox"/> park
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> work in progress	<input type="checkbox"/> educational	<input type="checkbox"/> private residence
<input type="checkbox"/> site	Public Acquisition	Accessible	<input type="checkbox"/> entertainment	<input type="checkbox"/> religious
<input checked="" type="checkbox"/> object	<input type="checkbox"/> in process	<input checked="" type="checkbox"/> yes: restricted	<input type="checkbox"/> government	<input type="checkbox"/> scientific
	<input type="checkbox"/> being considered	<input type="checkbox"/> yes: unrestricted	<input type="checkbox"/> industrial	<input checked="" type="checkbox"/> transportation
	<input checked="" type="checkbox"/> not applicable	<input type="checkbox"/> no	<input type="checkbox"/> military	<input type="checkbox"/> other:

4. Owner of Property (give names and mailing addresses of all owners)

name Captain Norman Benton

street & number telephone no.: 784-2668

city, town Wenona state and zip code Maryland 21870

5. Location of Legal Description

courthouse, registry of deeds, etc. n/a liber

street & number folio

city, town state

6. Representation in Existing Historical Surveys

title Survey of Surviving Traditional Chesapeake Bay Craft

date 1983-1984 federal state county local

depository for survey records Maryland Historical Trust, 21 State Circle

city, town Annapolis state MD 21401

7. Description

Survey No. S-233

Condition		Check one	Check one	
<input type="checkbox"/> excellent	<input type="checkbox"/> deteriorated	<input type="checkbox"/> unaltered	<input checked="" type="checkbox"/> original site	n/a
<input type="checkbox"/> good	<input type="checkbox"/> ruins	<input checked="" type="checkbox"/> altered	<input type="checkbox"/> moved	date of move _____
<input type="checkbox"/> fair	<input type="checkbox"/> unexposed			

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

This oyster dredgeboat is a 41.3-foot long, two-sail bateau, or V-bottom deadrise type of centerboard sloop, commonly referred to as a skipjack. She is built by cross-planked construction methods and has a beam of 8' and a depth of 3.6'. The vessel was built in 1904 in Crisfield, Maryland for the oyster dredge fleet. With a gross register tonnage of 8 tons, she carries a typical skipjack rig-- a jib-headed mainsail laced to the boom and carried on wood hoops at the mast, and a single large jib with a club on its foot. The vessel is painted white, with dark tan trim on the caprail.

In shape, the vessel has a longhead bow with a straight, almost plumb, stem. Her transom stern is low and sharply raking with a shallow "tuck" at the waterline. The hull is relatively straight-sided, with an overlapped sheer log. The rudder is carried well inboard and a "jig" for the pushboat is centered on the transom.

The vessel is flush-decked with a main cabin with an added "doghouse" with three windows. She is fitted out for oystering with winders, a box over the winders, dredges, etc. There is a pushboat suspended on davits over the stern.

The single mast is set up with double shrouds and deadeyes. The long boom is jawed to the mast. There is an octagonal bowsprit with wood "runners" along its sides; it is set up with double chain bowsprit shrouds and bobstays.

Decorations include carved and painted trailboards with the name FANNIE L. DAUGHERTY in red on a green background, with a shield and arrows motif also in red and green.

8. Significance

Survey No. S-233

Period	Areas of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input type="checkbox"/> community planning	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600-1699	<input type="checkbox"/> architecture	<input type="checkbox"/> education	<input type="checkbox"/> military	<input type="checkbox"/> social/
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	<input type="checkbox"/> humanitarian
<input type="checkbox"/> 1800-1899	<input checked="" type="checkbox"/> commerce	<input type="checkbox"/> exploration/settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> theater
<input checked="" type="checkbox"/> 1900-	<input type="checkbox"/> communications	<input type="checkbox"/> industry	<input type="checkbox"/> politics/government	<input checked="" type="checkbox"/> transportation
		<input type="checkbox"/> invention		<input type="checkbox"/> other (specify)

Specific dates	1904	Builder/Architect	Unknown
check: Applicable Criteria:	<input checked="" type="checkbox"/> A	<input type="checkbox"/> B	<input checked="" type="checkbox"/> C <input type="checkbox"/> D
and/or			
Applicable Exception:	<input type="checkbox"/> A	<input type="checkbox"/> B	<input type="checkbox"/> C <input type="checkbox"/> D <input type="checkbox"/> E <input type="checkbox"/> F <input type="checkbox"/> G <input checked="" type="checkbox"/> none
Level of Significance:	<input checked="" type="checkbox"/> national	<input type="checkbox"/> state	<input type="checkbox"/> local

Prepare both a summary paragraph of significance and a general statement of history and support.

This vessel is significant as being one of the 35 surviving traditional Chesapeake Bay skipjacks and a member of the last commercial sailing fleet in the United States. Out of a fleet of hundreds of skipjacks that worked Bay waters in the early years of this century, today only this small number remain to carry on the tradition of working sail.

The skipjack evolved as a distinct type of Bay vessel in the 1890's as a cheaper-to-construct alternative to the earlier bugeyes and other traditional framed craft, in a period when shipbuilding costs were rising and the oyster catch was diminishing. The type was devised by enlarging (to 25 to 60 feet) the hull of the ordinary, unframed, square-sterned Bay crabbing skiff, and giving it a deadrise bottom, a-deck, a cabin, and a sloop rig. The result--with its unframed, hard chine, cross-planked, V-bottom--proved inexpensive to build, easy to repair, and could be constructed by a competent house carpenter. Skipjacks were specifically designed as oyster dredge boats, with wide beams and low freeboard lending stability and providing a large working space on deck. The single masted rig, with sharp-headed mainsail and large jib, was easy to handle, powerful in light winds, and handy in coming about quickly for another pass over the oyster beds.

The Maryland oyster season begins November 1 and ends March 15. Skipjacks must dredge under sail on all days except Mondays and Tuesdays, when they are allowed to use their motorized pushboat for dredging. The pushboat, normally carried on davits at the stern, is lowered into the water and literally "pushes" the skipjack along from behind, the nose of the pushboat resting against a "jig" on the stern of the skipjack. The pushboat can also legally be used to get the skipjack to and from the oyster beds each day. Each skipjack's crew is made up of the captain, who is often also the owner, and five crew members.

FANNIE L. DAUGHERTY is of interest as being one of the older skipjacks still dredging in the Chesapeake fleet. She was built in 1904 in Crisfield, Maryland following traditional Bay-area design and construction methods. She has worked in the oyster-dredging fleet since her building and is presently based at Deal Island. The vessel is one of the 21 surviving working skipjacks to have been built previous to 1912, although, like the other members of the fleet, she has been much repaired over the years. A recent addition is a "doghouse" added to the top of the cabin to increase the comfort of the skipper. The lines of the FANNIE L. DAUGHERTY were used in 1955 as the basis for the skipjack H.M. KRENTZ, built in Harryhogan, Virginia.

9. Major Bibliographical References

Survey No. S-233

See Thematic Group nomination cover form, Continuation Sheets No. 8-13.

10. Geographical Data

Acreage of nominated property less than one acre
Quadrangle name Deal Island, MD Quadrangle scale 1:24000

UTM References do NOT complete UTM references

A	18	416870	4220240	B			
	Zone	Easting	Northing		Zone	Easting	Northing
C				D			
E				F			
G				H			

Verbal boundary description and justification

This working vessel is usually docked at the location indicated in Item 2. Historic boundaries are coterminous with the hull.

List all states and counties for properties overlapping state or county boundaries

state	n/a	code	county	code
state		code	county	code

11. Form Prepared By

name/title	Anne Witty/ M. E. Hayward			
organization	Radcliffe Maritime Museum		date	May, 1984
street & number	201 West Monument Street		telephone	(301) 685-3750
city or town	Baltimore		state	Maryland 21201

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust
Shaw House
21 State Circle
Annapolis, Maryland 21401
(301) 269-2438

Maryland Historical Trust State Historic Sites Inventory Form

Survey No. S-233

Magi No. 2002335733

DOE ___yes ___no

1. Name (indicate preferred name)

historic FANNIE L. DAUGHERTY

and/or common skipjack

2. Location

street & number _____ not for publication

city, town Wenona _____ vicinity of _____ congressional district

state Maryland _____ county Somerset

3. Classification

Category	Ownership	Status	Present Use	
<input type="checkbox"/> district	<input type="checkbox"/> public	<input checked="" type="checkbox"/> occupied	<input type="checkbox"/> agriculture	<input type="checkbox"/> museum
<input type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> unoccupied	<input checked="" type="checkbox"/> commercial	<input type="checkbox"/> park
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> work in progress	<input type="checkbox"/> educational	<input type="checkbox"/> private residence
<input type="checkbox"/> site	Public Acquisition	Accessible	<input type="checkbox"/> entertainment	<input type="checkbox"/> religious
<input checked="" type="checkbox"/> object	<input type="checkbox"/> in process	<input checked="" type="checkbox"/> yes: restricted	<input type="checkbox"/> government	<input type="checkbox"/> scientific
	<input type="checkbox"/> being considered	<input type="checkbox"/> yes: unrestricted	<input type="checkbox"/> industrial	<input checked="" type="checkbox"/> transportation
	<input checked="" type="checkbox"/> not applicable	<input type="checkbox"/> no	<input type="checkbox"/> military	<input type="checkbox"/> other:

4. Owner of Property (give names and mailing addresses of all owners)

name Captain Norman Benton

street & number _____ telephone no.: 784-2668

city, town Wenona _____ state and zip code Maryland 21870

5. Location of Legal Description

courthouse, registry of deeds, etc. _____ liber

street & number _____ folio

city, town _____ state

6. Representation in Existing Historical Surveys

title _____

date _____ federal ___ state ___ county ___ local

pository for survey records _____

city, town _____ state

7. Description

Survey No. S-233

Condition		Check one	Check one	
<input type="checkbox"/> excellent	<input type="checkbox"/> deteriorated	<input type="checkbox"/> unaltered	<input type="checkbox"/> original site	
<input checked="" type="checkbox"/> good	<input type="checkbox"/> ruins	<input checked="" type="checkbox"/> altered	<input type="checkbox"/> moved	date of move _____
<input type="checkbox"/> fair	<input type="checkbox"/> unexposed			

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

This oyster dredgeboat is a 41.3-foot long, two-sail bateau, or V-bottom deadrise type of centerboard sloop, commonly referred to as a skipjack. She is built by cross-planked construction methods and has a beam of 8' and a depth of 3.6'. The vessel was built in 1904 in Crisfield, Maryland for the oyster dredge fleet. With a gross register tonnage of 8 tons, she carries a typical skipjack rig-- a jib-headed mainsail laced to the boom and carried on wood hoops at the mast, and a single large jib with a club on its foot. The vessel is painted white, with dark tan trim on the caprail.

In shape, the vessel has a longhead bow with a straight, almost plumb, stem. Her transom stern is low and sharply raking with a shallow "tuck" at the waterline. The hull is relatively straight-sided, with an overlapped sheer log. The rudder is carried well inboard and a "jig" for the pushboat is centered on the transom.

The vessel is flush-decked with a main cabin with an added "doghouse" with three windows. She is fitted out for oystering with winders, a box over the winders, dredges, etc. There is a pushboat suspended on davits over the stern.

The single mast is set up with double shrouds and deadeyes. The long boom is jawed to the mast. There is an octagonal bowsprit with wood "runners" along its sides; it is set up with double chain bowsprit shrouds and bobstays.

Decorations include carved and painted trailboards with the name FANNIE L. DAUGHERTY in red on a green background, with a shield and arrows motif also in red and green.

8. Significance

Period	Areas of Significance—Check and justify below			
___ prehistoric	___ archeology-prehistoric	___ community planning	___ landscape architecture	___ religion
___ 1400-1499	___ archeology-historic	___ conservation	___ law	___ science
___ 1500-1599	___ agriculture	___ economics	___ literature	___ sculpture
___ 1600-1699	___ architecture	___ education	___ military	___ social/
___ 1700-1799	___ art	___ engineering	___ music	___ humanitarian
___ 1800-1899	<input checked="" type="checkbox"/> commerce	___ exploration/settlement	___ philosophy	___ theater
<input checked="" type="checkbox"/> 1900-	___ communications	___ industry	___ politics/government	<input checked="" type="checkbox"/> transportation
		___ invention		___ other (specify)

Specific dates 1904 **Builder/Architect** Unknown

check: Applicable Criteria: A B C D
and/or
Applicable Exception: A B C D E F G

Level of Significance: national state local

Prepare both a summary paragraph of significance and a general statement of history and support.

This vessel is significant as being one of the 36 surviving traditional Chesapeake Bay skipjacks and a member of the last commercial sailing fleet in the United States. Out of a fleet of hundreds of skipjacks that worked Bay waters in the early years of this century, today only this small number remain to carry on the tradition of working sail.

The skipjack evolved as a distinct type of Bay vessel in the 1890's as a cheaper-to-construct alternative to the earlier bugeyes and other traditional framed craft, in a period when shipbuilding costs were rising and the oyster catch was diminishing. The type was devised by enlarging (to 25 to 60 feet) the hull of the ordinary, unframed, square-sterned Bay crabbing skiff, and giving it a deadrise bottom, a-deck, a cabin, and a sloop rig. The result--with its unframed, hard chine, cross-planked, V-bottom--proved inexpensive to build, easy to repair, and could be constructed by a competent house carpenter. Skipjacks were specifically designed as oyster dredge boats, with wide beams and low freeboard lending stability and providing a large working space on deck. The single masted rig, with sharp-headed mainsail and large jib, was easy to handle, powerful in light winds, and handy in coming about quickly for another pass over the oyster beds.

The Maryland oyster season begins November 1 and ends March 15. Skipjacks must dredge under sail on all days except Mondays and Tuesdays, when they are allowed to use their motorized pushboat for dredging. The pushboat, normally carried on davits at the stern, is lowered into the water and literally "pushes" the skipjack along from behind, the nose of the pushboat resting against a "jig" on the stern of the skipjack. The pushboat can also legally be used to get the skipjack to and from the oyster beds each day. Each skipjack's crew is made up of the captain, who is often also the owner, and five crew members.

FANNIE L. DAUGHERTY is of interest as being one of the older skipjacks still dredging in the Chesapeake fleet. She was built in 1904 in Crisfield, Maryland following traditional Bay-area design and construction methods. She has worked in the oyster-dredging fleet since her building and is presently based at Deal Island. The vessel is one of the 19 surviving working skipjacks to have been built previous to 1912, although, like the other members of the fleet, she has been much repaired over the years. A recent addition is a "doghouse" added to the top of the cabin to increase the comfort of the skipper. The lines of the FANNIE L. DAUGHERTY were used in 1955 as the basis for the skipjack M. KRENTZ, built in Harryhogan, Virginia.

9. Major Bibliographical References

Survey No. S-233

Howard I. Chapelle, American Small Sailing Craft (New York: W.W. Norton, 1951)

H.I. Chapelle, Chesapeake Bay Skipjacks (St. Michaels, Md: CBMM, n.d.)

10. Geographical Data

Acreeage of nominated property _____

Quadrangle name _____

Quadrangle scale _____

UTM References do NOT complete UTM references

A

--	--	--	--	--	--	--	--	--	--	--	--

Zone Easting Northing

B

--	--	--	--	--	--	--	--	--	--	--	--

Zone Easting Northing

C

--	--	--	--	--	--	--	--	--	--	--	--

D

--	--	--	--	--	--	--	--	--	--	--	--

E

--	--	--	--	--	--	--	--	--	--	--	--

F

--	--	--	--	--	--	--	--	--	--	--	--

G

--	--	--	--	--	--	--	--	--	--	--	--

H

--	--	--	--	--	--	--	--	--	--	--	--

Verbal boundary description and justification

List all states and counties for properties overlapping state or county boundaries

state	code	county	code

state	code	county	code

11. Form Prepared By

name/title Anne Witty/ M.E. Hayward

organization Maryland Historical Society date 5/84

street & number 201 W. Monument St. telephone 685-3750


city or town Baltimore state Maryland 21201

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust
Shaw House
21 State Circle
Annapolis, Maryland 21401
(301) 269-2438

S-233



SKIPJACK

FORESTAY

JIBSTAY

JIB

MAINSAIL

TOPPING LIFT

LAZY JACKS

BOOM

BOBSTAYS

BOWSPRIT

CLUB

SHROUDS

DAVITS FOR PUSH BOAT

LOW HEAD

STEM LINE

LOG RAIL

PIPERAIL

PIPERAIL

PLUG RUDER



S-233

FANNIE L. DAUGHERTY
Wenona, Md

under sail
M.C. Wootton 11/83



S-233

FANNIE L. DAUGHERTY
Wenona, Md

port side
M.C. Wootton 10/83



S-233

FANNIE L. DAUGHERTY
Wenona, Md

stern
M.C. Wootton 10/83



S-233

FANNIE L. DAUGHERTY
Wenona, Md

bow

M.C. Wootton 10/83



303-12

S-233

FANNIE L. DAUGHERTY
Wenona, Md.

Bow - under sail
M.C. Wootton 10/83



303-11

S-233

FANNIE L. DAUGHERTY
Wenona, Md.

Port bow
M.C. Wootton 10/83



S-233

FANNIE L. DAUGHERTY
Wenona, Md

starboard side

M.C. Wootton 10/83